

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	23

STA. TO STA.
 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT
 * FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 ** D6 INTERSTATE RS,BR,M CAB 2008

LOCATION	EARTH EXCAVATION CU YD	EARTH EX ADJ FOR SHRINKAGE CU YD	EMBANKMENT CU YD	FURNISHED EXCAVATION CU YD
I-55				
STA 93+00 TO 111+00 (SE CORRECTION)	22	17	1,056	1,034
STA 118+00 TO 348+50 (CABLE BARRIER)			2,115	2,115
AROUND VARIOUS DRAINAGE STRUCTURES			40	40
I-72				
MEDIAN CROSSOVER STA 640+55			610	610
SOUTH GRAND INTERCHANGE				
STA 14+96 TO 23+50	152	114	2,090	1,938
TOTAL	174		5,911	5,737

EMERGENCY MEDIAN CROSSOVER AND APPROACH SHOULDER SCHEDULE

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	AGG BASE CSE TY A (TON)	HMA SURF REM 2" (SQ YD)	HMA BASE CSE 8" (SQ YD)	HMA SURF MIX C N 30 (TON)
I-72 MAINLINE						
STA 635+65 TO STA 637+20	155.0	1.0 TO 6.0			60.28	6.75
STA 637+20 TO STA 640+25	305.0	6.0			101.67	11.39
STA 640+55 (MEDIAN X-OVER)	56.0	30.0	51.96		228.13	25.55
STA 640+85 TO STA 643+90	305.0	6.0			101.67	11.39
STA 643+90 TO STA 645+45	155.0	6.0 TO 1.0			60.28	6.75
I-55 MAINLINE						
STA 15+55 (MEDIAN X-OVER)	25.0	30.0			91.64	10.26
STA 15+70 TO STA 16+07	37.0	1.0 TO 6.0			14.39	1.61
STA 16+07 TO STA 17+98	191.0	6.0			63.67	7.13
STA 17+98 TO STA 19+53	155.0	6.0 TO 1.0			60.28	6.75
STA 112+59 TO STA 114+14	155.0	1.0 TO 6.0			60.28	6.75
STA 114+14 TO STA 117+19	305.0	6.0			101.67	11.39
STA 117+45 (MEDIAN X-OVER)	34.0	30.0		142.11	37.45	20.11
STA 117+69 TO STA 120+74	305.0	6.0			101.67	11.39
STA 120+74 TO STA 122+29	155.0	6.0 TO 1.0			60.28	6.75
TOTAL			51.96	142.11	1,143.36	143.97

MATERIAL TRANSFER DEVICE

LOCATION	BINDER (TON)	SURFACE (TON)	TOTAL (TON)
I-72 MAINLINE	4,336.82	2,891.24	7,228.06
BL-55 MAINLINE	1,386.87	1,689.26	3,076.13
I-55 MAINLINE	25,374.60	16,916.36	42,290.96
6TH ST INTERCHANGE	2,535.22	2,015.54	4,550.76
STEVENSON DR INTERCHANGE	1,477.13	984.74	2,461.87
SOUTH GRAND INTERCHANGE	2,848.09	1,898.69	4,746.78
CLEAR LAKE INTERCHANGE	3,092.31	2,061.56	5,153.87
			69,508.43

PLOT DATE : Nov-19-2007 08:12:00AM
 FILE NAME : c:\projects\0652882\shsch.dgn
 PLOT SCALE : 1/8"=1'-0" / IN.
 USER NAME : laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY
 SCALE: DATE DRAWN BY CHECKED BY