

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	24

STA. TO STA.
 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT
 * FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 ** D6 INTERSTATE RS,BR,M CAB 2008

MILLING SCHEDULE

LOCATION	PAVEMENT WIDTH (FOOT)	OUTSIDE SHOULDER WIDTH (FOOT)	MEDIAN SHOULDER WIDTH (FOOT)	HMA SURF REM 0.75"	HMA SURF REM 1.5"	HMA SURF REM 2"	HMA SURF REM 2.5"	HMA SURF REM 3.25"	HMA SURF REM 3.75"	HMA SURF REM 5"	TOTAL AREA (SQ YD)	PAVT AREA (SQ YD)	SHLD AREA (SQ YD)
I-72 MAINLINE													
EASTBOUND													
STA 627+00.00	TO	STA 635+79.29 BK	24	10	4		1,367.78		2,344.77		3,712.55	2,344.77	1,367.78
STA 634+03.49 AH	TO	STA 646+56.00	24	10	4		1,948.35		3,340.03		5,288.38	3,340.03	1,948.35
STA 646+56.00	TO	STA 649+30.00	24	10	4			426.22		730.67	1,156.89	730.67	426.22
STA 649+30.00	TO	STA 652+57.06	24	10	4		508.76			872.16	1,380.92	872.16	508.76
STA 652+57.06	TO	STA 659+20.00	24	0	4		294.64			1,767.84	2,062.48	1,767.84	294.64
STA 659+20.00	TO	STA 671+02.00	24	10	4			1,838.67		3,152.00	4,990.67	3,152.00	1,838.67
STA 671+02.00	TO	STA 673+12.11	24	0	4			93.38		560.29	653.67	560.29	93.38
STA 675+04.78	TO	STA 678+44.00	24	0	4			150.76		904.59	1,055.35	904.59	150.76
STA 678+44.00	TO	STA 684+54.96	24	8	4			814.61		1,629.23	2,443.84	1,629.23	814.61
STA 688+01.96	TO	STA 689+25.00	24	8	4			164.05		328.11	492.16	328.11	164.05
STA 689+25.00	TO	STA 694+78.00	24	8 TO 16	6		1,106.00			1,474.67	2,580.67	1,474.67	1,106.00
STA 694+78.00	TO	STA 695+67.00	24	10	4			138.44		237.33	375.77	237.33	138.44
WESTBOUND													
STA 627+00.00	TO	STA 635+79.29 BK	24	10	4		1,367.78		2,344.77		3,712.55	2,344.77	1,367.78
STA 634+03.49 AH	TO	STA 657+60.37	24	10	4		3,666.26		6,285.01		9,951.27	6,285.01	3,666.26
STA 657+60.37	TO	STA 673+13.13	24	0	4		690.12		4,140.69		4,830.81	4,140.69	690.12
STA 675+05.80	TO	STA 677+20.00	24	0	4		95.20		571.20		666.40	571.20	95.20
STA 677+20.00	TO	STA 684+19.00	24	8	4			932.00		1,864.00	2,796.00	1,864.00	932.00
STA 684+19.00	TO	STA 691+08.25	24	0	4		306.33		1,838.00		2,144.33	1,838.00	306.33
STA 691+08.25	TO	STA 691+21.00	24	10	4		19.83		34.00		53.83	34.00	19.83
I-55 BUSINESS LOOP													
NORTHBOUND													
STA 27+74.75	TO	STA 29+74.00	24	4	4			177.11		531.33	708.44	531.33	177.11
STA 29+74.00	TO	STA 40+27.62	24	8	4		1,404.83		2,809.65		4,214.48	2,809.65	1,404.83
STA 43+03.26	TO	STA 51+83.67	24	8	4		1,173.88		2,347.76		3,521.64	2,347.76	1,173.88
STA 51+83.67	TO	STA 58+97.00	24	0	4		2,219.25				2,219.25	1,902.21	317.04
STA 58+97.00	TO	STA 61+29.29	24	8 TO 9	4		942.07			942.07	942.07	619.44	322.63
STA 61+29.29	TO	STA 61+59.25	24	10	4		126.50			126.50	126.50	79.89	46.60
STA 61+59.25	TO	STA 62+93.73	24	0	4		418.38			418.38	418.38	358.61	59.77
STA 62+93.73	TO	STA 63+50.00	24	8	4		225.08			225.08	225.08	150.05	75.03
SOUTHBOUND													
STA 31+21.67	TO	STA 35+76.00	28 TO 36.9	10	0		504.81		1,638.11		2,142.92	1,638.11	504.81
STA 35+76.00	TO	STA 41+32.00	24	0	4		247.11		1,482.67		1,729.78	1,482.67	247.11
STA 41+32.00	TO	STA 49+56.00	24	10	4		1,281.78		2,197.33		3,479.11	2,197.33	1,281.78
STA 49+56.00	TO	STA 54+00.00	24	0	4		1,381.33		1,381.33		1,381.33	1,184.00	197.33
STA 54+00.00	TO	STA 54+15.24	24	0	4		47.41			47.41	47.41	40.64	6.77
STA 54+15.24	TO	STA 61+05.00	24	8	4		2,759.04			2,759.04	2,759.04	1,839.36	919.68
STA 61+05.00	TO	STA 63+50.00	24	0	4		762.22			762.22	762.22	653.33	108.89
I-55 MAINLINE													
NORTHBOUND													
STA 9+97.00	TO	STA 11+34.00	36	10	4		213.11		548.00		761.11	548.00	213.11
STA 11+34.00	TO	STA 27+77.96	36 TO 58	10	4		2,557.27		8,585.12		11,142.39	8,585.12	2,557.27
STA 27+77.96	TO	STA 64+66.59	24	10	4		5,737.87		9,836.35		15,574.22	9,836.35	5,737.87
STA 64+66.59	TO	STA 67+13.00	64 TO 58	10	0		273.79		1,670.11		1,943.90	1,670.11	273.79
STA 67+13.00	TO	STA 68+50.00	58 TO 51	10	4		213.11		829.61		1,042.72	829.61	213.11
STA 68+50.00	TO	STA 72+75.50	51 TO 36	10	4		661.89		2,056.58		2,718.47	2,056.58	661.89
STA 72+75.50	TO	STA 92+11.00	36	10	4		3,010.78		7,742.00		10,752.78	7,742.00	3,010.78
STA 92+11.00	TO	STA 98+11.00	36 TO 25	10	4		933.33		2,033.33		2,966.66	2,033.33	933.33
STA 98+11.00	TO	STA 128+87.38 BK	24	10	4		4,785.48		8,203.68		12,989.16	8,203.68	4,785.48
STA 128+91.29 AH	TO	STA 171+00.60	24	10	4		6,547.82		11,224.83		17,772.65	11,224.83	6,547.82

PLOT DATE = 08/15/2007 08:15:00AM
 FILE NAME = c:\p\projects\4652882\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY
 SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____