

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	25
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS) ** D6 INTERSTATE RS,BR,M CAB 2008				

MILLING SCHEDULE

LOCATION		PAVEMENT WIDTH (FOOT)	OUTSIDE SHOULDER WIDTH (FOOT)	MEDIAN SHOULDER WIDTH (FOOT)	HMA SURF REM 0.75" (SQ YD)	HMA SURF REM 1.5" (SQ YD)	HMA SURF REM 2" (SQ YD)	HMA SURF REM 2.5" (SQ YD)	HMA SURF REM 3.25" (SQ YD)	HMA SURF REM 3.75" (SQ YD)	HMA SURF REM 5" (SQ YD)	TOTAL AREA (SQ YD)	PAVT AREA (SQ YD)	SHLD AREA (SQ YD)
STA 171+00.60	TO	STA 175+81.00	24	0	4		213.51			1,281.07		1,494.58	1,281.07	213.51
STA 175+81.00	TO	STA 182+68.00	24	10	4			1,068.67		1,832.00		2,900.67	1,832.00	1,068.67
STA 182+68.00	TO	STA 194+76.00	24	0	4			536.89		3,221.33		3,758.22	3,221.33	536.89
STA 194+76.00	TO	STA 233+44.43 BK	24	10	4			6,017.56		10,315.81		16,333.37	10,315.81	6,017.56
STA 233+52.70 AH	TO	STA 250+04.00	24	10	4			2,568.69		4,403.47		6,972.16	4,403.47	2,568.69
STA 250+04.00	TO	STA 259+78.00	24	10	0			1,082.22		2,597.33		3,679.55	2,597.33	1,082.22
STA 262+55.00	TO	STA 265+30.00	24					0.00		733.33		733.33	733.33	0.00
STA 265+30.00	TO	STA 271+56.00	24	10	0			695.56		1,669.33		2,364.89	1,669.33	695.56
STA 271+56.00	TO	STA 273+14.00	24					0.00		421.33		421.33	421.33	0.00
STA 277+50.00	TO	STA 279+84.00	24					0.00		624.00		624.00	624.00	0.00
STA 279+84.00	TO	STA 286+04.00	24	10	0			688.89		1,653.33		2,342.22	1,653.33	688.89
STA 286+04.00	TO	STA 286+74.00	24	10	4			108.89		186.67		295.56	186.67	108.89
STA 286+74.00	TO	STA 297+35.71	24	0	4			471.87		2,831.23		3,303.10	2,831.23	471.87
STA 297+35.71	TO	STA 315+70.88	24	10	4			2,854.71		4,893.79		7,748.50	4,893.79	2,854.71
STA 315+70.88	TO	STA 322+25.00	24	0	4			290.72		1,744.32		2,035.04	1,744.32	290.72
STA 322+25.00	TO	STA 330+83.00	24	10	4			1,334.67		2,288.00		3,622.67	2,288.00	1,334.67
STA 330+83.00	TO	STA 337+60.00	24	0	4			300.89		1,805.33		2,106.22	1,805.33	300.89
STA 337+60.00	TO	STA 343+95.00	24	10	4			987.78		1,693.33		2,681.11	1,693.33	987.78
STA 343+95.00	TO	STA 354+63.47	24	0	4			474.88		2,849.25		3,324.13	2,849.25	474.88
STA 354+63.47	TO	STA 355+49.48 BK	24	10	4			133.79		229.36		363.15	229.36	133.79
STA 695+67.32 AH	TO	STA 693+00.00	24	10	4			415.83		712.85		1,128.68	712.85	415.83
SOUTHBOUND														
STA 13+59.00	TO	STA 19+28.00	37	TO	42	10		4		885.11		2,497.28	2,497.28	885.11
STA 19+28.00	TO	STA 31+22.04	42	TO	56	10		4		1,857.40		6,500.88	6,500.88	1,857.40
STA 31+22.04	TO	STA 34+95.41	24			0		4		165.94		995.65	995.65	165.94
STA 34+95.41	TO	STA 35+75.41	24			10		4			124.44	337.77	213.33	124.44
STA 35+75.41	TO	STA 39+41.00	24			10		4		568.70		974.91	974.91	568.70
STA 39+41.00	TO	STA 44+34.00	24			10		4		766.89		1,314.67	1,314.67	766.89
STA 44+34.00	TO	STA 50+00.00	24			10		4		880.44		1,509.33	1,509.33	880.44
STA 50+00.00	TO	STA 56+63.00	24		11	TO	15	6		1,399.67		1,768.00	1,768.00	1,399.67
STA 56+63.00	TO	STA 61+22.00	24		15	TO	17	6				1,122.00	1,122.00	
STA 61+22.00	TO	STA 64+32.03	24		17	TO	19	6		826.75		826.75	826.75	826.75
STA 64+32.03	TO	STA 74+87.00	68	TO	39	10		6		1,875.50		6,271.21	6,271.21	1,875.50
STA 74+87.00	TO	STA 77+88.00	39	TO	36	10		6		535.11		1,254.17	1,254.17	535.11
STA 77+88.00	TO	STA 83+88.00	36			10		6		1,066.67		3,466.67	2,400.00	1,066.67
STA 83+88.00	TO	STA 86+63.86 BK	36	TO	33	10		6		490.42		1,057.46	1,057.46	490.42
STA 82+99.33 AH	TO	STA 90+23.61	33	TO	25	10		6		1,287.61		3,621.40	2,333.79	1,287.61
STA 90+23.61	TO	STA 128+87.38 BK	24			10		4		6,010.31		10,303.39	10,303.39	6,010.31
STA 128+91.29 AH	TO	STA 163+18.00	24			10		4		5,330.44		14,468.33	9,137.89	5,330.44
STA 163+18.00	TO	STA 174+02.00	24			0		4		481.78		3,372.45	2,890.67	481.78
STA 174+02.00	TO	STA 181+27.00	24			10		4		1,127.78		1,933.33	1,933.33	1,127.78
STA 181+27.00	TO	STA 187+95.91	24			0		4		297.29		1,783.76	2,081.05	297.29
STA 187+95.91	TO	STA 233+44.43 BK	24			10		4		7,075.48		12,129.39	12,129.39	7,075.48
STA 233+52.70 AH	TO	STA 250+04.00	24			10		4		2,568.69		6,972.16	4,403.47	2,568.69
STA 250+04.00	TO	STA 253+81.91	24			10		0		419.90		1,427.66	1,007.76	419.90
STA 253+81.91	TO	STA 260+03.00	24					0.00		1,656.24		1,656.24	1,656.24	0.00
STA 262+80.00	TO	STA 264+83.00	24					0.00		541.33		541.33	541.33	0.00
STA 264+83.00	TO	STA 271+34.00	24			10		0		723.33		2,459.33	1,736.00	723.33
STA 271+34.00	TO	STA 273+44.00	24					0.00		560.00		560.00	560.00	0.00

PLOT DATE = 08/15/10  
 FILE NAME = c:\p\projects\65282\shsch.dgn  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = laughlin

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES FA155(I-55), FA172(I-72), FAP666(I-55 BUS) SECTION D6 INTERSTATE RS,BR,M CAB 2008 SANGAMON COUNTY
SCALE:	DRAWN BY:	CHECKED BY:
DATE:		