

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	26

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 ** D6 INTERSTATE RS,BR,M CAB 2008

MILLING SCHEDULE

LOCATION	PAVEMENT WIDTH (FOOT)	OUTSIDE SHOULDER WIDTH (FOOT)	MEDIAN SHOULDER WIDTH (FOOT)	HMA SURF REM 0.75" (SQ YD)	HMA SURF REM 1.5" (SQ YD)	HMA SURF REM 2" (SQ YD)	HMA SURF REM 2.5" (SQ YD)	HMA SURF REM 3.25" (SQ YD)	HMA SURF REM 3.75" (SQ YD)	HMA SURF REM 5" (SQ YD)	TOTAL AREA (SQ YD)	PAVT AREA (SQ YD)	SHLD AREA (SQ YD)
STA 277+75.00 TO STA 278+87.00	24					0.00			298.67		298.67	298.67	0.00
STA 278+87.00 TO STA 286+00.00	24	10	0			792.22			1,901.33		2,693.55	1,901.33	792.22
STA 286+00.00 TO STA 287+33.00	24	10	4			206.89			354.67		561.56	354.67	206.89
STA 287+33.00 TO STA 293+54.97	24	0	4			276.43			1,658.59		1,935.02	1,658.59	276.43
STA 293+54.97 TO STA 312+52.40	24	10	4			2,951.56			5,059.81		8,011.37	5,059.81	2,951.56
STA 312+52.40 TO STA 323+12.00	24	0	4			470.93			2,825.60		3,296.53	2,825.60	470.93
STA 323+12.00 TO STA 329+68.00	24	10	4			1,020.44			1,749.33		2,769.77	1,749.33	1,020.44
STA 329+68.00 TO STA 336+14.00	24	0	4			287.11			1,722.67		2,009.78	1,722.67	287.11
STA 336+14.00 TO STA 344+89.00	24	10	4			1,361.11			2,333.33		3,694.44	2,333.33	1,361.11
STA 344+89.00 TO STA 351+24.04	24	0	4			282.24			1,693.44		1,975.68	1,693.44	282.24
STA 351+24.04 TO STA 355+49.48 BK	24	10	4			661.80			1,134.51		1,796.31	1,134.51	661.80
STA 695+67.32 AH TO STA 693+00.00	24	10	4			415.83			712.85		1,128.68	712.85	415.83
SIXTH STREET INTERCHANGE													
RAMP A													
STA 0+00.00 TO STA 0+50.00	1 TO 3.6	9 TO 6	0			41.67			12.78		54.45	12.78	41.67
STA 0+50.00 TO STA 3+14.00	3.6 TO 17	6	0			176.00			302.13		478.13	302.13	176.00
STA 3+14.00 TO STA 5+30.00	16	6	0			144.00			384.00		528.00	384.00	144.00
STA 5+30.00 TO STA 6+62.40	16	6	4 TO 18			250.09			235.38		485.47	235.38	250.09
STA 6+62.40 TO STA 26+12.00	16	6	4			2,166.22			3,465.96		5,632.18	3,465.96	2,166.22
STA 26+12.00 TO STA 26+54.00	16								74.67		74.67	74.67	0.00
STA 26+54.00 TO STA 27+28.00	16 TO 14								123.33		123.33	123.33	0.00
STA 27+28.00 TO STA 28+28.00	14								155.56		155.56	155.56	0.00
STA 26+12.00 TO STA 28+28.00		6	18 TO 6			432.00			432.00		432.00	0.00	432.00
STA 28+28.00 TO STA 30+28.00	14	6	0			133.33			311.11		444.44	311.11	133.33
STA 30+28.00 TO STA 31+65.18	16 TO 13	6	0			91.45			220.25		311.70	220.25	91.45
GORE AREA @ BL-55	VARY								88.89		88.89	88.89	0.00
GORE AREA @ EB I-72	VARY								247.44		247.44	247.44	0.00
RAMP B													
STA 3+04.74 TO STA 3+84.00	14 TO 12	8	0			70.45			112.29		182.74	112.29	70.45
STA 3+84.00 TO STA 4+50.00	12 TO 17	8	0			58.67			106.33		165.00	106.33	58.67
STA 4+50.00 TO STA 6+12.00	17 TO 33	8	0			144.00			445.50		589.50	445.50	144.00
STA 6+12.00 TO STA 6+42.00	19 TO 17	8	4 TO 14			56.67			59.17		115.84	59.17	56.67
STA 6+42.00 TO STA 6+60.00	17 TO 16	8	4			24.00			33.00		57.00	33.00	24.00
STA 6+60.00 TO STA 17+39.00	16	8	4			1,438.67			1,918.22		3,356.89	1,918.22	1,438.67
STA 17+39.00 TO STA 17+74.00	16	8	4			46.67			62.22		108.89	62.22	46.67
STA 17+74.00 TO STA 17+98.25	16	8	12 TO 6			88.92			88.92		177.84	88.92	88.92
STA 17+98.25 TO STA 18+45.45	16 TO 14	8	0			120.62			120.62		241.24	120.62	120.62
STA 18+45.45 TO STA 21+07.57	20 TO 16	8	0			751.41			751.41		1,502.82	751.41	751.41
GORE AREA	VARY								155.22		155.22	155.22	0.00
RAMP C													
STA 0+00.00 TO STA 1+97.03	16 TO 12	8	0			479.44			479.44		958.88	479.44	479.44
STA 1+97.03 TO STA 3+84.00	12 TO 34	8	0			649.20			649.20		1,298.40	649.20	649.20
STA 3+84.00 TO STA 4+01.00	19 TO 17	8	4 TO 14			65.83			65.83		131.66	65.83	65.83
STA 4+01.00 TO STA 4+18.00	17 TO 16	8	4			22.67			31.36		54.03	31.36	22.67
STA 4+18.00 TO STA 4+36.00	16	8	4			24.00			32.00		56.00	32.00	24.00
STA 4+36.00 TO STA 13+72.00	16	8	4			1,248.00			1,664.00		2,912.00	1,664.00	1,248.00
STA 13+72.00 TO STA 14+12.63	16	8	18 TO 10			99.99			72.23		172.22	72.23	99.99

PLOT DATE = 08/11/2007 08:14:24AM
 FILE NAME = c:\p\projects\652882\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY
 SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____