

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	27

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

\* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)  
 \*\* D6 INTERSTATE RS,BR,M CAB 2008

MILLING SCHEDULE

LOCATION	PAVEMENT WIDTH (FOOT)	OUTSIDE SHOULDER WIDTH (FOOT)	MEDIAN SHOULDER WIDTH (FOOT)	HMA SURF REM 0.75" (SQ YD)	HMA SURF REM 1.5" (SQ YD)	HMA SURF REM 2" (SQ YD)	HMA SURF REM 2.5" (SQ YD)	HMA SURF REM 3.25" (SQ YD)	HMA SURF REM 3.75" (SQ YD)	HMA SURF REM 5" (SQ YD)	TOTAL AREA (SQ YD)	PAVT AREA (SQ YD)	SHLD AREA (SQ YD)
STA 14+12.63 TO STA 14+75.95	16 TO 14	8	10 TO 4			106.59			105.53		212.12	105.53	106.59
STA 14+75.95 TO STA 15+82.37	20 TO 18	8	0			94.60			223.48		318.08	223.48	94.60
STA 17+72.14 TO STA 20+25.83	16 TO 12	8	0			225.50			394.63		620.13	394.63	225.50
STA 20+25.83 TO STA 21+57.00	12 TO 5.7	8	0			116.60			128.98		245.58	128.98	116.60
STA 21+57.00 TO STA 22+76.16	5.7 TO 0	0	0			0.00			37.73		37.73	37.73	0.00
GORE AREA @ BL-55	VARY					155.22					155.22	155.22	0.00
RAMP D													
STA 4+12.72 TO STA 5+30.00	16	8	0			312.75					312.75	208.50	104.25
STA 5+30.00 TO STA 6+57.00	16	8	4 TO 16			479.78					479.78	225.78	254.00
STA 6+57.00 TO STA 6+92.00	16	8	4			46.67			62.22		108.89	62.22	46.67
STA 6+92.00 TO STA 13+72.00	16	8	4			906.67		1,208.89			2,115.56	1,208.89	906.67
STA 13+72.00 TO STA 14+43.15	16	8	18 TO 12			181.83			126.49		308.32	126.49	181.83
STA 14+43.15 TO STA 15+15.82	16 TO 14	8	12 TO 6			137.27			121.12		258.39	121.12	137.27
STA 15+15.82 TO STA 17+15.84	14	8	0			177.80			311.14		488.94	311.14	177.80
STA 17+15.84 TO STA 25+37.88	16 TO 1	8	0			730.70			776.37		1,507.07	776.37	730.70
GORE AREA @ BL-55	VARY					200.79					200.79	200.79	0.00
GORE AREA @ WB I-72	VARY								88.89		88.89	88.89	0.00
SW LOOP RAMP													
STA 0+00.00 TO STA 2+00.00	1 TO 12	4 TO 6	0								0.00	144.44	111.11
STA 2+00.00 TO STA 3+15.00	12	6	0			230.00					230.00	153.33	76.67
STA 3+15.00 TO STA 3+82.35	12 TO 17	6	0			153.41					153.41	108.51	44.90
STA 3+82.35 TO STA 4+40.00	16	6	0			140.92					140.92	102.49	38.43
STA 4+40.00 TO STA 4+56.00	16	6	4 TO 10			51.56					51.56	28.44	23.11
STA 4+56.00 TO STA 17+89.00	16	6	4			1,481.11		2,369.78			3,850.89	2,369.78	1,481.11
STA 17+89.00 TO STA 18+31.92	16	6	18 TO 9			92.99			76.30		169.29	76.30	92.99
STA 18+31.92 TO STA 18+96.13	16 TO 14	6	9 TO 6			96.32			107.02		203.34	107.02	96.32
STA 18+96.13 TO STA 19+95.19	14	6	0			66.04			154.09		220.13	154.09	66.04
GORE AREA @ BL-55	VARY					116.51					116.51	116.51	0.00
GORE AREA @ I-72	VARY								54.18		54.18	54.18	0.00
NE RAMP													
STA 0+00.00 TO STA 0+50.00	1 TO 2.8	7 TO 6	0			36.11			10.56		46.67	10.56	36.11
STA 0+50.00 TO STA 3+03.00	2.8 TO 17	6	0			168.67			278.30		446.97	278.30	168.67
STA 3+03.00 TO STA 5+30.00	16	6	0			151.33			403.56		554.89	403.56	151.33
STA 5+30.00 TO STA 6+85.00	16	6	4 TO 18			292.78			275.56		568.34	275.56	292.78
STA 6+85.00 TO STA 7+10.00	16	6	4			27.78			44.44		72.22	44.44	27.78
STA 7+10.00 TO STA 17+64.00	16	6	4	1,171.11			1,873.78				3,044.89	1,873.78	1,171.11
STA 17+64.00 TO STA 19+06.00	16	8	0	126.22			252.44				378.66	252.44	126.22
STA 19+06.00 TO STA 19+84.23	16 TO 1	8 TO 10	0	78.23			73.88				152.11	73.88	78.23
GORE AREA @ I-72	VARY										248.37	248.37	0.00
STEVENSON DRIVE													
RAMP A													
STA 0+00.00 TO STA 3+03.68	1 TO 17	8	0			269.94			303.68		573.62	303.68	269.94
STA 3+03.68 TO STA 5+21.00	16	8	0			193.17			386.35		579.52	386.35	193.17
STA 5+21.00 TO STA 6+68.00	16	8	4 TO 11			253.17			261.33		514.50	261.33	253.17
STA 6+68.00 TO STA 6+93.00	16	8	4			33.33			44.44		77.77	44.44	33.33
STA 6+93.00 TO STA 12+29.60	16	8	4	715.47			953.96				1,669.43	953.96	715.47
STA 12+29.60 TO STA 14+63.86	16 TO 24	8 TO 4	4	260.29			520.58				780.87	520.58	260.29
STA 14+63.86 TO STA 16+77.00	24	4	4	189.46			568.37				757.83	568.37	189.46
GORE AREA											247.64	247.64	0.00

PLOT DATE = 08/11/2007 08:15:13AM  
 FILE NAME = c:\p\projects\4652882\shsch.dgn  
 PLOT SCALE = 1/8"=1'-0" / IN.  
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)  
 SECTION D6 INTERSTATE RS,BR,M CAB 2008  
 SANGAMON COUNTY  
 SCALE: \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 DATE \_\_\_\_\_ CHECKED BY \_\_\_\_\_