CONTRACT NO. 72659

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	28
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI55(I-55), FAI72(I-72), FAP666(I-55 BUS)
** D6 INTERSTATE RS,BR,M CAB 2008

MILLING SCHEDULE

LOCATION			PAVEMENT WIDTH (FOOT)	OUTSIDE SHOULDER WIDTH (FOOT)	MEDIAN SHOULDER WIDTH (FOOT)	HMA SURF REM 0.75" (SQ YD)	HMA SURF REM 1.5" (SQ YD)	HMA SURF REM 2" (SQ YD)	HMA SURF REM 2.5" (SQ YD)	HMA SURF REM 3.25" (SQ YD)	HMA SURF REM 3.75" (SQ YD)	HMA SURF REM 5" (SQ YD)	TOTAL AREA (SQ YD)	PAVT AREA (SQ YD)	SHLD AREA (SQ YD)
RAMP B															
STA 1+21.00	TO	STA 7+31.00	16	6	4	677.78			1,084.44				1,762.22	1,084.44	677.78
STA 7+31.00	TO	STA 7+56.00	16	6	4			27.78			44.44		72.22	44.44	27.78
STA 7+56.00	TO	STA 8+04.00	16					0.00			85.33		85.33	85.33	0.00
STA 8+04.00	TO	STA 8+74.00	16 TO 14					0.00			116.67		116.67	116.67	0.00
STA 8+74.00	TO	STA 18+15.73	20 TO 1	6	0			627.82			1,098.69		1,726.51	1,098.69	627.82
STA 7+56.00	TO	STA 8+46.00		6	18 TO 6			180.00					180.00	0.00	180.00
STA 8+46.00	TO	STA 8+74.00		6				18.67					18.67	0.00	18.67
RAMP C															
STA 0+00.00	TO	STA 2+29.36	1 TO 17	6	0			152.91			229.36		382.27	229.36	152.91
STA 2+29.36	TO	STA 3+91.00	16	6	0			107.76			287.36		395.12	287.36	107.76
STA 3+91.00	TO	STA 4+84.00	16	6	4 TO 18			175.67			165.33		341.00	165.33	175.67
STA 4+84.00	TO	STA 5+09.00	16	6	4			27.78			44.44		72.22	44.44	27.78
STA 5+09.00	TO	STA 9+97.79	16	6	4	543.10			868.96				1,412.06	868.96	543.10
STA 9+97.79	TO	STA 11+17.79	17 TO 24	6 TO 4	4	120.00			273.33				393.33	273.33	120.00
STA 11+17.79	TO	STA 13+46.00	24	4	4	202.85			608.56				811.41	608.56	202.85
GORE AREA											195.19		195.19	195.19	0.00
RAMP D															
STA 1+03.00	TO	STA 10+99.00	16	6	4	1,106.67			1,770.67				2,877.34	1,770.67	1,106.67
STA 10+99.00	TO	STA 11+24.00	16	6	4			27.78			44.44		72.22	44.44	27.78
STA 11+24.00	TO	STA 11+35.60	16					0.00			20.62		20.62	20.62	0.00
STA 11+35.60	TO	STA 11+92.26	16 TO 14					0.00			94.43		94.43	94.43	0.00
STA 11+92.26	TO	STA 13+92.41	14					0.00			311.34		311.34	311.34	0.00
STA 13+92.41	TO	STA 23+29.60	20 TO 1	6	0			624.79			1,093.39		1,718.18	1,093.39	624.79
STA 11+24.00	TO	STA 13+92.41		6	14 TO 6			477.17					477.17	0.00	477.17
SOUTH GRAND AVE.															
RAMP A															
STA 4+25.00	TO	STA 10+77.00	16	8	4	869.33			1,159.11				2,028.44	1,159.11	869.33
STA 10+77.00	TO	STA 11+02.00	16	8	4			33.33			44.44		77.77	44.44	33.33
STA 11+02.00	TO	STA 11+31.00	16					0.00			51.56		51.56	51.56	0.00
STA 11+31.00	TO	STA 11+81.00	16 TO 14					0.00			83.33		83.33	83.33	0.00
STA 11+81.00	TO	STA 12+09.40	20 TO 20	8	0			25.24			62.48		87.72	62.48	25.24
STA 11+02.00	TO	STA 11+81.00		8	16 TO 6			166.78			0.00		166.78	0.00	166.78
RAMP B															
STA 0+00.00	TO	STA 3+03.68	1 TO 17	8	0			269.94			303.68		573.62	303.68	269.94
STA 3+03.68	TO	STA 5+27.00	16	8	0			198.51			397.01		595.52	397.01	198.51
STA 5+27.00	TO	STA 6+21.00	16	8	4 TO 14			177.56			167.11		344.67	167.11	177.56
STA 6+21.00	TO	STA 6+46.00	16	8	4			33.33			44.44		77.77	44.44	33.33
STA 6+46.00	TO	STA 18+92.00	16	8	4	1,661.33			2,215.11				3,876.44	2,215.11	1,661.33
GORE AREA											248.28		248.28	248.28	0.00
RAMP C															
STA 2+27.00	TO	STA 4+34.00	13 TO 33	8	0			184.00			517.50		701.50	517.50	184.00
STA 4+34.00	TO	STA 4+43.00	16	8	4			12.00			16.00		28.00	16.00	12.00
STA 4+43.00	TO	STA 4+68.00	16	8	4			33.33			44.44		77.77	44.44	33.33
STA 4+68.00	TO	STA 17+10.00	16	8	4	1,656.00			2,208.00				3,864.00	2,208.00	1,656.00
GORE AREA											155.22		155.22	155.22	0.00
RAMP D															
STA 2+89.00	TO	STA 19+51.00	16	8	4	2,216.00			2,954.67				5,170.67	2,954.67	2,216.00
STA 19+51.00	TO	STA 19+76.00	16	8	4			33.33			44.44		77.77	44.44	33.33

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAI55(I-55), FAI72(I-72), FAP666(I-55 BUS)
SECTION D6 INTERSTATE RS,BR,M CAB 2008
SANGAMON COUNTY

SCALE: DRAWN BY
DATE CHECKED BY

PLOT DATE = Oct-22-2007 08:19:14AM
FILE NAME = c:\Projects\d65288\sht sch.dgn
PLOT SCALE = 100.0000 ' / IN.
USER NAME = Langfur-I