

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	30
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS) ** D6 INTERSTATE RS,BR,M CAB 2008				

MILLING SCHEDULE

LOCATION	PAVEMENT WIDTH (FOOT)	OUTSIDE SHOULDER WIDTH (FOOT)	MEDIAN SHOULDER WIDTH (FOOT)	HMA SURF REM 0.75" (SQ YD)	HMA SURF REM 1.5" (SQ YD)	HMA SURF REM 2" (SQ YD)	HMA SURF REM 2.5" (SQ YD)	HMA SURF REM 3.25" (SQ YD)	HMA SURF REM 3.75" (SQ YD)	HMA SURF REM 5" (SQ YD)	TOTAL AREA (SQ YD)	PAVT AREA (SQ YD)	SHLD AREA (SQ YD)		
STA 1+75.23	14 TO 33	8	0			166.91			485.07		651.98	485.07	166.91		
STA 3+63.00	16	8	4			38.67			51.56		90.23	51.56	38.67		
STA 3+92.00	16	8	4			13.33			17.78		31.11	17.78	13.33		
STA 4+02.00	16	8	4		1,044.00			1,392.00			2,436.00	1,392.00	1,044.00		
GORE AREA									155.22		155.22	155.22	0.00		
RAMP D															
STA 3+20.00	16	8	4		1,808.00			2,410.67			4,218.67	2,410.67	1,808.00		
STA 16+76.00	16	8	4			13.33			17.78		31.11	17.78	13.33		
STA 16+86.00	16								97.78		97.78	97.78	0.00		
STA 17+41.00	16 TO 14								120.00		120.00	120.00	0.00		
STA 18+13.00	20 TO 1	8	0			826.67			1,085.00		1,911.67	1,085.00	826.67		
STA 16+86.00	8	18 TO 6				282.22					282.22	0.00	282.22		
RAMP E															
STA 3+79.00	16	8	4		1,334.67			1,779.56			3,114.23	1,779.56	1,334.67		
STA 13+80.00	16	8	4			13.33			17.78		31.11	17.78	13.33		
STA 13+90.00	16					0.00			44.44		44.44	44.44	0.00		
STA 14+15.00	16 TO 14					0.00			95.00		95.00	95.00	0.00		
STA 14+72.00	20 TO 16	8	0			173.04			389.34		562.38	389.34	173.04		
STA 13+90.00	8	18 TO 6				182.22			0.00		182.22	0.00	182.22		
RAMP F															
STA 0+00.00	1 TO 17	8	0			265.78			299.00		564.78	299.00	265.78		
STA 2+99.00	16	8	0			201.78			403.56		605.34	403.56	201.78		
STA 5+26.00	16	8	4 TO 18			270.22			227.56		497.78	227.56	270.22		
STA 6+54.00	16	8	4			13.33			17.78		31.11	17.78	13.33		
STA 6+65.00	16	8	4		2,032.00			2,709.33			4,741.33	2,709.33	2,032.00		
GORE AREA									248.28		248.28	248.28	0.00		
RAMP G															
STA 0+00.00	16 TO 13	8	0			161.34			288.40		449.74	288.40	161.34		
STA 1+81.51	13 TO 33	8	0			157.77			444.71		602.48	444.71	157.77		
STA 3+59.00	16	8	4			44.00			58.67		102.67	58.67	44.00		
STA 3+92.00	16	8	4			13.33			17.78		31.11	17.78	13.33		
STA 4+02.00	16	8	4		1,029.33			1,372.44			2,401.77	1,372.44	1,029.33		
GORE AREA									155.22		155.22	155.22	0.00		
RAMP H															
STA 3+36.00	16	8	4		1,777.33			2,369.78			4,147.11	2,369.78	1,777.33		
STA 16+69.00	16	8	4			13.33			17.78		31.11	17.78	13.33		
STA 16+79.00	16					0.00			65.78		65.78	65.78	0.00		
STA 17+16.00	16 TO 14					0.00			123.33		123.33	123.33	0.00		
STA 17+90.00	20 TO 1	8	0			847.96			1,112.94		1,960.90	1,112.94	847.96		
STA 16+79.00	8	18 TO 6				246.67			0.00		246.67	0.00	246.67		
EMERGENCY MEDIAN CROSSOVERS & APPR SHLDS															
I-72															
STA 640+55											552.03		552.03		
I-55															
STA 15+55											0.00		0.00		
STA 116+40		8	18 TO 6			142.11					229.98		229.98		
TOTAL						17,531.16	25,682.79	135,403.13	25,302.30	42,639.54	257,758.00	1,224.00	506,684.28	335,534.61	171,405.23

PLOT DATE = 08/22/2007 08:15:16AM
 FILE NAME = c:\p\projects\4652882\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY
 SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____