

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	34
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)				
** D6 INTERSTATE RS,BR,M CAB 2008				

PAVING SCHEDULE

LOCATION	PAVEMENT WIDTH (FOOT)	OUTSIDE SHOULDER WIDTH (FOOT)	MEDIAN SHOULDER WIDTH (FOOT)	TOTAL AREA (SQ YD)	PAVT AREA (SQ YD)	SHLD AREA (SQ YD)	BIT MATL PR CT (TON)	AGG PR CT (TON)	BINDER DEPTH (INCHES)	SURFACE DEPTH (INCHES)	SHLD SURF DEPTH (INCHES)	BINDER N105 (TON)	SURFACE N105 (TON)	SURF N30 FOR SHLD (TON)	
STA 14+12.63	TO 14	8	10 TO 4	212.12	105.53	106.59	0.08	0.42	2.25	1.50	2.00	13.30	8.86	11.94	
STA 14+75.95	TO 18	8	0	318.08	223.48	94.60	0.12	0.64	2.25	1.50	2.00	28.16	18.77	10.60	
STA 17+72.14	TO 12	8	0	620.13	394.63	225.50	0.24	1.24	2.25	1.50	2.00	49.72	33.15	25.26	
STA 20+25.83	TO 5.7	8	0	245.58	128.98	116.60	0.09	0.49	2.25	1.50	2.00	16.25	10.83	13.06	
STA 21+57.00	TO 0	0	0	37.73	37.73	0.00	0.01	0.08	2.25	1.50	2.00	4.75	3.17	0.00	
GORE AREA @ BL-55	VARY			155.22	155.22	0.00	0.06	0.31		2.00	2.00	0.00	17.38	0.00	
RAMP D															
STA 4+12.72	TO 16	8	0	312.75	208.50	104.25	0.12	0.63		2.00	2.00		23.35	11.68	
STA 5+30.00	TO 16	8	4 TO 16	479.78	225.78	254.00	0.18	0.96		2.00	2.00		25.29	28.45	
STA 6+57.00	TO 16	8	4	108.89	62.22	46.67	0.04	0.22	2.25	1.50	2.00	7.84	5.23	5.23	
STA 6+92.00	TO 16	8	4	2,115.56	1,208.89	906.67	0.80	4.23	2.25	1.50	2.00	152.32	101.55	101.55	
STA 13+72.00	TO 16	8	18 TO 12	308.32	126.49	181.83	0.12	0.62	2.25	1.50	2.00	15.94	10.63	20.36	
STA 14+43.15	TO 14	8	12 TO 6	258.39	121.12	137.27	0.10	0.52	2.25	1.50	2.00	15.26	10.17	15.37	
STA 15+15.82	TO 14	8	0	488.94	311.14	177.80	0.19	0.98	2.25	1.50	2.00	39.20	26.14	19.91	
STA 17+15.84	TO 1	8	0	1,507.07	776.37	730.70	0.57	3.01	2.25	1.50	2.00	97.82	65.22	81.84	
GORE AREA @ BL-55	VARY			200.79	200.79	0.00	0.08	0.40		2.00	2.00		22.49	0.00	
GORE AREA @ WB I-72	VARY			88.89	88.89	0.00	0.03	0.18	2.25	1.50	2.00	11.20	7.47	0.00	
SW LOOP RAMP															
STA 0+00.00	TO 12	4 TO 6	0	0.00	144.44	111.11	0.00	0.00		2.00	2.00	0.00	16.18	12.44	
STA 2+00.00	TO 12	6	0	230.00	153.33	76.67	0.09	0.46		2.00	2.00	0.00	17.17	8.59	
STA 3+15.00	TO 17	6	0	153.41	108.51	44.90	0.06	0.31		2.00	2.00	0.00	12.15	5.03	
STA 3+82.35	TO 16	6	0	140.92	102.49	38.43	0.05	0.28		2.00	2.00	0.00	11.48	4.30	
STA 4+40.00	TO 16	6	4 TO 10	51.56	28.44	23.11	0.02	0.10		2.00	2.00	0.00	3.19	2.59	
STA 4+56.00	TO 16	6	4	3,850.89	2,369.78	1,481.11	1.46	7.70	2.25	1.50	2.00	298.59	199.06	165.88	
STA 17+89.00	TO 16	6	18 TO 9	169.29	76.30	92.99	0.06	0.34	2.25	1.50	2.00	9.61	6.41	10.41	
STA 18+31.92	TO 14	6	9 TO 6	203.34	107.02	96.32	0.08	0.41	2.25	1.50	2.00	13.48	8.99	10.79	
STA 18+96.13	TO 14	6	0	220.13	154.09	66.04	0.08	0.44	2.25	1.50	2.00	19.42	12.94	7.40	
GORE AREA @ BL-55	VARY			116.51	116.51	0.00	0.04	0.23		2.00	2.00	0.00	13.05	0.00	
GORE AREA @ I-72	VARY			54.18	54.18	0.00	0.02	0.11	2.25	1.50	2.00	6.83	4.55	0.00	
NE RAMP															
STA 0+00.00	TO 2.8	7 TO 6	0	46.67	10.56	36.11	0.02	0.09	2.25	1.50	2.00	1.33	0.89	4.04	
STA 0+50.00	TO 17	6	0	446.97	278.30	168.67	0.17	0.89	2.25	1.50	2.00	35.07	23.38	18.89	
STA 3+03.00	TO 16	6	0	554.89	403.56	151.33	0.21	1.11	2.25	1.50	2.00	50.85	33.90	16.95	
STA 5+30.00	TO 16	6	4 TO 18	568.34	275.56	292.78	0.22	1.14	2.25	1.50	2.00	34.72	23.15	32.79	
STA 6+85.00	TO 16	6	4	72.22	44.44	27.78	0.03	0.14	2.25	1.50	2.00	5.60	3.73	3.11	
STA 7+10.00	TO 16	6	4	3,044.89	1,873.78	1,171.11	1.16	6.09	2.25	1.50	2.00	236.10	157.40	131.16	
STA 17+64.00	TO 16	8	0	378.66	252.44	126.22	0.14	0.76	2.25	1.50	2.00	31.81	21.20	14.14	
STA 19+06.00	TO 1	8 TO 10	0	152.11	73.88	78.23	0.06	0.30	2.25	1.50	2.00	9.31	6.21	8.76	
GORE AREA @ I-72	VARY			248.37	248.37	0.00	0.09	0.50	2.25	1.50	2.00	31.29	20.86	0.00	
STEVENSON DRIVE															
RAMP A															
STA 0+00.00	TO 17	8	0	573.62	303.68	269.94	0.22	1.15	2.25	1.50	2.00	38.26	25.51	30.23	
STA 3+03.68	TO 16	8	0	579.52	386.35	193.17	0.22	1.16	2.25	1.50	2.00	48.68	32.45	21.64	
STA 5+21.00	TO 16	8	4 TO 11	514.50	261.33	253.17	0.20	1.03	2.25	1.50	2.00	32.93	21.95	28.36	
STA 6+68.00	TO 16	8	4	77.77	44.44	33.33	0.03	0.16	2.25	1.50	2.00	5.60	3.73	3.73	
STA 6+93.00	TO 16	8	4	1,669.43	953.96	715.47	0.63	3.34	2.25	1.50	2.00	120.20	80.13	80.13	
STA 12+29.60	TO 24	8 TO 4	4	780.87	520.58	260.29	0.30	1.56	2.25	1.50	2.00	65.59	43.73	29.15	
STA 14+63.86	TO 24	4	4	757.83	568.37	189.46	0.29	1.52	2.25	1.50	2.00	71.61	47.74	21.22	
GORE AREA				247.64	247.64	0.00	0.09	0.50	2.25	1.50	2.00	31.20	20.80	0.00	

PLOT DATE = 08/15/2007 08:15:21AM  
 FILE NAME = c:\p\projects\652882\hshsch.dgn  
 PLOT SCALE = 1/8"=1'-0" / IN.  
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)  
 SECTION D6 INTERSTATE RS,BR,M CAB 2008  
 SANGAMON COUNTY  
 SCALE: \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 DATE \_\_\_\_\_ CHECKED BY \_\_\_\_\_