

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	35
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)				
** D6 INTERSTATE RS,BR,M CAB 2008				

PAVING SCHEDULE

LOCATION	PAVEMENT WIDTH (FOOT)	OUTSIDE SHOULDER WIDTH (FOOT)	MEDIAN SHOULDER WIDTH (FOOT)	TOTAL AREA (SQ YD)	PAVT AREA (SQ YD)	SHLD AREA (SQ YD)	BIT MATL PR CT (TON)	AGG PR CT (TON)	BINDER DEPTH (INCHES)	SURFACE DEPTH (INCHES)	SHLD SURF DEPTH (INCHES)	BINDER N105 (TON)	SURFACE N105 (TON)	SURF N30 FOR SHLD (TON)		
RAMP B																
STA 1+21.00	TO	STA 7+31.00	16	6	4	1,762.22	1,084.44	677.78	0.67	3.52	2.25	1.50	2.00	136.64	91.09	75.91
STA 7+31.00	TO	STA 7+56.00	16	6	4	72.22	44.44	27.78	0.03	0.14	2.25	1.50	2.00	5.60	3.73	3.11
STA 7+56.00	TO	STA 8+04.00	16			85.33	85.33	0.00	0.03	0.17	2.25	1.50	2.00	10.75	7.17	0.00
STA 8+04.00	TO	STA 8+74.00	16 TO 14			116.67	116.67	0.00	0.04	0.23	2.25	1.50	2.00	14.70	9.80	0.00
STA 8+74.00	TO	STA 18+15.73	20 TO 1	6	0	1,726.51	1,098.69	627.82	0.66	3.45	2.25	1.50	2.00	138.43	92.29	70.32
STA 7+56.00	TO	STA 8+46.00	6	18 TO 6		180.00	0.00	180.00	0.07	0.36	2.25	1.50	2.00	0.00	0.00	20.16
STA 8+46.00	TO	STA 8+74.00	6			18.67	0.00	18.67	0.01	0.04	2.25	1.50	2.00	0.00	0.00	2.09
RAMP C																
STA 0+00.00	TO	STA 2+29.36	1 TO 17	6	0	382.27	229.36	152.91	0.15	0.76	2.25	1.50	2.00	28.90	19.27	17.13
STA 2+29.36	TO	STA 3+91.00	16	6	0	395.12	287.36	107.76	0.15	0.79	2.25	1.50	2.00	36.21	24.14	12.07
STA 3+91.00	TO	STA 4+84.00	16	6	4 TO 18	341.00	165.33	175.67	0.13	0.68	2.25	1.50	2.00	20.83	13.89	19.68
STA 4+84.00	TO	STA 5+09.00	16	6	4	72.22	44.44	27.78	0.03	0.14	2.25	1.50	2.00	5.60	3.73	3.11
STA 5+09.00	TO	STA 9+97.79	16	6	4	1,412.06	868.96	543.10	0.54	2.82	2.25	1.50	2.00	109.49	72.99	60.83
STA 9+97.79	TO	STA 11+17.79	17 TO 24	6 TO 4	4	393.33	273.33	120.00	0.15	0.79	2.25	1.50	2.00	34.44	22.96	13.44
STA 11+17.79	TO	STA 13+46.00	24	4	4	811.41	608.56	202.85	0.31	1.62	2.25	1.50	2.00	76.68	51.12	22.72
GORE AREA						195.19	195.19	0.00	0.07	0.39	2.25	1.50	2.00	24.59	16.40	0.00
RAMP D																
STA 1+03.00	TO	STA 10+99.00	16	6	4	2,877.34	1,770.67	1,106.67	1.09	5.75	2.25	1.50	2.00	223.10	148.74	123.95
STA 10+99.00	TO	STA 11+24.00	16	6	4	72.22	44.44	27.78	0.03	0.14	2.25	1.50	2.00	5.60	3.73	3.11
STA 11+24.00	TO	STA 11+35.60	16			20.62	20.62	0.00	0.01	0.04	2.25	1.50	2.00	2.60	1.73	0.00
STA 11+35.60	TO	STA 11+92.26	16 TO 14			94.43	94.43	0.00	0.04	0.19	2.25	1.50	2.00	11.90	7.93	0.00
STA 11+92.26	TO	STA 13+92.41	14			311.34	311.34	0.00	0.12	0.62	2.25	1.50	2.00	39.23	26.15	0.00
STA 13+92.41	TO	STA 23+29.60	20 TO 1	6	0	1,718.18	1,093.39	624.79	0.65	3.44	2.25	1.50	2.00	137.77	91.84	69.98
STA 11+24.00	TO	STA 13+92.41	6	14 TO 6		477.17	0.00	477.17	0.18	0.95	2.25	1.50	2.00	0.00	0.00	53.44
SOUTH GRAND AVE.																
RAMP A																
STA 4+25.00	TO	STA 10+77.00	16	8	4	2,028.44	1,159.11	869.33	0.77	4.06	2.25	1.50	2.00	146.05	97.37	97.36
STA 10+77.00	TO	STA 11+02.00	16	8	4	77.77	44.44	33.33	0.03	0.16	2.25	1.50	2.00	5.60	3.73	3.73
STA 11+02.00	TO	STA 11+31.00	16			51.56	51.56	0.00	0.02	0.10	2.25	1.50	2.00	6.50	4.33	0.00
STA 11+31.00	TO	STA 11+81.00	16 TO 14			83.33	83.33	0.00	0.03	0.17	2.25	1.50	2.00	10.50	7.00	0.00
STA 11+81.00	TO	STA 12+09.40	20 TO 20	8	0	87.72	62.48	25.24	0.03	0.18	2.25	1.50	2.00	7.87	5.25	2.83
STA 11+02.00	TO	STA 11+81.00	8	16 TO 6		166.78	0.00	166.78	0.06	0.33	2.25	1.50	2.00	0.00	0.00	18.68
RAMP B																
STA 0+00.00	TO	STA 3+03.68	1 TO 17	8	0	573.62	303.68	269.94	0.22	1.15	2.25	1.50	2.00	38.26	25.51	30.23
STA 3+03.68	TO	STA 5+27.00	16	8	0	595.52	397.01	198.51	0.23	1.19	2.25	1.50	2.00	50.02	33.35	22.23
STA 5+27.00	TO	STA 6+21.00	16	8	4 TO 14	344.67	167.11	177.56	0.13	0.69	2.25	1.50	2.00	21.06	14.04	19.89
STA 6+21.00	TO	STA 6+46.00	16	8	4	77.77	44.44	33.33	0.03	0.16	2.25	1.50	2.00	5.60	3.73	3.73
STA 6+46.00	TO	STA 18+92.00	16	8	4	3,876.44	2,215.11	1,661.33	1.47	7.75	2.25	1.50	2.00	279.10	186.07	186.07
GORE AREA						248.28	248.28	0.00	0.09	0.50	2.25	1.50	2.00	31.28	20.86	0.00
RAMP C																
STA 2+27.00	TO	STA 4+34.00	13 TO 33	8	0	701.50	517.50	184.00	0.27	1.40	2.25	1.50	2.00	65.21	43.47	20.61
STA 4+34.00	TO	STA 4+43.00	16	8	4	28.00	16.00	12.00	0.01	0.06	2.25	1.50	2.00	2.02	1.34	1.34
STA 4+43.00	TO	STA 4+68.00	16	8	4	77.77	44.44	33.33	0.03	0.16	2.25	1.50	2.00	5.60	3.73	3.73
STA 4+68.00	TO	STA 17+10.00	16	8	4	3,864.00	2,208.00	1,656.00	1.47	7.73	2.25	1.50	2.00	278.21	185.47	185.47
GORE AREA						155.22	155.22	0.00	0.06	0.31	2.25	1.50	2.00	19.56	13.04	0.00
RAMP D																
STA 2+89.00	TO	STA 19+51.00	16	8	4	5,170.67	2,954.67	2,216.00	1.96	10.34	2.25	1.50	2.00	372.29	248.19	248.19
STA 19+51.00	TO	STA 19+76.00	16	8	4	77.77	44.44	33.33	0.03	0.16	2.25	1.50	2.00	5.60	3.73	3.73

PLOT DATE = 08/15/2007 08:15:22AM  
 FILE NAME = c:\p\projects\4652882\shsch.dgn  
 PLOT SCALE = 1/8"=1'-0" / IN.  
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)  
 SECTION D6 INTERSTATE RS,BR,M CAB 2008  
 SANGAMON COUNTY  
 SCALE: \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 DATE \_\_\_\_\_ CHECKED BY \_\_\_\_\_