

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	43
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)				
** D6 INTERSTATE RS,BR,M CAB 2008				

CLASS B PATCHING SCHEDULE (I-55)											
LOCATION	DL (FOOT)	LENGTH ML (FOOT)	PL (FOOT)	WIDTH (FOOT)	CL B 16" TY II (SQ YD)	CL B 16" TY III (SQ YD)	CL B 16" TY IV (SQ YD)	SAW CUTS (FOOT)	DOWEL BARS (EACH)	TIE BARS (EACH)	PAVT FABRIC (SQ YD)
NORTHBOUND I-55											
STA 32+00	12.0			12.0		16.00		60.0	20		16.00
STA 32+00			12.0	12.0		16.00		60.0	20		16.00
STA 34+90	12.0			12.0		16.00		60.0	20		16.00
STA 34+90			12.0	12.0		16.00		60.0	20		16.00
STA 58+00	9.0			12.0	12.00			54.0	20		
STA 59+00	10.0			12.0	13.33			56.0	20		
STA 67+00	6.0			12.0	8.00			48.0	20		
STA 71+25	9.0			12.0	12.00			54.0	20		
STA 71+25		6.0		12.0	8.00			48.0	20		
STA 71+25			6.0	12.0	8.00			48.0	20		
STA 73+00			6.0	12.0	8.00			48.0	20		
STA 73+00		6.0		12.0	8.00			48.0	20		
STA 84+00	6.0			12.0	8.00			48.0	20		
STA 84+30	8.0			12.0	10.67			52.0	20		
STA 87+00	6.0			12.0	8.00			48.0	20		
STA 95+05	6.0			12.0	8.00			48.0	20		
STA 98+00	8.0			12.0	10.67			52.0	20		
STA 98+00			6.0	12.0	8.00			48.0	20		
STA 101+00	6.0			12.0	8.00			48.0	20		
STA 117+50	8.0			12.0	10.67			52.0	20		
STA 126+50	10.0			12.0	13.33			56.0	20		
STA 127+55	15.0			12.0		20.00		66.0	20		20.00
STA 127+65			8.0	12.0	10.67			52.0	20		
STA 131+00	6.0			12.0	8.00			48.0	20		
STA 131+00			6.0	12.0	8.00			48.0	20		
STA 138+70	6.0			12.0	8.00			48.0	20		
STA 139+00	19.0			12.0			25.33	74.0	20		25.33
STA 144+00	38.0			12.0			50.67	112.0	20	19.0	50.67
STA 147+40	6.0			12.0	8.00			48.0	20		
STA 155+00	8.0			12.0	10.67			52.0	20		
STA 167+00			8.0	12.0	10.67			52.0	20		
STA 172+00	8.0			12.0	10.67			52.0	20		
STA 172+00			8.0	12.0	10.67			52.0	20		
STA 194+80	10.0			12.0	13.33			56.0	20		
STA 195+00	6.0			12.0	8.00			48.0	20		
STA 196+00	16.0			12.0		21.33		68.0	20		21.33
STA 197+45	6.0			12.0	8.00			48.0	20		
STA 197+45			6.0	12.0	8.00			48.0	20		
STA 200+00	20.0			12.0		26.67		76.0	20	10.0	26.67
STA 200+40	6.0			12.0	8.00			48.0	20		
STA 202+20	6.0			12.0	8.00			48.0	20		
STA 203+10	25.0			12.0		33.33		86.0	20	13.0	33.33
STA 204+90			8.0	12.0	10.67			52.0	20		
STA 207+00	10.0			12.0	13.33			56.0	20		
STA 209+00	6.0			12.0	8.00			48.0	20		
STA 209+80	15.0			12.0		20.00		66.0	20		20.00
STA 209+80			8.0	12.0	10.67			52.0	20		
STA 212+00	15.0			12.0		20.00		66.0	20		20.00
STA 219+00	25.0			12.0		33.33		86.0	20	13.0	33.33
STA 219+00			15.0	12.0		20.00		66.0	20		20.00
STA 219+80	6.0			12.0	8.00			48.0	20		
STA 219+80			6.0	12.0	8.00			48.0	20		
STA 222+10	7.0			12.0	9.33			50.0	20		
STA 229+00	6.0			12.0	8.00			48.0	20		
STA 229+00			6.0	12.0	8.00			48.0	20		
STA 230+00	20.0			12.0		26.67		76.0	20	10.0	26.67

PLOT DATE = 08/15/2007 08:15:28AM
 FILE NAME = c:\p\projects\4652882\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY
 SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____