

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	45
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)				
** D6 INTERSTATE RS,BR,M CAB 2008				

CLASS B PATCHING SCHEDULE (I-55)											
LOCATION	LENGTH			WIDTH (FOOT)	CL B 16"			SAW CUTS (FOOT)	DOWEL BARS (EACH)	TIE BARS (EACH)	PAVT FABRIC (SQ YD)
	DL (FOOT)	ML (FOOT)	PL (FOOT)		TY II (SQ YD)	TY III (SQ YD)	TY IV (SQ YD)				
SOUTHBOUND I-55											
STA 250+00	8.0			12.0	10.67			52.0	20		
STA 234+00	14.0			12.0		18.67		64.0	20		18.67
STA 234+00			14.0	12.0		18.67		64.0	20		18.67
STA 210+80	6.0			12.0	8.00			48.0	20		
STA 208+00	16.0			12.0		21.33		68.0	20		21.33
STA 208+00			12.0	12.0		16.00		60.0	20		16.00
STA 207+00	10.0			12.0	13.33			56.0	20		
STA 202+70	16.0			12.0		21.33		68.0	20		21.33
STA 162+00	8.0			12.0	10.67			52.0	20		
STA 162+00			12.0	12.0		16.00		60.0	20		16.00
STA 156+10	6.0			12.0	8.00			48.0	20		
STA 138+00	12.0			12.0		16.00		60.0	20		16.00
STA 136+20	14.0			12.0		18.67		64.0	20		18.67
STA 127+20	6.0			12.0	8.00			48.0	20		
STA 126+70			7.0	12.0	9.33			50.0	20		
STA 122+45	6.0			12.0	8.00			48.0	20		
STA 122+45			10.0	12.0	13.33			56.0	20		
STA 116+00	6.0			12.0	8.00			48.0	20		
STA 116+00			6.0	12.0	8.00			48.0	20		
STA 112+00	6.0			12.0	8.00			48.0	20		
STA 99+00	10.0			12.0	13.33			56.0	20		
STA 99+00			6.0	12.0	8.00			48.0	20		
STA 98+00	6.0			12.0	8.00			48.0	20		
STA 98+00			6.0	12.0	8.00			48.0	20		
STA 94+00	6.0			12.0	8.00			48.0	20		
STA 94+00			6.0	12.0	8.00			48.0	20		
STA 91+00	6.0			12.0	8.00			48.0	20		
STA 91+00			6.0	12.0	8.00			48.0	20		
STA 86+00	8.0			12.0	10.67			52.0	20		
STA 86+00		8.0		12.0	10.67			52.0	20		
STA 86+00			8.0	12.0	10.67			52.0	20		
STA 79+50	8.0			12.0	10.67			52.0	20		
STA 79+50		8.0		12.0	10.67			52.0	20		
STA 75+10			6.0	12.0	8.00			48.0	20		
STA 63+00	10.0			12.0	13.33			56.0	20		
STA 59+00	6.0			12.0	8.00			48.0	20		
STA 59+00			6.0	12.0	8.00			48.0	20		
STA 55+70	10.0			12.0	13.33			56.0	20		
STA 55+70			10.0	12.0	13.33			56.0	20		
STA 50+60	8.0			12.0	10.67			52.0	20		
STA 50+60			8.0	12.0	10.67			52.0	20		
STA 31+50	6.0			12.0	8.00			48.0	20		
STA 31+00	6.0			12.0	8.00			48.0	20		
STA 31+00			6.0	12.0	8.00			48.0	20		
STA 28+00			7.0	12.0	9.33			50.0	20		
STA 27+50			8.0	12.0	10.67			52.0	20		
STA 25+50	6.0			12.0	8.00			48.0	20		
STA 25+50			6.0	12.0	8.00			48.0	20		
STA 16+40	6.0			12.0	8.00			48.0	20		
STA 16+40			6.0	12.0	8.00			48.0	20		
STA 15+50	8.0			12.0	10.67			52.0	20		
STA 15+50			8.0	12.0	10.67			52.0	20		
STA 14+60			14.0	12.0		18.67		64.0	20		18.67
STA 13+50		6.0		12.0	8.00			48.0	20		
STA 13+50			6.0	12.0	8.00			48.0	20		
TOTALS					1,124.00	700.00	314.66	9,220	3,340	101	1,014.66

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY

SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____

PLOT DATE = 08/15/2007 08:15:30AM
 FILE NAME = c:\p\projects\4652882\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1