

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	48

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

\* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)  
 \*\* D6 INTERSTATE RS,BR,M CAB 2008

CLASS B PATCHING SCHEDULE ( STEVENSON DRIVE INTERCHANGE RAMP)

LOCATION		LENGTH ( FOOT )	WIDTH ( FOOT )	CL B 13" TY I ( SQ YD )	CL B 13" TY II ( SQ YD )	SAW CUTS ( FOOT )	DOWEL BARS ( EACH )	TIE BARS ( EACH )	PAVT FABRIC ( SQ YD )	
RAMP A										
STA 2+00	LEFT	6.0	9.0		6.00	39.0	16	3		
STA 2+00	RIGHT	6.0	7.0	4.67		33.0	16	3		
STA 6+00	LEFT	6.0	9.0		6.00	39.0	16	3		
STA 6+00	RIGHT	6.0	7.0	4.67		33.0	16	3		
STA 11+00	LEFT	6.0	9.0		6.00	39.0	16	3		
STA 11+00	RIGHT	6.0	7.0	4.67		33.0	16	3		
RAMP C										
STA 5+00	LEFT	6.0	9.0		6.00	39.0	16	3		
STA 5+00	RIGHT	6.0	7.0	4.67		33.0	16	3		
STA 5+20	LEFT	8.0	9.0		8.00	43.0	16	4		
STA 5+20	RIGHT	8.0	7.0		6.22	37.0	16	4		
RAMP D										
STA 9+00	LEFT	6.0	9.0		6.00	39.0	16			
STA 9+00	RIGHT	6.0	7.0	4.67		33.0	16			
STA 11+00	LEFT	8.0	9.0		8.00	43.0	16	4		
STA 11+00	RIGHT	8.0	7.0		6.22	37.0	16	4		
STA 11+50	LEFT	7.0	9.0		7.00	41.0	16			
STA 11+50	RIGHT	7.0	7.0		5.44	35.0	16			
TOTALS					23.35	70.88	596.0	256	40	0

CLASS B PATCHING SCHEDULE ( SOUTH GRAND INTERCHANGE RAMP)

LOCATION		LENGTH ( FOOT )	WIDTH ( FOOT )	CL B 13" TY I ( SQ YD )	CL B 13" TY II ( SQ YD )	CL B 13" TY III ( SQ YD )	SAW CUTS ( FOOT )	DOWEL BARS ( EACH )	TIE BARS ( EACH )	PAVT FABRIC ( SQ YD )	
RAMP D											
STA 17+00	LEFT	6.0	9.0		6.00		39.0	16	3		
STA 17+00	RIGHT	6.0	7.0	4.67			33.0	16	3		
STA 18+00	LEFT	6.0	9.0		6.00		39.0	16	3		
STA 18+00	RIGHT	6.0	7.0	4.67			33.0	16	3		
RAMP E											
STA 7+25	LEFT	6.0	9.0		6.00		39.0	16	3		
STA 7+25	RIGHT	6.0	7.0	4.67			33.0	16	3		
RAMP H											
STA 20+00	LEFT	20.0	9.0			20.00	67.0	16	10	20.00	
STA 20+00	RIGHT	20.0	7.0			15.56	61.0	16	10	15.56	
STA 23+00	LEFT	6.0	9.0		6.00		39.0	16			
STA 23+00	RIGHT	6.0	7.0	4.67			33.0	16			
STA 27+50	LEFT	8.0	9.0		8.00		43.0	16			
STA 27+50	RIGHT	8.0	7.0		6.22		37.0	16			
TOTALS					18.68	38.22	35.56	496.0	192	38	35.56

PLOT DATE = 08/15/2007 08:15:32AM  
 FILE NAME = c:\p\projects\4652882\shsch.dgn  
 PLOT SCALE = 1/8"=1'-0" / IN.  
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)  
 SECTION D6 INTERSTATE RS,BR,M CAB 2008  
 SANGAMON COUNTY

SCALE: \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 DATE \_\_\_\_\_ CHECKED BY \_\_\_\_\_