

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	49

STA. TO STA.  
 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT  
 \* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)  
 \*\* D6 INTERSTATE RS,BR,M CAB 2008

CLASS B PATCHING SCHEDULE (CLEAR LAKE INTERCHANGE RAMPS)

LOCATION		LENGTH (FOOT)	WIDTH (FOOT)	CL B 13" TY I (SQ YD)	CL B 13" TY II (SQ YD)	CL B 13" TY III (SQ YD)	SAW CUTS (FOOT)	DOWEL BARS (EACH)	TIE BARS (EACH)	PAVT FABRIC (SQ YD)	
RAMP B											
STA 4+25	LEFT	6.0	9.0		6.00		39.0	16	3		
STA 4+25	RIGHT	6.0	7.0	4.67			33.0	16	3		
STA 5+25	LEFT	6.0	9.0		6.00		39.0	16	3		
STA 5+25	RIGHT	6.0	7.0	4.67			33.0	16	3		
STA 7+00	LEFT	6.0	9.0		6.00		39.0	16	3		
STA 7+00	RIGHT	6.0	7.0	4.67			33.0	16	3		
STA 14+00	LEFT	7.0	9.0		7.00		41.0	16	4		
STA 14+00	RIGHT	7.0	7.0		5.44		35.0	16	4		
RAMP C											
STA 5+00	LEFT	6.0	9.0		6.00		39.0	16	3		
STA 5+00	RIGHT	6.0	7.0	4.67			33.0	16	3		
RAMP D											
STA 14+40	LEFT	6.0	9.0		6.00		39.0	16	3		
STA 14+40	RIGHT	6.0	7.0	4.67			33.0	16	3		
STA 21+00	LEFT	6.0	9.0		6.00		39.0	16	3		
STA 21+00	RIGHT	6.0	7.0	4.67			33.0	16	3		
STA 21+50	LEFT	6.0	9.0		6.00		39.0	16	3		
STA 21+50	RIGHT	6.0	7.0	4.67			33.0	16	3		
RAMP E											
STA 14+00	LEFT	7.0	9.0		7.00		41.0	16	4		
STA 14+00	RIGHT	7.0	7.0		5.44		35.0	16	4		
RAMP F											
STA 4+50	LEFT	8.0	9.0		8.00		43.0	16	4		
STA 4+50	RIGHT	8.0	7.0		6.22		37.0	16	4		
STA 7+30	LEFT	20.0	9.0			20.00	67.0	16	10	20.00	
STA 7+30	RIGHT	20.0	7.0			15.56	61.0	16	10	15.56	
STA 9+80	LEFT	8.0	9.0		8.00		43.0	16	4		
STA 9+80	RIGHT	8.0	7.0		6.22		37.0	16	4		
STA 11+50	LEFT	6.0	9.0		6.00		39.0	16	3		
STA 11+50	RIGHT	6.0	7.0	4.67			33.0	16	3		
STA 15+25	LEFT	12.0	9.0		12.00		51.0	16	6		
STA 15+25	RIGHT	12.0	7.0		9.33		45.0	16	6		
RAMP G											
STA 3+00	LEFT	7.0	9.0		7.00		41.0	16	4		
STA 3+00	RIGHT	7.0	7.0		5.44		35.0	16	4		
RAMP H											
STA 9+75	LEFT	6.0	9.0		6.00		39.0	16	3		
STA 9+75	RIGHT	6.0	7.0	4.67			33.0	16	3		
STA 12+75	LEFT	8.0	9.0		8.00		43.0	16	4		
STA 12+75	RIGHT	8.0	7.0		6.22		37.0	16	4		
STA 16+00	LEFT	7.0	9.0		7.00		41.0	16	4		
STA 16+00	RIGHT	7.0	7.0		5.44		35.0	16	4		
STA 19+00	LEFT	7.0	9.0		7.00		41.0	16	4		
STA 19+00	RIGHT	7.0	7.0		5.44		35.0	16	4		
TOTALS					42.03	180.19	35.56	1,492.0	608	150	35.56

PLOT DATE = 08/15/2007 08:15:33AM  
 FILE NAME = c:\p\projects\652882\shsch.dgn  
 PLOT SCALE = 1/8"=1'-0" / IN.  
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)  
 SECTION D6 INTERSTATE RS,BR,M CAB 2008  
 SANGAMON COUNTY  
 SCALE: DRAWN BY  
 DATE CHECKED BY