CONTRACT NO. 72659

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	55
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI55(I-55), FAI72(I-72), FAP666(I-55 BUS)
** D6 INTERSTATE RS,BR,M CAB 2008

MAINTENANCE MOWING

LOCATION				LENGTH (FOOT)	WIDTH (FOOT)	AREA (ACRES)	NUMBER OF MOWINGS	TOTAL AREA (ACRES)
I-72 MAINLINE								
EASTBOUND								
	STA 627+00.00	TO	STA 635+79.29 BK	879.29	35	0.71	2	1.42
	STA 634+03.49 AH	TO	STA 694+78.00	6,074.51	35	4.88	2	9.76
WESTBOUND								
	STA 627+00.00	TO	STA 635+79.29 BK	879.29	35	0.71	2	1.42
	STA 634+03.49 AH	TO	STA 688+96.00	5,492.51	35	4.41	2	8.82
I-55 BUSINESS LOOP								
NORTHBOUND	STA 29+74.00	TO	STA 63+50.00	3,376.00	35	2.71	2	5.42
SOUTHBOUND	STA 34+96.00	TO	STA 63+50.00	2,854.00	35	2.29	2	4.58
I-55 MAINLINE								
NORTHBOUND								
	STA 9+97.00	TO	STA 128+87.38 BK	11,890.38	35	9.55	2	19.10
	STA 128+91.29 AH	TO	STA 233+44.43 BK	10,453.14	35	8.40	2	16.80
	STA 233+52.70 AH	TO	STA 355+49.48 BK	12,196.78	35	9.80	2	19.60
	STA 695+67.32 AH	TO	STA 693+00.00	267.32	35	0.21	2	0.42
SOUTHBOUND								
	STA 13+59.00	TO	STA 86+63.86 BK	7,304.86	35	5.87	2	11.74
	STA 82+99.33 AH	TO	STA 128+87.38 BK	4,588.05	35	3.69	2	7.38
	STA 128+91.29 AH	TO	STA 233+44.43 BK	10,453.14	35	8.40	2	16.80
	STA 233+52.70 AH	TO	STA 355+49.48 BK	12,196.78	35	9.80	2	19.60
	STA 695+67.32 AH	TO	STA 693+00.00	267.32	35	0.21	2	0.42
SIXTH STREET INTERCHANGE								
RAMP A	STA 6+62.40	TO	STA 26+12.00	1,949.60	30	1.34	2	2.68
RAMP B	STA 6+42.00	TO	STA 17+74.00	1,132.00	30	0.78	2	1.56
RAMP C	STA 4+01.00	TO	STA 13+72.00	971.00	30	0.67	2	1.34
RAMP D	STA 6+57.00	TO	STA 13+72.00	715.00	30	0.49	2	0.98
SW LOOP RAMP	STA 4+56.00	TO	STA 17+89.00	1,333.00	30	0.92	2	1.84
NE RAMP	STA 6+85.00	TO	STA 18+90.00	1,205.00	30	0.83	2	1.66
STEVENSON DRIVE								
RAMP A	STA 6+68.00	TO	STA 16+77.00	1,009.00	30	0.69	2	1.38
RAMP B	STA 1+21.00	TO	STA 7+56.00	635.00	30	0.44	2	0.88
RAMP C	STA 4+84.00	TO	STA 13+46.00	862.00	30	0.59	2	1.18
RAMP D	STA 1+03.00	TO	STA 11+24.00	1,021.00	30	0.70	2	1.40
SOUTH GRAND AVE.								
RAMP A	STA 4+25.00	TO	STA 11+02.00	677.00	30	0.47	2	0.94
RAMP B	STA 6+21.00	TO	STA 18+92.00	1,271.00	30	0.88	2	1.76
RAMP C	STA 4+35.00	TO	STA 17+10.00	1,275.00	30	0.88	2	1.76
RAMP D	STA 2+89.00	TO	STA 19+76.00	1,687.00	30	1.16	2	2.32
RAMP E	STA 4+38.00	TO	STA 10+28.00	590.00	30	0.41	2	0.82
RAMP F	STA 4+21.00	TO	STA 15+00.00	1,079.00	30	0.74	2	1.48
RAMP G	STA 4+75.00	TO	STA 16+20.00	1,145.00	30	0.79	2	1.58
RAMP H	STA 3+13.00	TO	STA 20+52.00	1,739.00	30	1.20	2	2.40
CLEAR LAKE AVE.								
RAMP A	STA 3+69.00	TO	STA 13+88.00	1,019.00	30	0.70	2	1.40
RAMP B	STA 6+35.00	TO	STA 21+33.00	1,498.00	30	1.03	2	2.06
RAMP C	STA 3+92.00	TO	STA 11+85.00	793.00	30	0.55	2	1.10
RAMP D	STA 3+20.00	TO	STA 16+86.00	1,366.00	30	0.94	2	1.88
RAMP E	STA 3+79.00	TO	STA 13+90.00	1,011.00	30	0.70	2	1.40
RAMP F	STA 6+54.00	TO	STA 21+89.00	1,535.00	30	1.06	2	2.12
RAMP G	STA 3+92.00	TO	STA 11+74.00	782.00	30	0.54	2	1.08
RAMP H	STA 3+36.00	TO	STA 16+79.00	1,343.00	30	0.92	2	1.84
TOTAL								184.12

CLEANING UNDERDRAIN OUTLETS

LOCATION				EACH
I-55 MAINLINE				
STA 9+97	TO	STA 170+00		128
STA 170+00	TO	STA 250+00		64
STA 250+00	TO	STA 286+00		14
STA 286+00	TO	STA 355+49		56
I-72 MAINLINE				
STA 626+20	TO	STA 695+00		56
6TH ST INTERCHANGE				36
STEVENSON DRIVE INTERCHANGE RAMPS				24
SOUTH GRAND INTERCHANGE RAMPS				48
CLEAR LAKE INTERCHANGE RAMPS				48
TOTAL				474

QUANTITIES ARE ESTIMATED, ASSUMING 500'
SPACING OF UNDERDRAIN OUTLETS

OUTLET MARKERS

LOCATION				EACH
I-55 MAINLINE				
STA 9+97	TO	STA 170+00		128
STA 170+00	TO	STA 250+00		64
STA 250+00	TO	STA 286+00		14
STA 286+00	TO	STA 355+49		56
I-72 MAINLINE				
STA 626+20	TO	STA 695+00		56
6TH ST INTERCHANGE				36
STEVENSON DRIVE INTERCHANGE RAMPS				24
SOUTH GRAND INTERCHANGE RAMPS				48
CLEAR LAKE INTERCHANGE RAMPS				48
TOTAL				474

QUANTITIES ARE ESTIMATED, ASSUMING 500'
SPACING OF UNDERDRAIN OUTLETS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAI55(I-55), FAI72(I-72), FAP666(I-55 BUS)
SECTION D6 INTERSTATE RS,BR,M CAB 2008
SANGAMON COUNTY

SCALE: DRAWN BY
DATE CHECKED BY

PLOT DATE = Oct-22-2007 08:19:36AM
FILE NAME = c:\Projects\d652882\sht sch.dgn
PLOT SCALE = 100.0000 ' / IN.
USER NAME = Laughlur1