

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	56

STA. TO STA.  
 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT  
 \* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)  
 \*\* D6 INTERSTATE RS,BR,M CAB 2008

GUARDRAIL SCHEDULE

LOCATION	GR REM (FOOT)	R & R SPBGR (FOOT)	SPBGR TYPE A (FOOT)	TRAFFIC BARRIER TERMINAL				TERM MK DA (EACH)	GR MARK (EACH)
				TY 1	SP (T) (EACH)	TY 2 (EACH)	TY 5 (EACH)		
I-55 MAINLINE									
NORTHBOUND									
1	RT STA 23+05	TO STA 23+55			1			1	
	RT STA 23+55	TO STA 24+18	62.5						2
	RT STA 24+18	TO STA 24+30					1		
2	RT STA 58+41	TO STA 61+29	50.0	237.5	50.0				5
3	LT STA 62+50	TO STA 63+00				1		1	
	LT STA 63+00	TO STA 77+75	50.0		1,475.0				20
	LT STA 77+75	TO STA 92+63	25.0	1,462.5	25.0				20
4	RT STA 80+60	TO STA 83+48	37.5		37.5				5
5	RT STA 121+50	TO STA 127+38		587.5					9
6	RT STA 156+25	TO STA 173+00	50.0	1,625.0	50.0				22
7	LT STA 165+15	TO STA 167+15	200.0						
8	LT STA 170+34	TO STA 172+47	212.5						
9	LT STA 182+80	TO STA 184+18	137.5						
10	RT STA 256+24	TO STA 256+74	50.0			1		1	
	RT STA 256+74	TO STA 260+11	25.0	312.5	25.0				6
11	LT STA 289+10	TO STA 290+23	112.5						
12	RT STA 303+60	TO STA 306+60		300.0					5
13	LT STA 305+35	TO STA 306+73	137.5						
14	LT STA 317+54	TO STA 318+67	112.5						
15	RT STA 331+10	TO STA 331+60	50.0			1		1	
	RT STA 331+60	TO STA 334+60		300.0					5
16	LT STA 331+70	TO STA 334+33	262.5						
17	LT STA 346+29	TO STA 348+17	187.5						
SOUTHBOUND									
18	RT STA 24+18	TO STA 24+31						1	
	RT STA 24+31	TO STA 24+93			62.5				2
	RT STA 24+93	TO STA 25+43				1		1	
19	RT STA 41+39	TO STA 44+26		287.5					5
20	LT STA 41+99	TO STA 45+24	25.0	300.0	25.0				6
21	LT STA 58+17	TO STA 60+80		262.5					5
	LT STA 60+80	TO STA 61+30	50.0			1		1	
22	RT STA 59+48	TO STA 62+60	25.0	287.5	25.0				5
23	LT STA 71+69	TO STA 74+81	25.0	287.5	25.0				5
	LT STA 74+81	TO STA 75+31	50.0			1		1	
24	LT STA 70+56	TO STA 70+68							1
	LT STA 70+68	TO STA 81+93	50.0		1,125.0				16
	LT STA 81+93	TO STA 92+78		1,450.0					20
25	LT STA 83+60	TO STA 88+48		487.5					8
26	LT STA 124+73	TO STA 131+02	37.5	587.5	37.5				9
27	LT STA 159+93	TO STA 160+05	12.5					1	
	LT STA 160+05	TO STA 163+05	50.0	250.0	50.0				5
	LT STA 163+05	TO STA 163+55	50.0			1		1	
28	LT STA 166+32	TO STA 174+19	75.0	712.5	75.0				11
29	RT STA 171+55	TO STA 171+68						1	
	RT STA 171+68	TO STA 173+18		150.0					3
	RT STA 173+18	TO STA 173+68	50.0			1		1	
30	RT STA 183+88	TO STA 184+75		87.5					3
31	LT STA 230+98	TO STA 260+69	87.5	2,875.0	87.5				39
32	LT STA 265+63	TO STA 270+00		437.5					7
	LT STA 270+00	TO STA 270+50	50.0			1		1	
33	RT STA 290+01	TO STA 290+51		50.0					2
	RT STA 290+51	TO STA 291+01	50.0			1		1	
34	LT STA 306+38	TO STA 309+00		262.5					5
35	RT STA 306+47	TO STA 307+22		75.0					2
	RT STA 307+22	TO STA 307+72	50.0			1		1	
36	RT STA 318+05	TO STA 318+17							
	RT STA 318+17	TO STA 318+92		50.0	25.0			1	2
	RT STA 318+92	TO STA 319+42				1		1	

PLOT DATE = 08/15/2007 08:15:37AM  
 FILE NAME = c:\p\projects\652882\shsch.dgn  
 PLOT SCALE = 1/8"=1'-0" / IN.  
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)  
 SECTION D6 INTERSTATE RS,BR,M CAB 2008  
 SANGAMON COUNTY  
 SCALE: DRAWN BY  
 DATE CHECKED BY