

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	57
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS) ** D6 INTERSTATE RS,BR,M CAB 2008				

GUARDRAIL SCHEDULE

LOCATION	GR REM (FOOT)	R & R SPBGR (FOOT)	SPBGR TYPE A (FOOT)	TRAFFIC BARRIER TERMINAL				TERM MK DA (EACH)	GR MARK (EACH)
				TY 1 SP (T) (EACH)	TY 2 (EACH)	TY 5 (EACH)	TY 6 (EACH)		
37 LT STA 331+28 TO STA 335+28	25.0	375.0	25.0						6
LT STA 335+28 TO STA 335+78	50.0			1			1		
38 RT STA 332+75 TO STA 332+87	12.5				1				
RT STA 332+87 TO STA 334+75	187.5		187.5						4
RT STA 334+75 TO STA 335+25	50.0			1			1		
I-72 MAINLINE									
EASTBOUND									
39 RT STA 645+38 TO STA 645+88	50.0			1			1		
RT STA 645+88 TO STA 648+00		212.5							4
40 RT STA 670+44 TO STA 670+94	50.0			1			1		
RT STA 670+94 TO STA 672+69	175.0		175.0						4
RT STA 672+69 TO STA 673+14	45.5						1		
41 LT STA 671+64 TO STA 673+14	150.0								
LT STA 668+81 TO STA 669+31				1			1		
LT STA 669+31 TO STA 672+69			337.5						6
LT STA 672+69 TO STA 673+14							1		
WESTBOUND									
44 LT STA 647+84 TO STA 649+97		212.5							4
LT STA 649+97 TO STA 650+47	50.0			1			1		
45 LT STA 675+03 TO STA 676+86	183.0								
LT STA 675+03 TO STA 675+48							1		
LT STA 675+48 TO STA 676+36			87.5						3
LT STA 676+36 TO STA 676+86				1			1		
46 RT STA 675+03 TO STA 676+58	155.5								
RT STA 675+03 TO STA 675+48							1		
RT STA 675+48 TO STA 678+86			337.5						6
RT STA 678+86 TO STA 679+36				1			1		
BL-55									
SOUTHBOUND									
51 LT STA 55+62 TO STA 57+24		162.5							4
LT STA 57+24 TO STA 57+74	50.0			1			1		
SIXTH ST INTERCHANGE									
RAMP B									
52 LT STA 8+50 TO STA 9+00				1			1		
LT STA 9+00 TO STA 12+00			300.0						5
LT STA 12+00 TO STA 12+13							1		
53 RT STA 17+70 TO STA 18+20	50.0			1			1		
RT STA 18+20 TO STA 20+33	25.0	187.5	25.0						4
RAMP C									
54 LT STA 9+16 TO STA 9+79		62.5							2
NORTHEAST RAMP									
55 RT STA 0+86 TO STA 3+24		237.5							4
56 LT STA 12+77 TO STA 14+27		150.0							3
SOUTH GRAND INTERCHANGE									
RAMP A									
57 RT STA 10+35 TO STA 10+85	50.0			1			1		
RT STA 10+85 TO STA 12+48		162.5							4
RAMP C									
59 LT STA 5+05 TO STA 5+55	50.0			1			1		
LT STA 5+55 TO STA 8+18		262.5							5
RAMP D									
60 LT STA 13+90 TO STA 14+40	50.0			1			1		
LT STA 14+40 TO STA 18+78		437.5							7
61 RT STA 15+84 TO STA 22+09		625.0							9
RAMP E									
62 RT STA 10+40 TO STA 12+02		162.5							4
RAMP F									
63 RT STA 0+65 TO STA 0+78	13.5					1			
RT STA 0+78 TO STA 12+16	25.0	1,112.5	25.0						16
64 LT STA 5+34 TO STA 5+84	50.0			1			1		
LT STA 5+84 TO STA 8+97		312.5							5

PLOT DATE = 08/15/2007 08:15:38AM
 FILE NAME = c:\p\projects\652882\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY
 SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____