

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	59
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)				
** D6 INTERSTATE RS,BR,M CAB 2008				

DELINEATORS

LOCATION	SPACING (FOOT)	CURVE TOTAL (EACH)	ADVANCE TOTAL (EACH)	BEYOND TOTAL (EACH)	TOTAL (EACH)
I-72 MAINLINE					
EASTBOUND					
LT STA 640+55	MEDIAN CROSSOVER		3		3
RT STA 688+91	TO STA 694+78	150	4		4
WESTBOUND					
RT STA 640+55	MEDIAN CROSSOVER		3		3
I-55 MAINLINE					
NORTHBOUND					
RT STA 15+55	MEDIAN CROSSOVER		3		3
RT STA 99+02	TO STA 109+05	150	7	3	13
LT STA 117+40	MEDIAN CROSSOVER		3		3
SOUTHBOUND					
RT STA 117+40	MEDIAN CROSSOVER		3		3
LT STA 34+95	TO STA 41+39	175	4		4
LT STA 45+24	TO STA 51+90	175	4		4
SIXTH STREET INTERCHANGE					
RAMP A					
RT STA 0+00	TO STA 6+62	100	7	3	13
LT STA 6+62	TO STA 11+58	70	8	3	11
LT STA 22+28	TO STA 26+12	70	6	3	9
RT STA 28+28	TO STA 37+78	100	10		10
RAMP C					
LT STA 4+01	TO STA 13+72	40	25		25
RAMP D					
LT STA 6+62	TO STA 13+72	65	11		11
RT STA 15+16	TO STA 25+38	100	11	3	17
SW LOOP RAMP					
RT STA 0+00	TO STA 3+15	100	4	3	7
LT STA 4+65	TO STA 17+89	50	27		27
NE RAMP					
RT STA 0+00	TO STA 6+63	100	7	3	13
LT STA 6+85	TO STA 9+50	50	6		6
RT STA 13+57	TO STA 16+04	40	7	3	13
STEVENS ON DRIVE INTERCHANGE					
RAMP A					
RT STA 0+00	TO STA 6+53	100	7	3	13
LT STA 6+68	TO STA 11+14	75	6	3	9
RT STA 13+50	TO STA 15+55	40	6	3	12
RAMP B					
LT STA 2+39	TO STA 7+56	30	18	3	21
RAMP C					
LT STA 8+00	TO STA 12+03	35	12	3	15
RAMP D					
RT STA 2+49	TO STA 5+38	50	6	3	12
LT STA 7+60	TO STA 11+24	55	7	3	10
RT STA 11+92	TO STA 23+30	100	12	3	18

DELINEATORS

LOCATION	SPACING (FOOT)	CURVE TOTAL (EACH)	ADVANCE TOTAL (EACH)	BEYOND TOTAL (EACH)	TOTAL (EACH)
SOUTH GRAND INTERCHANGE					
RAMP A					
LT STA 4+25	TO STA 11+02	30	23		23
RAMP B					
RT STA 0+00	TO STA 6+62	100	7	3	13
LT STA 6+62	TO STA 18+92	75	17		17
RAMP C					
LT STA 4+35	TO STA 17+10	40	32		32
RAMP D					
LT STA 2+89	TO STA 8+55	55	11	3	14
RT STA 10+86	TO STA 15+17	55	8	3	11
RAMP E					
LT STA 4+38	TO STA 10+28	30	20		20
RAMP F					
LT STA 4+22	TO STA 5+34	75	2		2
LT STA 9+09	TO STA 15+00	75	8		8
RAMP G					
LT STA 4+75	TO STA 16+20	40	29		29
RAMP H					
LT STA 3+13	TO STA 7+67	55	9	3	12
RT STA 9+97	TO STA 13+34	55	7	3	13
LT STA 15+89	TO STA 20+52	75	7	3	10
RT STA 21+70	TO STA 31+12	100	10	3	16
CLEAR LAKE INTERCHANGE					
RAMP A					
LT STA 3+69	TO STA 13+88	40	26		26
RAMP B					
RT STA 0+00	TO STA 6+62	100	7	3	13
LT STA 6+62	TO STA 14+46	75	11		11
RT STA 14+67	TO STA 16+47	50	4	3	10
LT STA 18+64	TO STA 21+33	50	6	3	9
RAMP C					
LT STA 3+92	TO STA 11+85	35	23		23
RAMP D					
LT STA 3+20	TO STA 16+86	75	19		19
RT STA 18+13	TO STA 27+43	100	10	3	16
RAMP E					
LT STA 3+79	TO STA 13+90	40	26		26
RAMP F					
RT STA 0+00	TO STA 6+62	100	7	3	13
LT STA 6+62	TO STA 12+22	75	8	3	11
LT STA 18+82	TO STA 21+89	55	6	3	9
RAMP G					
LT STA 3+92	TO STA 11+74	35	23		23
RAMP H					
LT STA 3+36	TO STA 16+79	75	18		18
RT STA 18+93	TO STA 27+44	100	9	3	15
TOTAL		615	87	72	774

PLOT DATE = 08/22/2007 08:15:39AM
 FILE NAME = c:\p\projects\652282\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY
 SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____