

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	60
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)				
** D6 INTERSTATE RS,BR,M CAB 2008				

FENCE SCHEDULE

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	WOVEN WIRE FENCE REM (FOOT)	CHAIN LINK FENCE REM (FOOT)	CHAIN LINK FENCE 4' (FOOT)	TREE REM ACRES (ACRES)	CL 2 SEEDING (ACRES)	MULCH METH 2 (ACRES)
I-72 MAINLINE								
EASTBOUND								
STA 648+10.00 TO STA 654+89.00	679	14	679		679	0.22	0.22	0.22
WESTBOUND								
STA 648+10.00 TO STA 666+68.00	1,858	14	1,858		1,858	0.60	0.60	0.60
BL-55								
NORTHBOUND								
STA 63+14.00 TO STA 69+00.00	586	14	586		586	0.19	0.19	0.19
SOUTHBOUND								
STA 62+62.00 TO STA 69+00.00	638	14	638		638	0.21	0.21	0.21
I-55 MAINLINE								
NORTHBOUND								
STA 14+80.00 TO STA 67+17.00	5,237	14	5,237		5,237	1.68	1.68	1.68
STA 68+10.00 TO STA 83+13.00	1,503	14		1,503	1,503	0.48	0.48	0.48
STA 83+49.00 TO STA 116+00.00	3,251	14		3,251	3,251	1.04	1.04	1.04
STA 116+00.00 TO STA 126+57.00	1,057	14		1,057	1,057	0.34	0.34	0.34
STA 127+18.00 TO STA 128+87.38 BK	169	14		169	169	0.05	0.05	0.05
STA 128+91.29 AH TO STA 138+00.00	909	14		909	909	0.29	0.29	0.29
STA 138+00.00 TO STA 139+00.00	100	50		100	100	0.11	0.11	0.11
STA 139+00.00 TO STA 167+10.00	2,810	14		2,810	2,810	0.90	0.90	0.90
STA 184+00.00 TO STA 233+44.43 BK	4,944	14	4,944		4,944	1.59	1.59	1.59
STA 233+52.70 AH TO STA 260+58.00	2,705	14	2,705		2,705	0.87	0.87	0.87
STA 290+00.00 TO STA 306+40.00	1,640	14		1,640	1,640	0.53	0.53	0.53
STA 306+70.00 TO STA 315+66.00	896	14	896		896	0.29	0.29	0.29
SOUTHBOUND								
STA 14+65.00 TO STA 31+21.00	1,656	14	1,656		1,656	0.53	0.53	0.53
STA 64+19.00 TO STA 70+32.00	613	14	613		613	0.20	0.20	0.20
STA 71+17.00 TO STA 86+63.86 BK	1,547	14		1,547	1,547	0.50	0.50	0.50
STA 82+99.33 AH TO STA 83+56.00	57	14		57	57	0.02	0.02	0.02
STA 83+95.00 TO STA 127+33.00	4,338	14		4,338	4,338	1.39	1.39	1.39
STA 129+16.00 TO STA 152+50.00	2,334	14		2,334	2,334	0.75	0.75	0.75
STA 181+00.00 TO STA 210+68.00	2,968	14		2,968	2,968	0.95	0.95	0.95
STA 290+63.00 TO STA 306+40.00	1,577	14	1,577		1,577	0.51	0.51	0.51
STA 306+70.00 TO STA 314+00.00	730	14	730		730	0.23	0.23	0.23
SIXTH ST INTERCHANGE								
RAMP A								
STA 2+34.00 TO STA 36+20.00	3,386	14	3,386		3,386	1.09	1.09	1.09
RAMP D								
STA 5+03.00 TO STA 16+30.00	1,127	14	1,127		1,127	0.36	0.36	0.36
NE RAMP								
STA 0+00.00 TO STA 18+52.00	1,852	14	1,852		1,852	0.60	0.60	0.60
STEVENSON DRIVE INTERCHANGE								
RAMP A								
STA 7+02.00 TO STA 17+27.00	1,025	14		1,025	1,025	0.33	0.33	0.33
RAMP D								
STA 3+10.00 TO STA 12+51.00	941	14	941		941	0.30	0.30	0.30
SOUTH GRAND INTERCHANGE								
RAMP D								
STA 5+00.00 TO STA 7+30.00	230	14	230		230	0.07	0.07	0.07
RAMP F								
STA 0+00.00 TO STA 15+56.00	1,556	14	1,556		1,556	0.50	0.50	0.50
RAMP H								
STA 3+00.00 TO STA 23+50.00	2,050	14		2,050	2,050	0.66	0.66	0.66
CLEAR LAKE INTERCHANGE								
RAMP D								
STA 5+00.00 TO STA 25+94.00	2,094	14	2,094		2,094	0.67	0.67	0.67
RAMP F								
STA 0+00.00 TO STA 10+55.00	1,055	14	1,055		1,055	0.34	0.34	0.34
TOTAL			34,360	25,758	60,118	19.39	19.39	19.39

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY

SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____

PLOT DATE = 08/22/2007 08:14:00AM
 FILE NAME = c:\p\projects\652822\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1