

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	61

STA. \_\_\_\_\_ TO STA. \_\_\_\_\_  
 FED. ROAD DIST. NO. \_\_\_\_\_ ILLINOIS FED. AID PROJECT  
 \* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)  
 \*\* D6 INTERSTATE RS,BR,M CAB 2008

TRAFFIC CONTROL AND PROTECTION 701411

LOCATION	TOTAL (EACH)
<b>6TH ST INTERCHANGE</b>	
RAMP A ADJACENT TO I-72	1
RAMP A ADJACENT TO BL-55	1
RAMP B ADJACENT TO I-72	1
RAMP B ADJACENT TO BL-55	1
RAMP C ADJACENT TO I-72	1
RAMP C ADJACENT TO BL-55	1
RAMP D ADJACENT TO I-72	1
RAMP D ADJACENT TO BL-55	1
SW LOOP RAMP ADJACENT TO I-72	1
SW LOOP RAMP ADJACENT TO BL-55	1
NE RAMP ADJACENT TO I-72	1
NE RAMP ADJACENT TO BL-55	1
<b>STEVENSON DR INTERCHANGE</b>	
RAMP A ADJACENT TO I-55	1
RAMP B ADJACENT TO I-55	1
RAMP C ADJACENT TO I-55	1
RAMP D ADJACENT TO I-55	1
<b>SOUTH GRAND INTERCHANGE</b>	
RAMP A ADJACENT TO I-55	1
RAMP B ADJACENT TO I-55	1
RAMP C ADJACENT TO I-55	1
RAMP D ADJACENT TO I-55	1
RAMP E ADJACENT TO I-55	1
RAMP F ADJACENT TO I-55	1
RAMP G ADJACENT TO I-55	1
RAMP H ADJACENT TO I-55	1
<b>CLEAR LAKE INTERCHANGE</b>	
RAMP A ADJACENT TO I-55	1
RAMP B ADJACENT TO I-55	1
RAMP C ADJACENT TO I-55	1
RAMP D ADJACENT TO I-55	1
RAMP E ADJACENT TO I-55	1
RAMP F ADJACENT TO I-55	1
RAMP G ADJACENT TO I-55	1
RAMP H ADJACENT TO I-55	1
<b>TOTAL</b>	<b>32</b>

SIGN SCHEDULE

LOCATION	SIGN DESIGNATION	SIGN SPACING (FOOT)	# OF SIGNS	AREA PER SIGN (SQ FT)	POSTS PER SIGN	POST LENGTH (FOOT)	REMOVE SIGN COMPL (EACH)	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	TELE STL SIGN SUPPORT (FOOT)
<b>I-55 MAINLINE</b>										
<b>NORTHBOUND</b>										
STA 42+20 TO STA 49+20	W1-8R( 3648)	100	8	12	2	12	8		96.0	192.0
STA 149+40 TO STA 159+40	W1-8L( 3648)	100	11	12	2	12	11		132.0	264.0
<b>SOUTHBOUND</b>										
STA 51+90 TO STA 59+90	W1-8L( 3648)	100	9	12	2	12	9		108.0	216.0
STA 163+00 TO STA 168+00	W1-8R( 3648)	100	6	12	2	12	6		72.0	144.0
<b>SIXTH STREET INTERCHANGE</b>										
<b>RAMP B</b>										
STA 7+25 TO STA 16+70	W1-8R( 1824)	95	11	3	1	12	11	33.0		132.0
<b>NE RAMP</b>										
STA 9+50 TO STA 11+50	W1-8R( 1824)	40	6	3	1	12	6	18.0		72.0
<b>STEVENSON DRIVE INTERCHANGE</b>										
<b>RAMP C</b>										
STA 5+60 TO STA 8+00	W1-8R( 1824)	50	6	3	1	12	6	18.0		72.0
<b>CLEAR LAKE INTERCHANGE</b>										
<b>RAMP F</b>										
STA 15+50 TO STA 16+75	W1-8L( 1824)	25	6	3	1	12	6	18.0		72.0
<b>TOTAL</b>							<b>63</b>	<b>87.0</b>	<b>408.0</b>	<b>1,164.0</b>

PORTABLE CHANGEABLE MESSAGE SIGN

LOCATION	TYPE OF WORK	NUMBER NEEDED	APPROX DURATION (CAL MO)	TOTAL (CAL MO)
I-55 MAINLINE	ADVANCED WARNING	2	6.0	12
I-72 MAINLINE	ADVANCED WARNING	2	6.0	12
BL-55 MAINLINE	ADVANCED WARNING	1	6.0	6
STEVENSON DR INTERCHANGE	ADVANCED WARNING	2	6.0	12
SOUTH GRAND INTERCHANGE	ADVANCED WARNING	2	6.0	12
CLEAR LAKE INTERCHANGE	ADVANCED WARNING	1	6.0	6
6TH ST INTERCHANGE	SHORT TERM RAMP CLOSURE	2	1.0	2
STEVENSON DR INTERCHANGE	SHORT TERM RAMP CLOSURE	2	0.5	1
SOUTH GRAND INTERCHANGE	SHORT TERM RAMP CLOSURE	2	1.0	2
CLEAR LAKE INTERCHANGE	SHORT TERM RAMP CLOSURE	2	1.0	2
<b>TOTAL</b>				<b>67</b>

PLOT DATE = Nov-19-2007 08:23:02AM  
 FILE NAME = c:\projects\652882\shsch.dgn  
 PLOT SCALE = 1/8"=1'-0" / IN.  
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)  
 SECTION D6 INTERSTATE RS,BR,M CAB 2008  
 SANGAMON COUNTY

SCALE: \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 DATE \_\_\_\_\_ CHECKED BY \_\_\_\_\_