

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	63
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS) ** D6 INTERSTATE RS,BR,M CAB 2008				

URETHANE PAVEMENT MARKING TYPE 2 - LINE 5"

LOCATION	INSIDE EDGE LINE YELLOW (FOOT)	OUTSIDE EDGE LINE WHITE (FOOT)	CENTERLINE SKIP-DASH WHITE (FOOT)	TOTAL LENGTH (FOOT)
RAMP C				
STA 0+00.00	TO	STA 4+01.00	401	401
STA 4+01.00	TO	STA 13+72.00	971	1,942
STA 13+72.00	TO	STA 15+82.37	210	210
STA 17+72.14	TO	STA 21+57.00	385	385
RAMP D				
STA 4+12.72	TO	STA 6+57.00	244	244
STA 6+57.00	TO	STA 13+72.00	715	1,430
STA 13+72.00	TO	STA 25+37.88	1,166	1,166
SW LOOP RAMP				
STA 0+00.00	TO	STA 4+56.00	456	456
STA 4+56.00	TO	STA 17+89.00	1,333	2,666
STA 17+89.00	TO	STA 19+95.19	206	206
STA 19+95.19	TO	STA 21+87.00	192	192
NE RAMP				
STA 0+00.00	TO	STA 6+85.00	685	685
STA 6+85.00	TO	STA 18+90.00	1,205	2,410
STA 18+90.00	TO	STA 19+84.23	94	94
STEVENSON DRIVE				
RAMP A				
STA 0+00.00	TO	STA 6+68.00	668	668
STA 6+68.00	TO	STA 16+77.00	1,009	2,018
RAMP B				
STA 1+21.00	TO	STA 7+56.00	635	1,270
STA 7+56.00	TO	STA 18+15.73	1,060	1,060
RAMP C				
STA 0+00.00	TO	STA 4+84.00	484	484
STA 4+84.00	TO	STA 13+46.00	862	1,724
RAMP D				
STA 1+03.00	TO	STA 11+24.00	1,021	2,042
STA 11+24.00	TO	STA 23+29.60	1,206	1,206
SOUTH GRAND AVE.				
RAMP A				
STA 4+25.00	TO	STA 11+02.00	677	1,354
STA 11+02.00	TO	STA 12+09.40	107	107
RAMP B				
STA 0+00.00	TO	STA 6+21.00	621	621
STA 6+21.00	TO	STA 18+92.00	1,271	2,542
RAMP C				
STA 2+27.00	TO	STA 4+35.00	208	208
STA 4+35.00	TO	STA 17+10.00	1,275	2,550
RAMP D				
STA 2+89.00	TO	STA 19+76.00	1,687	3,374
STA 19+76.00	TO	STA 21+73.60	198	198
STA 24+50.70	TO	STA 30+71.73	621	621
RAMP E				
STA 4+38.00	TO	STA 10+28.00	590	1,180
STA 10+28.00	TO	STA 11+81.70	154	154
RAMP F				
STA 1+47.80	TO	STA 4+21.00	273	273
STA 4+21.00	TO	STA 15+00.00	1,079	2,158
RAMP G				
STA 2+48.70	TO	STA 4+75.00	226	226
STA 4+75.00	TO	STA 16+20.00	1,145	2,290
RAMP H				
STA 3+13.00	TO	STA 20+52.00	1,739	3,478
STA 20+52.00	TO	STA 31+11.61	1,060	1,060

URETHANE PAVEMENT MARKING TYPE 2 - LINE 5"

LOCATION	INSIDE EDGE LINE YELLOW (FOOT)	OUTSIDE EDGE LINE WHITE (FOOT)	CENTERLINE SKIP-DASH WHITE (FOOT)	TOTAL LENGTH (FOOT)
CLEAR LAKE AVE.				
RAMP A				
STA 3+69.00	TO	STA 13+88.00	1,019	2,038
STA 13+88.00	TO	STA 16+64.35	276	276
RAMP B				
STA 0+00.00	TO	STA 6+35.00	635	635
STA 6+35.00	TO	STA 21+33.00	1,498	2,996
RAMP C				
STA 0+00.00	TO	STA 3+92.00	392	392
STA 3+92.00	TO	STA 11+85.00	793	1,586
RAMP D				
STA 3+20.00	TO	STA 16+86.00	1,366	2,732
STA 16+86.00	TO	STA 27+43.00	1,057	1,057
RAMP E				
STA 3+79.00	TO	STA 13+90.00	1,011	2,022
STA 13+90.00	TO	STA 16+66.67	277	277
RAMP F				
STA 0+00.00	TO	STA 6+54.00	654	654
STA 6+54.00	TO	STA 21+89.00	1,535	3,070
RAMP G				
STA 0+00.00	TO	STA 3+92.00	392	392
STA 3+92.00	TO	STA 11+74.00	782	1,564
RAMP H				
STA 3+36.00	TO	STA 16+79.00	1,343	2,686
STA 16+79.00	TO	STA 27+43.95	1,065	1,065
TOTAL			119,576	239,497

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"

LOCATION	TOTAL LENGTH (FOOT)
NB I-55 / NB BL-55 DIVERGENCE	148
SB I-55 / WB I-72 DIVERGENCE	427
TOTAL	575

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY

SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____