

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	64
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)				
** D6 INTERSTATE RS,BR,M CAB 2008				

URETHANE PAVEMENT MARKING TYPE 2 - LINE 6"

LOCATION	TOTAL LENGTH (FOOT)
STEVENSON DRIVE	
RAMP A	
STA 13+48.00 TO STA 16+77.00	329
RAMP C	
STA 11+17.00 TO STA 17+10.00	593
TOTAL	922

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"

LOCATION	# OF LINES	LENGTH (FOOT)
I-72 MAINLINE		
EASTBOUND		
STA 627+00.00 TO STA 635+79.29 BK	1	220
STA 634+03.49 AH TO STA 673+12.11	1	980
STA 675+04.78 TO STA 684+54.96	1	240
STA 688+01.96 TO STA 700+21.00	1	310
WESTBOUND		
STA 627+00.00 TO STA 635+79.29 BK	1	220
STA 634+03.49 AH TO STA 673+13.13	1	980
STA 675+05.80 TO STA 698+73.00	1	600
I-55 BUSINESS LOOP		
NORTHBOUND		
STA 24+01.00 TO STA 40+27.62	1	410
STA 43+03.26 TO STA 63+50.00	1	520
SOUTHBOUND		
STA 34+96.00 TO STA 63+50.00	1	720
I-55 MAINLINE		
NORTHBOUND		
STA 9+97.00 TO STA 24+04.00	2	720
STA 24+04.00 TO STA 69+20.00	1	1,130
STA 69+20.00 TO STA 91+07.00	2	1,100
STA 91+07.00 TO STA 128+87.38 BK	1	950
STA 128+91.29 AH TO STA 233+44.43 BK	1	2,620
STA 233+52.70 AH TO STA 259+78.00	1	660
STA 262+55.00 TO STA 273+14.00	1	270
STA 277+50.00 TO STA 355+49.48 BK	1	1,950
STA 695+67.32 AH TO STA 693+00.00	1	70
SOUTHBOUND		
STA 13+59.00 TO STA 31+22.04	2	900
STA 31+22.04 TO STA 71+82.00	1	1,020
STA 71+82.00 TO STA 83+88.00	2	620
STA 83+88.00 TO STA 86+63.86 BK	1	70
STA 82+99.33 AH TO STA 128+87.38 BK	1	1,150
STA 128+91.29 AH TO STA 233+44.43 BK	1	2,620
STA 233+52.70 AH TO STA 260+03.00	1	670
STA 262+80.00 TO STA 273+44.00	1	270
STA 277+75.00 TO STA 355+49.48 BK	1	1,950
STA 695+67.32 AH TO STA 693+00.00	1	70
TOTAL		24,010

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS

LOCATION	DESCRIPTION	QUANTITY (SQ FT)
I-55 MAINLINE		
NORTHBOUND		
STA 83+00	LANE DROP ARROW	41.5
STA 88+00	LANE DROP ARROW	41.5
STA 91+25	LANE DROP ARROW	
STEVENSON DRIVE		
RAMP A		
STA 13+50	LEFT ARROW	15.6
STA 13+50	RIGHT ARROW	15.6
STA 15+00	LEFT ARROW	15.6
STA 15+00	RIGHT ARROW	15.6
STA 15+85	LEFT ARROW	15.6
STA 15+85	RIGHT ARROW	15.6
STA 16+70	LEFT ARROW	15.6
STA 16+70	RIGHT ARROW	15.6
RAMP C		
STA 11+25	COMB LEFT / THROUGH ARROW	26.0
STA 11+25	RIGHT ARROW	15.6
STA 12+50	COMB LEFT / THROUGH ARROW	26.0
STA 12+50	RIGHT ARROW	15.6
TOTAL		291.0

PLOT DATE = 08/14/2007 08:14:30AM
 FILE NAME = c:\p\projects\6525882\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY

SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____