

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	67
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)				
** D6 INTERSTATE RS,BR,M CAB 2008				

SHORT TERM PAVEMENT MARKING

LOCATION	INSIDE EDGE LINE YELLOW (FOOT)	OUTSIDE EDGE LINE WHITE (FOOT)	CENTERLINE SKIP-DASH WHITE (FOOT)	TOTAL LENGTH (FOOT)
SW LOOP RAMP				
STA 0+00.00 TO STA 4+56.00		36.4		36.4
STA 4+56.00 TO STA 17+89.00	106.6	106.6		213.2
STA 17+89.00 TO STA 19+95.19		16.4		16.4
STA 19+95.19 TO STA 21+87.00		15.4		15.4
NE RAMP				
STA 0+00.00 TO STA 6+85.00		54.8		54.8
STA 6+85.00 TO STA 18+90.00	96.4	96.4		192.8
STA 18+90.00 TO STA 19+84.23		7.6		7.6
STEVENSON DRIVE				
RAMP A				
STA 0+00.00 TO STA 6+68.00		53.4		53.4
STA 6+68.00 TO STA 16+77.00	80.8	80.8		161.6
RAMP B				
STA 1+21.00 TO STA 7+56.00	50.8	50.8		101.6
STA 7+56.00 TO STA 18+15.73		84.8		84.8
RAMP C				
STA 0+00.00 TO STA 4+84.00		38.8		38.8
STA 4+84.00 TO STA 13+46.00	69.0	69.0		138.0
RAMP D				
STA 1+03.00 TO STA 11+24.00	81.6	81.6		163.2
STA 11+24.00 TO STA 23+29.60		96.4		96.4
SOUTH GRAND AVE.				
RAMP A				
STA 4+25.00 TO STA 11+02.00	54.2	54.2		108.4
STA 11+02.00 TO STA 12+09.40		8.6		8.6
RAMP B				
STA 0+00.00 TO STA 6+21.00		49.6		49.6
STA 6+21.00 TO STA 18+92.00	101.6	101.6		203.2
RAMP C				
STA 2+27.00 TO STA 4+35.00		16.6		16.6
STA 4+35.00 TO STA 17+10.00	102.0	102.0		204.0
RAMP D				
STA 2+89.00 TO STA 19+76.00	135.0	135.0		270.0
STA 19+76.00 TO STA 21+73.60		15.8		15.8
STA 24+50.70 TO STA 30+71.73		49.6		49.6
RAMP E				
STA 4+38.00 TO STA 10+28.00	47.2	47.2		94.4
STA 10+28.00 TO STA 11+81.70		12.2		12.2
RAMP F				
STA 1+47.80 TO STA 4+21.00		21.8		21.8
STA 4+21.00 TO STA 15+00.00	86.4	86.4		172.8
RAMP G				
STA 2+48.70 TO STA 4+75.00		18.2		18.2
STA 4+75.00 TO STA 16+20.00	91.6	91.6		183.2
RAMP H				
STA 3+13.00 TO STA 20+52.00	139.2	139.2		278.4
STA 20+52.00 TO STA 31+11.61		84.8		84.8

SHORT TERM PAVEMENT MARKING

LOCATION	INSIDE EDGE LINE YELLOW (FOOT)	OUTSIDE EDGE LINE WHITE (FOOT)	CENTERLINE SKIP-DASH WHITE (FOOT)	TOTAL LENGTH (FOOT)
CLEAR LAKE AVE.				
RAMP A				
STA 3+69.00 TO STA 13+88.00	81.6	81.6		163.2
STA 13+88.00 TO STA 16+64.35		22.2		22.2
RAMP B				
STA 0+00.00 TO STA 6+35.00		50.8		50.8
STA 6+35.00 TO STA 21+33.00	119.8	119.8		239.6
RAMP C				
STA 0+00.00 TO STA 3+92.00		31.4		31.4
STA 3+92.00 TO STA 11+85.00	63.4	63.4		126.8
RAMP D				
STA 3+20.00 TO STA 16+86.00	109.2	109.2		218.4
STA 16+86.00 TO STA 27+43.00		84.6		84.6
RAMP E				
STA 3+79.00 TO STA 13+90.00	80.8	80.8		161.6
STA 13+90.00 TO STA 16+66.67		22.2		22.2
RAMP F				
STA 0+00.00 TO STA 6+54.00		52.4		52.4
STA 6+54.00 TO STA 21+89.00	122.8	122.8		245.6
RAMP G				
STA 0+00.00 TO STA 3+92.00		31.4		31.4
STA 3+92.00 TO STA 11+74.00	62.6	62.6		125.2
RAMP H				
STA 3+36.00 TO STA 16+79.00	107.4	107.4		214.8
STA 16+79.00 TO STA 27+43.95		85.2		85.2
TOTAL	9,372.4	9,323.8	17,468.3	36,164.5

PLOT DATE = 08/22/2007 08:15:45AM
 FILE NAME = c:\p\projects\652882\shshch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY
 SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____