

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	69

STA. TO STA.  
 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT  
 \* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)  
 \*\* D6 INTERSTATE RS,BR,M CAB 2008

WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION		INSIDE EDGE LINE YELLOW (SO FT)	OUTSIDE EDGE LINE WHITE (SO FT)	TOTAL AREA (SO FT)
<b>SW LOOP RAMP</b>				
STA 0+00.00	TO STA 4+56.00		7.6	7.6
STA 4+56.00	TO STA 17+89.00	22.2	22.2	44.4
STA 17+89.00	TO STA 19+95.19		3.4	3.4
STA 19+95.19	TO STA 21+87.00		3.2	3.2
<b>NE RAMP</b>				
STA 0+00.00	TO STA 6+85.00		11.4	11.4
STA 6+85.00	TO STA 18+90.00	20.1	20.1	40.2
STA 18+90.00	TO STA 19+84.23		1.6	1.6
<b>STEVENSON DRIVE</b>				
<b>RAMP A</b>				
STA 0+00.00	TO STA 6+68.00		11.1	11.1
STA 6+68.00	TO STA 16+77.00	16.8	16.8	33.6
<b>RAMP B</b>				
STA 1+21.00	TO STA 7+56.00	10.6	10.6	21.2
STA 7+56.00	TO STA 18+15.73		17.7	17.7
<b>RAMP C</b>				
STA 0+00.00	TO STA 4+84.00		8.1	8.1
STA 4+84.00	TO STA 13+46.00	14.4	14.4	28.8
<b>RAMP D</b>				
STA 1+03.00	TO STA 11+24.00	17.0	17.0	34.0
STA 11+24.00	TO STA 23+29.60		20.1	20.1
<b>SOUTH GRAND AVE.</b>				
<b>RAMP A</b>				
STA 4+25.00	TO STA 11+02.00	11.3	11.3	22.6
STA 11+02.00	TO STA 12+09.40		1.8	1.8
<b>RAMP B</b>				
STA 0+00.00	TO STA 6+21.00		10.4	10.4
STA 6+21.00	TO STA 18+92.00	21.2	21.2	42.4
<b>RAMP C</b>				
STA 2+27.00	TO STA 4+35.00		3.5	3.5
STA 4+35.00	TO STA 17+10.00	21.3	21.3	42.6
<b>RAMP D</b>				
STA 2+89.00	TO STA 19+76.00	28.1	28.1	56.2
STA 19+76.00	TO STA 21+73.60		3.3	3.3
STA 24+50.70	TO STA 30+71.73		10.4	10.4
<b>RAMP E</b>				
STA 4+38.00	TO STA 10+28.00	9.8	9.8	19.6
STA 10+28.00	TO STA 11+81.70		2.6	2.6
<b>RAMP F</b>				
STA 1+47.80	TO STA 4+21.00		4.6	4.6
STA 4+21.00	TO STA 15+00.00	18.0	18.0	36.0
<b>RAMP G</b>				
STA 2+48.70	TO STA 4+75.00		3.8	3.8
STA 4+75.00	TO STA 16+20.00	19.1	19.1	38.2
<b>RAMP H</b>				
STA 3+13.00	TO STA 20+52.00	29.0	29.0	58.0
STA 20+52.00	TO STA 31+11.61		17.7	17.7

WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION		INSIDE EDGE LINE YELLOW (SO FT)	OUTSIDE EDGE LINE WHITE (SO FT)	TOTAL AREA (SO FT)
<b>CLEAR LAKE AVE.</b>				
<b>RAMP A</b>				
STA 3+69.00	TO STA 13+88.00	17.0	17.0	34.0
STA 13+88.00	TO STA 16+64.35		4.6	4.6
<b>RAMP B</b>				
STA 0+00.00	TO STA 6+35.00		10.6	10.6
STA 6+35.00	TO STA 21+33.00	25.0	25.0	50.0
<b>RAMP C</b>				
STA 0+00.00	TO STA 3+92.00		6.5	6.5
STA 3+92.00	TO STA 11+85.00	13.2	13.2	26.4
<b>RAMP D</b>				
STA 3+20.00	TO STA 16+86.00	22.8	22.8	45.6
STA 16+86.00	TO STA 27+43.00		17.6	17.6
<b>RAMP E</b>				
STA 3+79.00	TO STA 13+90.00	16.9	16.9	33.8
STA 13+90.00	TO STA 16+66.67		4.6	4.6
<b>RAMP F</b>				
STA 0+00.00	TO STA 6+54.00		10.9	10.9
STA 6+54.00	TO STA 21+89.00	25.6	25.6	51.2
<b>RAMP G</b>				
STA 0+00.00	TO STA 3+92.00		6.5	6.5
STA 3+92.00	TO STA 11+74.00	13.0	13.0	26.0
<b>RAMP H</b>				
STA 3+36.00	TO STA 16+79.00	22.4	22.4	44.8
STA 16+79.00	TO STA 27+43.95		17.8	17.8
<b>TOTAL</b>				8,613.5

PLOT DATE = Nov-19-2007 08:23:46AM  
 FILE NAME = c:\projects\652882\shsch.dgn  
 PLOT SCALE = 1/8"=1'-0" / IN.  
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)  
 SECTION D6 INTERSTATE RS,BR,M CAB 2008  
 SANGAMON COUNTY  
 SCALE: DRAWN BY  
 DATE CHECKED BY