

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	70
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS) ** D6 INTERSTATE RS,BR,M CAB 2008				

RAISED REFLECTIVE PAVEMENT MARKER

LOCATION	LANE LOCATION	COLOR	# OF LINES	# OF REFL PER SPACING	TOTAL (EACH)
I-72 MAINLINE					
EASTBOUND					
STA 627+00.00	TO STA 635+79.29 BK	CENTERLINE	CRYSTAL	1 2 PER 80	22
STA 634+03.49 AH	TO STA 673+12.11	CENTERLINE	CRYSTAL	1 2 PER 80	98
STA 675+04.78	TO STA 684+54.96	CENTERLINE	CRYSTAL	1 2 PER 80	24
STA 688+01.96	TO STA 700+21.00	CENTERLINE	CRYSTAL	1 2 PER 80	32
WESTBOUND					
STA 627+00.00	TO STA 635+79.29 BK	CENTERLINE	CRYSTAL	1 2 PER 80	22
STA 634+03.49 AH	TO STA 673+13.13	CENTERLINE	CRYSTAL	1 2 PER 80	98
STA 675+05.80	TO STA 698+73.00	CENTERLINE	CRYSTAL	1 2 PER 80	60
I-55 BUSINESS LOOP					
NORTHBOUND					
STA 24+01.00	TO STA 40+27.62	CENTERLINE	CRYSTAL	1 2 PER 80	42
STA 24+01.00	TO STA 40+27.62	CENTERLINE	AMBER	1 1 PER 40	41
STA 43+03.26	TO STA 63+50.00	CENTERLINE	CRYSTAL	1 2 PER 80	52
SOUTHBOUND					
STA 34+96.00	TO STA 63+50.00	CENTERLINE	CRYSTAL	1 2 PER 80	72
I-55 MAINLINE					
NORTHBOUND					
STA 9+97.00	TO STA 24+04.00	CENTERLINE	CRYSTAL	2 2 PER 80	72
STA 24+04.00	TO STA 69+20.00	CENTERLINE	CRYSTAL	1 2 PER 80	114
STA 29+77.00	TO STA 63+75.00	INSIDE EOP	AMBER	1 1 PER 40	85
STA 69+20.00	TO STA 91+07.00	CENTERLINE	CRYSTAL	2 2 PER 80	112
STA 91+07.00	TO STA 128+87.38 BK	CENTERLINE	CRYSTAL	1 2 PER 80	96
STA 128+91.29 AH	TO STA 233+44.43 BK	CENTERLINE	CRYSTAL	1 2 PER 80	262
STA 233+52.70 AH	TO STA 259+78.00	CENTERLINE	CRYSTAL	1 2 PER 80	66
STA 262+55.00	TO STA 273+14.00	CENTERLINE	CRYSTAL	1 2 PER 80	28
STA 277+50.00	TO STA 355+49.48 BK	CENTERLINE	CRYSTAL	1 2 PER 80	196
STA 695+67.32 AH	TO STA 693+00.00	CENTERLINE	CRYSTAL	1 2 PER 80	8
SOUTHBOUND					
STA 13+59.00	TO STA 31+22.04	CENTERLINE	CRYSTAL	2 2 PER 80	92
STA 31+22.04	TO STA 71+82.00	CENTERLINE	CRYSTAL	1 2 PER 80	102
STA 34+95.41	TO STA 62+07.00	OUTSIDE EOP	AMBER	1 1 PER 40	68
STA 71+82.00	TO STA 83+88.00	CENTERLINE	CRYSTAL	2 2 PER 80	64
STA 83+88.00	TO STA 86+63.86 BK	CENTERLINE	CRYSTAL	1 2 PER 80	8
STA 82+99.33 AH	TO STA 128+87.38 BK	CENTERLINE	CRYSTAL	1 2 PER 80	116
STA 128+91.29 AH	TO STA 233+44.43 BK	CENTERLINE	CRYSTAL	1 2 PER 80	262
STA 233+52.70 AH	TO STA 260+03.00	CENTERLINE	CRYSTAL	1 2 PER 80	68
STA 262+80.00	TO STA 273+44.00	CENTERLINE	CRYSTAL	1 2 PER 80	28
STA 277+75.00	TO STA 355+49.48 BK	CENTERLINE	CRYSTAL	1 2 PER 80	196
STA 695+67.32 AH	TO STA 693+00.00	CENTERLINE	CRYSTAL	1 2 PER 80	8
SIXTH STREET INTERCHANGE					
NB I-55 / NB BL-55 DIVERGENCE					
STA 24+04.00	TO STA 29+77.00	GORE (I-55)	CRYSTAL	1 1 PER 40	15
STA 24+01.00	TO STA 29+74.00	GORE (BL-55)	CRYSTAL	1 1 PER 40	15
SB I-55 / WB I-72 DIVERGENCE					
STA 31+22.04	TO STA 34+95.41	GORE (I-55)	CRYSTAL	1 1 PER 40	10
STA 31+22.00	TO STA 34+96.00	GORE (I-72)	CRYSTAL	1 1 PER 40	10
RAMP A					
STA 0+00.00	TO STA 6+62.40	OUTSIDE EOP	CRYSTAL	1 1 PER 20	34
STA 655+72.00	TO STA 659+20.00	GORE (I-72)	CRYSTAL	1 1 PER 40	9
STA 3+14.00	TO STA 6+62.40	GORE (RAMP)	CRYSTAL	1 1 PER 40	9
STA 6+62.40	TO STA 26+12.00	INSIDE EOP	AMBER	1 1 PER 40	49
RAMP B					
STA 3+04.74	TO STA 6+42.00	OUTSIDE EOP	CRYSTAL	1 1 PER 20	17
STA 676+50.00	TO STA 678+44.00	GORE (I-72)	CRYSTAL	1 1 PER 40	5
STA 4+50.00	TO STA 6+42.00	GORE (RAMP)	CRYSTAL	1 1 PER 40	5
STA 6+42.00	TO STA 17+74.00	INSIDE EOP	AMBER	1 1 PER 40	29
RAMP C					
STA 57+75.00	TO STA 58+97.00	GORE (BL-55)	CRYSTAL	1 1 PER 40	4
STA 2+82.00	TO STA 4+01.00	GORE (RAMP)	CRYSTAL	1 1 PER 40	3
STA 4+01.00	TO STA 13+72.00	INSIDE EOP	AMBER	1 1 PER 40	25

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY

SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____