

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	71

STA. TO STA.
 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT
 * FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 ** D6 INTERSTATE RS,BR,M CAB 2008

RAISED REFLECTIVE PAVEMENT MARKER

LOCATION	LANE LOCATION	COLOR	# OF LINES	# OF REFL PER SPACING	TOTAL (EACH)
RAMP D					
STA 4+12.72	TO STA 6+57.00	OUTSIDE EOP	1	1 PER 20	13
STA 61+05.00	TO STA 63+50.00	GORE (BL-55)	1	1 PER 40	7
STA 4+12.72	TO STA 6+57.00	GORE (RAMP)	1	1 PER 40	7
STA 6+57.00	TO STA 13+72.00	INSIDE EOP	1	1 PER 40	18
SW LOOP RAMP					
STA 0+00.00	TO STA 4+56.00	OUTSIDE EOP	1	1 PER 20	23
STA 49+56.00	TO STA 50+57.00	GORE (BL-55)	1	1 PER 40	3
STA 3+58.00	TO STA 4+56.00	GORE (RAMP)	1	1 PER 40	3
STA 4+56.00	TO STA 17+89.00	INSIDE EOP	1	1 PER 40	34
NE RAMP					
STA 0+00.00	TO STA 6+85.00	OUTSIDE EOP	1	1 PER 20	35
STA 684+19.00	TO STA 687+92.00	GORE (I-72)	1	1 PER 40	10
STA 3+14.00	TO STA 6+85.00	GORE (RAMP)	1	1 PER 40	10
STA 6+85.00	TO STA 11+56.00	INSIDE EOP	1	1 PER 40	12
STEVENSON DRIVE INTERCHANGE					
RAMP A					
STA 0+00.00	TO STA 6+68.00	OUTSIDE EOP	1	1 PER 20	34
STA 181+27.00	TO STA 184+94.00	GORE (I-55)	1	1 PER 40	10
STA 3+02.00	TO STA 6+68.00	GORE (RAMP)	1	1 PER 40	10
STA 6+68.00	TO STA 11+14.00	INSIDE EOP	1	1 PER 40	12
RAMP C					
STA 0+00.00	TO STA 4+84.00	OUTSIDE EOP	1	1 PER 20	25
STA 173+44.00	TO STA 175+81.00	GORE (I-55)	1	1 PER 40	6
STA 2+45.00	TO STA 4+84.00	GORE (RAMP)	1	1 PER 40	6
STA 4+84.00	TO STA 12+04.00	INSIDE EOP	1	1 PER 40	18
SOUTH GRAND INTERCHANGE					
RAMP A					
STA 4+25.00	TO STA 11+02.00	INSIDE EOP	1	1 PER 40	17
RAMP B					
STA 0+00.00	TO STA 6+21.00	OUTSIDE EOP	1	1 PER 20	32
STA 287+33.00	TO STA 290+53.00	GORE (I-55)	1	1 PER 40	8
STA 3+01.00	TO STA 6+21.00	GORE (RAMP)	1	1 PER 40	8
STA 6+21.00	TO STA 18+92.00	INSIDE EOP	1	1 PER 40	32
RAMP C					
STA 2+27.00	TO STA 4+35.00	OUTSIDE EOP	1	1 PER 20	11
STA 271+30.00	TO STA 272+29.00	GORE (I-55)	1	1 PER 40	3
STA 3+41.00	TO STA 4+35.00	GORE (RAMP)	1	1 PER 40	3
STA 4+35.00	TO STA 17+10.00	INSIDE EOP	1	1 PER 40	32
RAMP D					
STA 2+89.00	TO STA 8+55.00	INSIDE EOP	1	1 PER 40	15
RAMP E					
STA 4+38.00	TO STA 10+28.00	INSIDE EOP	1	1 PER 40	15
RAMP F					
STA 1+47.80	TO STA 4+22.00	OUTSIDE EOP	1	1 PER 20	14
STA 262+98.00	TO STA 265+30.00	GORE (I-55)	1	1 PER 40	6
STA 1+90.00	TO STA 4+22.00	GORE (RAMP)	1	1 PER 40	6
STA 4+22.00	TO STA 15+00.00	INSIDE EOP	1	1 PER 40	27
RAMP G					
STA 2+48.70	TO STA 4+75.00	OUTSIDE EOP	1	1 PER 20	12
STA 278+51.00	TO STA 279+84.00	GORE (I-55)	1	1 PER 40	4
STA 3+48.00	TO STA 4+75.00	GORE (RAMP)	1	1 PER 40	4
STA 4+75.00	TO STA 16+20.00	INSIDE EOP	1	1 PER 40	29
RAMP H					
STA 3+13.00	TO STA 7+67.00	INSIDE EOP	1	1 PER 40	12

PLOT DATE = 08/14/2007 08:14:58AM
 FILE NAME = c:\p\projects\652282\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY
 SCALE: DRAWN BY
 DATE CHECKED BY