

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	72
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS) ** D6 INTERSTATE RS,BR,M CAB 2008				

RAISED REFLECTIVE PAVEMENT MARKER

LOCATION	LANE LOCATION	COLOR	# OF LINES	# OF REFL PER SPACING	TOTAL (EACH)
CLEAR LAKE INTERCHANGE					
RAMP A					
STA 3+69.00	TO STA 13+88.00	INSIDE EOP	1	1 PER 40	26
RAMP B					
STA 0+00.00	TO STA 6+35.00	OUTSIDE EOP	1	1 PER 20	32
STA 344+89.00	TO STA 348+22.00	GORE (I-55)	1	1 PER 40	9
STA 3+02.00	TO STA 6+35.00	GORE (RAMP)	1	1 PER 40	9
STA 6+35.00	TO STA 12+21.00	INSIDE EOP	1	1 PER 40	15
RAMP C					
STA 0+00.00	TO STA 3+92.00	OUTSIDE EOP	1	1 PER 20	20
STA 329+37.00	TO STA 330+72.00	GORE (I-55)	1	1 PER 40	4
STA 2+61.00	TO STA 3+92.00	GORE (RAMP)	1	1 PER 40	4
STA 3+92.00	TO STA 11+85.00	INSIDE EOP	1	1 PER 40	20
RAMP D					
STA 3+20.00	TO STA 16+86.00	INSIDE EOP	1	1 PER 40	35
RAMP E					
STA 3+79.00	TO STA 13+90.00	INSIDE EOP	1	1 PER 40	26
RAMP F					
STA 0+00.00	TO STA 6+54.00	OUTSIDE EOP	1	1 PER 20	33
STA 318+70.00	TO STA 322+25.00	GORE (I-55)	1	1 PER 40	9
STA 2+99.00	TO STA 6+54.00	GORE (RAMP)	1	1 PER 40	9
STA 6+54.00	TO STA 12+22.00	INSIDE EOP	1	1 PER 40	15
RAMP G					
STA 0+00.00	TO STA 3+92.00	OUTSIDE EOP	1	1 PER 20	20
STA 336+37.00	TO STA 337+60.00	GORE (I-55)	1	1 PER 40	4
STA 2+73.00	TO STA 3+92.00	GORE (RAMP)	1	1 PER 40	3
STA 3+92.00	TO STA 11+74.00	INSIDE EOP	1	1 PER 40	20
RAMP H					
STA 3+36.00	TO STA 16+79.00	INSIDE EOP	1	1 PER 40	34
TOTAL					3,786

LIGHTING SCHEDULE

LOCATION	TRENCH & BACKFILL FOR ELEC WORK (FOOT)	UNIT DUCT 2 #10 XLP GR, 3/4" POLY (FOOT)	UNIT DUCT 2 #6 XLP GR, 1" POLY (FOOT)	UNIT DUCT 2 #8 XLP GR, 3/4" POLY (FOOT)	UNIT DUCT 3 #8 XLP GR, 3/4" POLY (FOOT)	UNIT DUCT 3 #10 XLP GR, 3/4" POLY (FOOT)	UNIT DUCT 3 #2 XLP GR, 1 1/4" POLY (FOOT)	UNIT DUCT 3 #4 XLP GR, 1 1/4" POLY (FOOT)	UNIT DUCT 3 #6 XLP GR, 1" POLY (FOOT)	BREAKAWAY DEVICE COUPLING W STAIN ST SCREEN (EACH)	LIGHT POLE REM & RE-ERECT (EACH)	EX LIGHT POLE FOUND ADJUST (EACH)	JUNCTION BOX (SPL) (EACH)
I-55 MAINLINE													
STA 58+00 TO STA 88+00	910							910		4	1	1	
STA 107+00 TO STA 133+00	350		350							4	1	1	
STA 158+00 TO STA 187+00	1,585			200					1,385	16	4	4	
SOUTH GRAND INTERCHANGE	4,200				1,500	500	950	1,250		24	6	6	1
CLEAR LAKE INTERCHANGE	1,290	710				250			330	20	5	5	
TOTAL	8,335	710	350	200	1,500	750	950	2,160	1,715	68	17	17	1

PLOT DATE = Oct-22-2007 08:15:00AM
 FILE NAME = c:\p\projects\652882\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY
 SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____