

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685	(113)B-3	HANCOCK	48	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

TRAFFIC CONTROL

LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATOR TEMPORARY FULLY REDIRECTIVE NARROW, TL3	IMPACT ATTENUATOR, RELOCATE FULLY REDIRECTIVE TEST LEVEL 3	TRAFFIC CONTROL & PROTECTION STD. 701321 (SPECIAL)	TRAFFIC CONTROL & PROTECTION STD. 701326	TRAFFIC CONTROL & PROTECTION STD. 701306	TRAFFIC CONTROL & PROTECTION STD. BLR 21	WIDTH RESTRICTION SIGNING
STATION TO STATION	FOOT		EACH		L. SUM				
IL RTE 96 116+50      120+50	480	350							
IL RTE 96 STA. 116+30 STA. 120+75			1 1	1 1					
APPLE RIVER RD. 10+80.79    17+42.42								1	
114+00      123+00					1	1	1		1
TOTAL	480	350	2	2	1	1	1	1	1

RAISED REFLECTIVE PAVEMENT MARKER

LOCATION	EACH
IL-96	
STA. 122+90	1
STA. 122+10	1
STA. 121+30	1
STA. 120+50	1
STA. 119+70	1
STA. 118+90	1
STA. 118+10	1
STA. 117+30	1
STA. 116+50	1
STA. 115+70	1
STA. 114+90	1
STA. 114+10	1
TOTAL	12

WORK ZONE

LOCATION	TRAFFIC CONTROL SURVEILLANCE	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY RAMP	TEMPORARY BRIDGE TRAFFIC SIGNALS
STATION TO STATION	CAL DA.	SO. FT.	SO. YD.	EACH
IL RTE 96 114+00      123+00	5			
STAGE III REMOVAL		94		
IL RTE 96 114+00 TO 114+05 122+95 TO 123+00			12.2 12.2	
APPLE RIVER RD. 17+36.3 TO 17+42.42			15.0	
STAGES I & II & III				1
TOTAL	5	94	39.4	1

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	EACH
IL RTE 96 STA. 114+00 TO STA. 123+00	12
TOTAL	12

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE  
DATE: 7/07

DRAWN BY: SGL  
CHECKED BY: FML