

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
321	18(N-1,TS)	PIKE	55	12
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

THERMOPLASTIC PAVEMENT MARKING - LINE 5"				
LOCATION	COLOR / DESCRIPTION	# OF LINES	LENGTH (FOOT)	
STA 32+05 TO STA 36+43	WHITE/EDGE	1	438.0	
STA 32+05 TO STA 35+61	WHITE/EDGE	1	356.0	
STA 32+05 TO STA 33+25	YELLOW/SKIP DASH	1	30.0	
STA 33+25 TO STA 36+43	YELLOW/SOLID	4	1,272.0	
STA 36+43 TO STA 37+58	YELLOW/SOLID	2	230.0	
STA 38+45 TO STA 39+60	YELLOW/SOLID	2	230.0	
STA 39+60 TO STA 40+31	YELLOW/SOLID	4	284.0	
STA 40+31 TO STA 41+72	YELLOW/SOLID	2	282.0	
STA 40+31 TO STA 41+72	YELLOW/SKIP DASH	2	80.0	
STA 41+72 TO STA 42+43	YELLOW/SOLID	4	284.0	
STA 42+43 TO STA 43+43	YELLOW/SOLID	2	200.0	
STA 44+23 TO STA 45+23	YELLOW/SOLID	2	200.0	
STA 45+23 TO STA 45+93	YELLOW/SOLID	4	280.0	
STA 45+93 TO STA 47+63	YELLOW/SOLID	2	340.0	
STA 45+93 TO STA 47+63	YELLOW/SKIP DASH	2	80.0	
STA 47+63 TO STA 49+35	YELLOW/SOLID	4	688.0	
STA 49+35 TO STA 50+35	YELLOW/SOLID	2	200.0	
STA 51+15 TO STA 51+67	YELLOW/SOLID	2	104.0	
STA 51+15 TO STA 51+67	YELLOW/SKIP DASH	2	20.0	
Franklin St.				
STA 9+22 TO STA 9+53	YELLOW/SOLID	2	62.0	
STA 10+48 TO STA 12+77	YELLOW/SOLID	2	458.0	
STA 11+02 TO STA 12+34	WHITE/EDGE	1	132.0	
Clinton St.				
STA 9+22 TO STA 9+55	WHITE/EDGE	1	33.0	
TOTAL			6,283.0	

THERMOPLASTIC PAVEMENT MARKING - LINE 12"						
LOCATION	DESCRIPTION	COLOR	LENGTH (FOOT)			
STA 32+05 TO STA 36+43	DIAGONALS	WHITE	165.5			
STA 32+05 TO STA 35+61	DIAGONALS	WHITE	139.9			
STA 33+25 TO STA 36+43	DIAGONALS	YELLOW	106.6			
STA 39+72 TO STA 40+27	DIAGONALS	YELLOW	25.5			
STA 41+76 TO STA 42+28	DIAGONALS	YELLOW	26.1			
STA 45+37 TO STA 45+90	DIAGONALS	YELLOW	26.9			
STA 48+66 TO STA 49+18	DIAGONALS	YELLOW	28.0			
Franklin St.						
STA 11+02 TO STA 12+34	DIAGONALS	WHITE	26.5			
Clinton St.						
STA 9+22 TO STA 9+55	DIAGONALS	WHITE	4.3			
TOTAL			549.3			

RAISED REFLECTIVE PAVEMENT MARKER						
LOCATION	DESCRIPTION	ONE-WAY AMBER	TWO-WAY AMBER	ONE-WAY CRYSTAL		
STA 32+05 TO STA 33+14	SKIP DASH		1			
STA 33+14 TO STA 36+35	GORE AREA	18				
STA 36+43 TO STA 37+58	CL		6			
STA 36+43 TO STA 37+58	LANE LINE			3		
STA 38+45 TO STA 39+60	CL		6			
STA 38+45 TO STA 39+60	LANE LINE			3		
STA 39+60 TO STA 42+43	TWLTL	14				
STA 42+43 TO STA 43+43	CL		6			
STA 42+43 TO STA 43+43	LANE LINE			3		
STA 44+23 TO STA 45+23	CL		6			
STA 44+23 TO STA 45+23	LANE LINE			3		
STA 45+23 TO STA 49+35	TWLTL	20				
STA 49+35 TO STA 50+35	CL		6			
STA 49+35 TO STA 50+35	LANE LINE			3		
STA 51+15 TO STA 51+67	TWLTL		4			
TOTALS		52	35	15		
JOB TOTAL		102	EACH			

PREFORMED PLASTIC PAVEMENT MARKING, TY B - INLAID - LINE 24"				
LOCATION	DIRECTION	DESCRIPTION	LENGTH (FOOT)	
STA 37+58	WB	STOP BAR	26.0	
STA 38+45	EB	STOP BAR	26.0	
Franklin St.				
STA 9+53	NB	STOP BAR	12.6	
STA 10+48	SB	STOP BAR	13.9	
Clinton St.				
STA 9+55	NB	STOP BAR	14.7	
STA 10+46	SB	STOP BAR	12.6	
TOTAL			105.8	

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"				
LOCATION	COLOR	DESCRIPTION	LENGTH (FOOT)	
STA 36+43 TO STA 37+58	WHITE	LANE LINE	115.0	
STA 37+67	WHITE	CROSSWALK	46.8	
STA 37+73	WHITE	CROSSWALK	54.3	
STA 38+27	WHITE	CROSSWALK	56.7	
STA 38+33	WHITE	CROSSWALK	48.3	
STA 38+45 TO STA 39+60	WHITE	LANE LINE	115.0	
STA 42+43 TO STA 43+43	WHITE	LANE LINE	100.0	
STA 44+23 TO STA 45+23	WHITE	LANE LINE	100.0	
STA 49+35 TO STA 50+35	WHITE	LANE LINE	100.0	
Franklin St.				
STA 9+61	WHITE	CROSSWALK	32.2	
STA 9+67	WHITE	CROSSWALK	39.8	
STA 10+37	WHITE	CROSSWALK	41.1	
STA 10+43	WHITE	CROSSWALK	34.8	
Clinton St.				
STA 9+60	WHITE	CROSSWALK	29.6	
STA 9+66	WHITE	CROSSWALK	35.4	
STA 10+35	WHITE	CROSSWALK	31.6	
STA 10+41	WHITE	CROSSWALK	26.6	
TOTAL			1,007.2	

PREFORMED PLASTIC PAVEMENT MARKING, TY B - INLAID - LETTERS & SYMBOLS				
LOCATION	LANE	SYMBOL TYPE	SQ FT	
STA 36+48	LT	LEFT TURN	15.6	
STA 37+35	LT	LEFT TURN	15.6	
STA 38+66	LT	LEFT TURN	15.6	
STA 39+55	LT	LEFT TURN	15.6	
STA 40+43	BI-DIR.	LEFT TURN	31.2	
STA 41+61	BI-DIR.	LEFT TURN	31.2	
STA 42+47	LT	LEFT TURN	15.6	
STA 43+22	LT	LEFT TURN	15.6	
STA 44+45	LT	LEFT TURN	15.6	
STA 45+19	LT	LEFT TURN	15.6	
STA 46+11	BI-DIR.	LEFT TURN	31.2	
STA 48+47	BI-DIR.	LEFT TURN	31.2	
STA 49+39	LT	LEFT TURN	15.6	
STA 50+19	LT	LEFT TURN	15.6	
STA 51+31	BI-DIR.	LEFT TURN	31.2	
TOTAL			312.0	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAP 321 (US 54/IL 106)
 SECTION 18(N-1,TS)
 PIKE COUNTY
 SCALE: VERT. / HORIZ.
 DATE: / / DRAWN BY: / CHECKED BY: /