

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	*	MASON	11	6
STA. 572+65.00		TO STA. 641+68.50		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

*D-6 SHLDR RUMBLE STRIPS 2008-2

SCHEDULE OF QUANTITIES

EXCAVATING AND GRADING EXISTING SHOULDER

LOCATION	QUANTITY (UNIT)
	100' =UNIT
<i>F. A. P. 315 (US 136)</i>	
STA. 572+65.00 to 573+53.00	1.76
STA. 573+53.00 to 575+97.00 LT	2.44
<i>(IL 10 - Intersection - Sta. 574+42.43 RT)</i>	
STA. 575+97.00 to 582+77.57	13.61
STA. 606+14.91 to 611+74.18	11.19
STA. 635+34.31 to 637+14.50	3.60
<i>Side Road Omission</i>	
<i>(CH 4 - 2800 E Intersection - Sta. 637+19.00 to 637+74.50)</i>	
STA. 637+79.00 to 641+68.50	7.80
PROJECT TOTAL	41

SHOULDER RUMBLE STRIP

LOCATION	QUANTITY (FOOT)
<i>F. A. P. 315 (US 136)</i>	
STA. 572+65.00 to 573+53.00	176.0
STA. 573+53.00 to 575+97.00 LT	244.0
<i>(IL 10 - Intersection - Sta. 574+42.43 RT)</i>	
STA. 575+97.00 to 591+37.31	3,080.62
STA. 591+37.31 to 592+59.31 LT	122.0
<i>(1650 N - Intersection - Sta. 592+80.36 RT)</i>	
STA. 592+59.31 to 637+14.50	8,910.38
<i>Side Road Omission</i>	
<i>(CH 4 - 2800 E Intersection - Sta. 637+19.00 to 637+74.50)</i>	
STA. 637+79.00 to 641+68.50	779.0
PROJECT TOTAL	13,312

PAINT PAVEMENT MARKING - LINE 5"

LOCATION	WHITE SOLID (FOOT)
<i>F. A. P. 315 (US 136)</i>	
STA. 572+65.00 to 573+53.00	176.0
STA. 573+53.00 to 575+97.00 LT	244.0
<i>(IL 10 - Intersection - Sta. 574+42.43 RT)</i>	
STA. 575+97.00 to 591+37.31	3,080.62
STA. 591+37.31 to 592+59.31 LT	122.0
<i>(1650 N - Intersection - Sta. 574+42.43 RT)</i>	
STA. 592+59.31 to 637+14.50	8,910.38
<i>Side Road Omission</i>	
<i>(CH 4 - 2800 E Intersection - Sta. 637+19.00 to 637+74.50)</i>	
STA. 637+79.00 to 641+68.50	779.0
PROJECT TOTAL	13,312

HOT-MIX ASPHALT SHOULDERS, 8"

LOCATION	QUANTITY (SQ YD)
<i>F. A. P. 315 (US 136)</i>	
STA. 572+65.00 to 573+53.00	58.67
STA. 573+53.00 to 575+97.00 LT	81.33
<i>(IL 10 - Intersection - Sta. 574+42.43 RT)</i>	
STA. 575+97.00 to 582+77.57	453.71
STA. 606+14.91 to 611+74.18	372.85
STA. 635+34.31 to 637+14.50	120.13
<i>Side Road Omission</i>	
<i>(CH 4 - 2800 E Intersection - Sta. 637+19.00 to 637+74.50)</i>	
STA. 637+79.00 to 641+68.50	259.67
PROJECT TOTAL	1,347

AGGREGATE SHOULDERS, TYPE B

LOCATION	QUANTITY (TON)
<i>F. A. P. 315 (US 136)</i>	
STA. 572+65.00 to 573+73.50	8.24
STA. 573+73.50 to 575+61.00 LT	7.12
<i>(IL 10 - Intersection - Sta. 574+42.43 RT)</i>	
STA. 575+61.00 to 582+77.57	54.41
STA. 606+14.91 to 611+74.18	42.46
STA. 635+34.31 to 637+19.00	14.02
<i>Side Road Omission</i>	
<i>(CH 4 - 2800 E Intersection - Sta. 637+19.00 to 637+74.50)</i>	
STA. 637+74.50 to 641+68.50	29.91
PROJECT TOTAL	157

PLOT DATE = 05-23-2007 10:57:00AM
 FILE NAME = shtsch.dgn
 PLOT SCALE = 1/8" = 1' IN.
 USER NAME = jwc

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES F.A.P. Route 315 (US 136) Section D-6 SHLDR RUMBLE STRIPS 2008-2 MASON COUNTY SCALE: VERT. _____ HORIZ. _____ DATE: MAY 23, 2007
DRAWN BY: JWC		CHECKED BY: RSC