

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	**	86	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

* D7 SAFETY 2008-1
 ** EFFINGHAM, CLAY, AND FAYETTE

SUMMARY OF QUANTITIES			90% FED. / 10% STATE	CONSTRUCTION TYPE CODE												
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	EFFINGHAM COUNTY						CLAY COUNTY		FAYETTE COUNTY				
				SFTY 3N LOCATION 1 SN 025-0060	SFTY 3N LOCATION 2 SN 025-0053	SFTY 3N LOCATION 3 SN 025-0061	SFTY 3J LOCATION 4 SN 025-0042	SFTY 3N LOCATION 5 SN 025-0073	SFTY 3N LOCATION 6 SN 025-0043	Y002-1C SIGN TRUSS M.P. 157.84	Y002-1C SIGN TRUSS M.P. 157.30	SFTY 3N LOCATION 7 SN 013-0027	SFTY 3N LOCATION 8 SN 026-0082	SFTY 3N LOCATION 9 SN 026-0081	SFTY 3N LOCATION 10 SN 026-0053	SFTY 3N LOCATION 11 SN 026-0071
20400800	FURNISHED EXCAVATION	CU YD	7891	800	844	631	179	449	527			835	845	585	1340	856
25000200	SEEDING, CLASS 2	ACRE	5.4	0.5	0.4	0.5	0.2	0.5	0.5			0.9	0.5	0.4	0.5	0.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	470	43	33	41	15	41	48			76	44	39	47	43
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	470	43	33	41	15	41	48			76	44	39	47	43
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	470	43	33	41	15	41	48			76	44	39	47	43
25002300	TEMPORARY SEEDING	ACRE	5.4	0.5	0.4	0.5	0.2	0.5	0.5			0.9	0.5	0.4	0.5	0.5
25100115	MULCH, METHOD 2	ACRE	5.4	0.5	0.4	0.5	0.2	0.5	0.5			0.9	0.5	0.4	0.5	0.5
28000300	TEMPORARY DITCH CHECKS	EACH	28	4	2	4		2	3			4	2	3	2	2
48101200	AGGREGATE SHOULDERS, TYPE B	TON	375													
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1330								168	207				
54200433	PIPE CULVERTS, TYPE 1 RCCP 18"	FOOT	353					353							920	410
54200439	PIPE CULVERTS, TYPE 1 RCCP 24"	FOOT	872		302											
54246205	INLET BOX, STANDARD 542526	EACH	3		1				1							42
54246305	INLET BOX, STANDARD 542526 (SPECIAL)	EACH	1					1					1			
55101200	STORM SEWER REMOVAL 24"	FOOT	10						10							
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	31		31											
60224005	MANHOLES, TYPE A, 6'-DIAMETER, TYPE B GRATE	EACH	3													2
60500060	REMOVING INLETS	EACH	1													
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	2													
60500305	FILLING INLETS	EACH	1													2
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1862.5													
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4					137.5				887.5	837.5			
63100167	TRAFFIC BARRIER TERMINAL TYPE 1 (SPECIAL) TANGENT	EACH	6					1					3			
63200310	GUARDRAIL REMOVAL	FOOT	254						154							
63400105	GUARD POSTS	EACH	100	10	10	10						100				
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5	0.5	0.5	0.5		10	10				10	10	10	10
67100100	MOBILIZATION	L SUM	1	0.1	0.1	0.1		0.1	0.1				0.5	0.5	0.5	0.5
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.1	0.1	0.1		0.1	0.1				0.1	0.1	0.1	0.1
78200410	GUARDRAIL MARKERS, TYPE A	EACH	36					4								

PLOT DATE = #DATE#
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 USER NAME = #USER#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____