

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	**	86	6

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

- D7 SAFETY 2008-1
- EFFINGHAM, CLAY, AND FAYETTE

GUARD POSTS

COUNTY	STRUCTURE NO.	LOCATION	STATION TO STATION	QUANTITY (EACH)
EFFINGHAM	SN 025-0060	1	4883+73 TO 4883+93 4890+09 TO 4890+29	5
EFFINGHAM	SN 025-0053	2	4779+39 TO 4779+59 4780+75 TO 4780+95	5
EFFINGHAM	SN 025-0061	3	4725+83 TO 4626+03 4727+19 TO 4727+39	5
EFFINGHAM	SN 025-0042	4	-----	0
EFFINGHAM	SN 025-0073	5	4480+61 TO 4480+81 4481+97 TO 4472+17	5
EFFINGHAM	SN 025-0043	6	4429+74 TO 4429+94 4431+12 TO 4431+32	5
CLAY	SN 013-0027	7	4203+96 TO 4204+16 4205+34 TO 4205+54	5
FAYETTE	SN 026-0082	8	3200+21 TO 3200+41 3201+49 TO 3201+79	5
FAYETTE	SN 026-0081	9	3088+21 TO 3088+41 3089+59 TO 3089+79	5
FAYETTE	SN 026-0053	10	2934+27 TO 2934+47 2936+00 TO 2936+20	5
EFFINGHAM	SN 026-0071	11	3045+14 TO 3045+34 3046+60 TO 3046+80	5
GRAND TOTAL				100

IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3

COUNTY	LOCATION	STRUCTURE NO.	STATION TO STATION	QUANTITY (EACH)
EFFINGHAM	1	SN 025-0060	4888+98 TO 4889+42 4889+58 TO 4890+04	1
EFFINGHAM	2	SN 025-0053	4779+64.56 TO 4780+10 4780+24.09 TO 4780+70	1
EFFINGHAM	3	SN 025-0061	4726+08 TO 4726+54 4726+68 TO 4727+14	1
EFFINGHAM	4	SN 025-0042	-----	0
EFFINGHAM	5	SN 025-0073	4480+86 TO 4481+32 4481+48 TO 4481+94	1
EFFINGHAM	6	SN 025-0043	4429+99 TO 4430+45 4430+62 TO 4431+08	1
CLAY	7	SN 013-0027	4204+21 TO 4204+67 4204+83 TO 4209+29	1
FAYETTE	8	SN 026-0082	3200+46 TO 3200+92 3201+08 TO 3201+54	1
FAYETTE	9	SN 026-0081	3088+46 TO 3088+92 3089+08 TO 3089+54	1
FAYETTE	10	SN 026-0053	2934+51 TO 2934+97 2935+50 TO 2935+95	1
FAYETTE	11	SN 026-0071	3045+40 TO 3045+85 3046+12 TO 3046+58	1
GRAND TOTAL				20

INLET BOX, STANDARD 542526

COUNTY	STRUCTURE NO.	LOCATION	STATION	QUANTITY (EACH)
EFFINGHAM	SN 025-0060	1	-----	-----
EFFINGHAM	SN 025-0053	2	4778+41	1
EFFINGHAM	SN 025-0061	3	-----	-----
EFFINGHAM	SN 025-0042	4	-----	-----
EFFINGHAM	SN 025-0073	5	-----	-----
EFFINGHAM	SN 025-0043	6	4432+32.5	1
CLAY	SN 013-0027	7	-----	-----
FAYETTE	SN 026-0082	8	3199+21	1
FAYETTE	SN 026-0081	9	-----	-----
FAYETTE	SN 026-0053	10	-----	-----
FAYETTE	SN 026-0071	11	-----	-----
GRAND TOTAL				3

PLUG EXISTING DRAINS

COUNTY	STRUCTURE NO.	LOCATION	STATION	SIDE	QUANTITY (EACH)
EFFINGHAM	SN 025-0060	1	4889+03 4889+04	LT RT	1 1
EFFINGHAM	SN 025-0053	2	-----	-----	-----
EFFINGHAM	SN 025-0061	3	4726+86 4726+85	LT RT	1 1
EFFINGHAM	SN 025-0042	4	-----	-----	-----
EFFINGHAM	SN 025-0073	5	-----	-----	-----
EFFINGHAM	SN 025-0043	6	-----	-----	-----
CLAY	SN 013-0027	7	4203+61	LT	1
FAYETTE	SN 026-0082	8	-----	-----	-----
FAYETTE	SN 026-0081	9	-----	-----	-----
FAYETTE	SN 026-0053	10	-----	-----	-----
FAYETTE	SN 026-0071	11	-----	-----	-----
GRAND TOTAL					5

EARTHWORK SCHEDULE

COUNTY	STRUCTURE NO.	LOCATION	STATION TO STATION	EARTH EXCAVATION (CU YD)	EARTH EX ADJ FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (=) OR SHORTAGE (-) (CU YD)
EFFINGHAM	SN 025-0060	1	4887+47 TO 4891+84	0	0	800	-800
EFFINGHAM	SN 025-0053	2	4778+40 TO 4781+69	38	28.5	872	-844
EFFINGHAM	SN 025-0061	3	4724+43 TO 4728+40	0	0	631	-631
EFFINGHAM	SN 025-0042	4	4645+66 TO 4649+54	0	0	180	-180
EFFINGHAM	SN 025-0073	5	4479+47 TO 4483+25	143	107.25	556	-449
EFFINGHAM	SN 025-0043	6	4427+99 TO 4432+32.5	85	63.75	591	-527
CLAY	SN 013-0027	7	2402+00 TO 4209+00	4	3	838	-835
FAYETTE	SN 026-0082	8	3199+00 TO 3203+00	100	75	920	-845
FAYETTE	SN 026-0081	9	3087+77 TO 3091+34	0	0	585	-585
FAYETTE	SN 026-0053	10	2933+00 TO 2937+40	0	0	1340	-1340
FAYETTE	SN 026-0071	11	3044+00 TO 3048+00	0	0	856	-856
TOTALS:				370*	277.5*	8169	-7891

* EARTH EXCAVATION WILL NOT BE PAID FOR SEPARATELY. THE MAJORITY OF THIS QUANTITY RESULTS FROM THE INSTALLATION OF NEW PIPE CULVERTS AND IS THEREFORE INCLUDED, BY THE SPECIFICATIONS, IN THE COST OF PIPE CULVERT AT THE SIZE SPECIFIED IN THE PLANS.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY