

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNITS	TOTAL	CONSTRUCTION TYPE CODE 100% STATE	
				ROADWAY	BRIDGE
				I000-2A	X024-2A
20200100	EARTH EXCAVATION	CU YD	78	78	0
20400800	FURNISHED EXCAVATION	CU YD	17	17	0
25000200	SEEDING, CLASS 2	ACRE	0.25	0.25	0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23	0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23	23	0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23	0
25100115	MULCH, METHOD 2	ACRE	0.25	0.25	0.0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	25	25	0
28000300	TEMPORARY DITCH CHECKS	EACH	3	3	0
28000500	INLET AND PIPE PROTECTION	EACH	6	6	0
28100107	STONE RIPRAP, CLASS A4	SQ YD	205	0	205
28200200	FILTER FABRIC	SQ YD	205	0	205
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	321	234	87
30201500	LIME	TON	6.4	4.7	1.7
35100100	AGGREGATE BASE COURSE, TYPE A	TON	110	80	30
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	30	30	0
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.0	1.0	0.0
40600300	AGGREGATE (PRIME COAT)	TON	5	5	0
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	41	41	0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	289	289	0
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	82	82	0
40701901	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11"	SQ YD	321	234	87
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	23	23	0
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	402	402	0
44000100	PAVEMENT REMOVAL	SQ YD	276	276	0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	89	89	0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	0	1
50105220	PIPE CULVERT REMOVAL	FOOT	124	124	0
50300225	CONCRETE STRUCTURES	CU YD	38.0	0.0	38.0
50800105	REINFORCEMENT BARS	POUND	3370	0	3370
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1	0
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1020	0	1020

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNITS	TOTAL	CONSTRUCTION TYPE CODE 100% STATE	
				ROADWAY	BRIDGE
				I000-2A	X024-2A
51202305	DRIVING PILES	FOOT	1020	0	1020
51203600	TEST PILE STEEL HP12X53	EACH	1	0	1
51204650	PILE SHOES	EACH	17	0	17
51500100	NAME PLATES	EACH	1	0	1
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	232	232	0
54213450	END SECTIONS, 15"	EACH	6	6	0
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	37.5	37.5	0.0
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	1	1	0
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1	0
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1	1	0
* 63100175	TRAFFIC BARRIER TERMINAL, TYPE 2 (SPECIAL)	EACH	2	2	0
63200310	GUARDRAIL REMOVAL	FOOT	25	25	0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	0
67100100	MOBILIZATION	L SUM	1	1	0
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	0
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15	0
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	1	0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	675	675	0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4	0
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	0
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	4		4
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4	4	0
X0323330	PRECAST CONCRETE SUBSTRUCTURE	L SUM	1	0	1
X0325701	STEEL RAILING, TYPE 2399	FOOT	63	0	63
* XX005496	TRAFFIC BARRIER TERMINAL TYPE 6A (SPECIAL)	EACH	3	3	0
X0325898	THREE-SIDED PRECAST CONCRETE STRUCTURE 24' x 8'	FOOT	41	0	41

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAU ROUTE 9296
 SECTION 65BR
 MONROE COUNTY
 SCALE: VERT. _____
 HORIZ. _____
 DATE JANUARY 2007
 DRAWN BY LLO
 CHECKED BY LEL