

F.A.U. RT. 9296	SECTION 65BR	COUNTY MONROE	TOTAL SHEETS 22	SHEET NO. 5
STA.		TO STA.		
FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT				

CONTRACT NO. 76387

GUARDRAIL SCHEDULE

LOCATION STATION TO STATION	STEEL BRIDGE RAIL (FOOT)	STEEL PLATE BEAM GUARD RAIL, TYPE A (FOOT)	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT) (EACH)	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED) (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 6A (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 6A (SPECIAL) (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 2 (SPECIAL) (EACH)
STRUCTURE 26+34.00	63.0						
RT. 26+86.25 27+23.75		37.5					
LT. 25+40.12 25+90.12				1			
RT. 27+23.75 27+73.75			1				
LT. 25+90.12 26+08.87						1	
LT. 26+38.00 26+56.75						1	
RT. 26+12.00 26+30.75						1	
RT. 26+57.00 26+88.25					1		
LT. 26+56.75 26+67.00							1
RT. 26+05.00 26+12.00							1
TOTAL	63.0	37.5	1	1	1	3	2

REMOVAL SCHEDULE

LOCATION STATION TO STATION	HMA SURFACE REMOVAL - BUTT JOINT (SQ YD)	**HMA SURFACE REMOVAL, VARIABLE DEPTH (SQ YD)	PAVEMENT REMOVAL (SQ YD)	PIPE CULVERT REMOVAL (FOOT)	CONCRETE HEADWALL REMOVAL (EACH)	GUARDRAIL REMOVAL (FOOT)
P.E. LT. 25+42.29	26.1					
S.R. LT. 26+84.31	88.2					
C.E. RT. 25+83.00	30.0					
MAINLINE 24+84.00 25+09.00	72.2					
LT. 24+84.00 25+74.00			10.0			
LT. 25+09.00 25+74.00		93.9				
RT. 24+84.00 25+83.00			11.0			
RT. 25+09.00 25+83.00		106.9				
LT. 25+74.00 26+19.00			65.0			
RT. 25+83.00 26+19.00			52.0			
LT. 26+48.97 26+85.00			52.0			
LT. 26+85.00 27+84.00			11.0			
RT. 26+48.97 26+94.00			65.0			
LT. 26+85.00 27+59.00		106.9				
RT. 26+94.00 27+59.00		93.9				
RT. 26+94.00 27+84.00			10.0			
MAINLINE 27+59.00 27+84.00	72.2					
20' LT. 25+34.00				22	1	
25' RT. 25+80.00				57		
21' LT. 26+62.00				45		
16' RT. 27+98.00 28+23.00						25
TOTAL	288.7	401.6	276.0	124	1	25

**VARIABLE DEPTH SURFACE REMOVAL REQUIRED TO ALSO CORRECT EXISTING PAVEMENT CROWN. SEE CROSS-SECTIONS

EROSION CONTROL SCHEDULE

LOCATION STATION TO STATION	TEMP. EROS. CONTROL SEEDING* (LB)	TEMPORARY DITCH CHECKS (EACH)	INLET AND PIPE PROTECTION (EACH)	STONE RIPRAP, CLASS A4 (SQ YD)	FILTER FABRIC (SQ YD)
LT. 24+84.00 TO 25+30.00	0.60				
LT. 25+39.00 TO 26+00.00	1.64				
LT. 26+49.00 TO 26+74.00	0.59				
LT. 26+94.00 TO 27+84.00	1.29				
RT. 24+84.00 TO 25+76.00	1.41				
RT. 26+06.00 TO 26+20.00	0.36				
RT. 26+71.00 TO 27+84.00	0.50				
26' LT. 25+14.00		1			
26' RT. 25+32.00		1			
25' LT. 27+25.00		1			
26' LT. 25+25.00			1		
26' RT. 25+51.00			1		
26' LT. 26+04.00			1		
26' RT. 26+24.00			1		
25' LT. 26+43.00			1		
25' LT. 27+12.00			1		
4 QUADRANTS @ STRUCTURE				205	205
TOTAL	6.4	3	6	205	205

* BDE REQUIRES MINIMUM 0.25 ACRES OF SEEDING. THE SUMMARY OF QUANTITIES REFLECTS RATE FOR 0.25 ACRES

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAU ROUTE 9296
 SECTION 65BR
 MONROE COUNTY
 SCALE: VERT. NONE
 HORIZ. DATE JANUARY 2007
 DRAWN BY LLQ
 CHECKED BY LEL