

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 100% STATE 1000-2A	URBAN 100% STATE Y031-1F
20200100	EARTH EXCAVATION	CU YD	339	339	
20400800	FURNISHED EXCAVATION	CU YD	517	517	
25000115	SEEDING, CLASS 1B	ACRE	0.3	0.3	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27	27	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27	27	
25000600 25100115	POTASSIUM FERTILIZER NUTRIENT MULCH, METHOD 2	POUND ACRE	27 0.6	27 0.6	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	60	60	
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	750	750	
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	667	667	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.8	1.8	
40600300	AGGREGATE (PRIME COAT)	TON	8.4	8.4	
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	121	121	
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	242	242	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	2319	2319	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	59	59	
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	250	250	
44003100	MEDIAN REMOVAL	SQ FT	14	14	
44004250	PAVED SHOULDER REMOVAL	SQ YD	524	524	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	699	699	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	88	88	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 100% STATE 1000-2A	URBAN 100% STATE Y031-1F
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	27	27	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	326	326	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	25	25	
50800105	REINFORCEMENT BARS	POUND	440	440	
54200439	PIPE CULVERTS, TYPE 1 RCCP 24"	FOOT	5.5	5.5	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	205	205	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	97	97	
60623711	CONCRETE MEDIAN	SQ FT	39	39	
66500700	WOVEN WIRE GATES, 4' X 8' SINGLE	EACH	1	1	
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	8	8	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	540	540	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	156	156	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1929	1929	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	183	183	