ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
789	IRS-1	MADISON	26	3

EXISTING CONDITIONS:

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	100% STATE URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE LOCATION #1 1000	LOCATION #2 1000	LOCATION #3 1000
28000400	PERIMETER EROSION BARRIER	FOOT	350			350
28100207	STONE RIPRAP, CLASS A4	TON	780			780
28200200	FILTER FABRIC	SQ YD	1160			1160
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	12.1	1.8	7.5	2.8
40600300	AGGREGATE (PRIME COAT)	TON	59	9	36	14
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	1274	195	785	294
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600990	TEMPORARY RAMP	SQ YD	1351	456	720	175
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2546	390	1569	587
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	29	29		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	38288	5643	23814	8831
44200152	PAVEMENT PATCHING, TYPE I, 13 INCH	SQ YD	10	10		
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	74	6	27	41
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	77		77	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	85	85		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	902	26	646	230
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	2	2	1
67100100	MOBILIZATION	L SUM	1	0.3	0.3	0.4
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.3	0.3	0.4
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.3	0.3	0.4
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	2		2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7518	1488	4694	1336
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	23982	4557	14421	5004
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	628	124	392	112
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	407	156	188	63
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21450	3999	12663	4788
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	240		240	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	302	93	173	36
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2382		2382	
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	410		410	

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	100% STATE URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE LOCATION #1 1000	LOCATION #2 1000	LOCATION #3 1000
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	163	26	99	38
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1197		1197	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	208	49	119	40
* 80300100	LOCATING UNDERGROUND CABLE	FOOT	340	80	200	60
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	4285	770	2890	625
* X7800450	POLYUREA PAVEMENT MARKING TYPE I - CURB	FOOT	932	452	336	144
* X7800455	POLYUREA PAVEMENT MARKING TYPE I - RAISED MEDIAN	SQ FT	505	58	302	145

*SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. 789 (IL RTE. 3 & 111)
SECTION IRS-1
MADISON COUNTY

PLOT DATE: 4/5/2007

PLAN NOTE BOOK NO. SURVEYED / DRAWN / ALIGNMENT CHECKED / PROFILE CHECKED / CLOD FILE LINE BY DATE