F. A. P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
789	IRS-1	MADISON	26	5
STA. _____		TO STA. _____		
EXISTING CONDITIONS: _____				

ILLINOIS DEPARTMENT OF TRANSPORTATION

PATCHING AND RESURFACING SCHEDULE

PATCHING SCHEDULE LOCATION #1

STATION	SIZE	TYPE I SQ. YD.	TYPE II SQ. YD.	LANE
5+97	4 x 11	4.89		E.B. DRIVE LANE
5+97	4 x 11	4.89		LT. TURN LANE
7+49	4 x 13		5.78	E.B. DRIVE LANE
TOTALS		**9.78**	**5.78**	

PATCHING SCHEDULE LOCATION #2

STATION	SIZE	TYPE II SQ. YD.	TYPE III SQ. YD.	LANE
104+16	12 x 12		16.00	E.B. DRIVE LANE
104+16	12 x 12		16.00	E.B. PASS LANE
104+16	6 x 16	10.67		W.B. DRIVE LANE
104+16	6 x 12	8.00		W.B. PASS LANE
110+07	6 x 13	8.67		E.B. PASS LANE
111+84	16 x 12.5		22.22	E.B. DRIVE LANE
111+84	16 x 12.5		22.22	E.B. PASS LANE
TOTALS		**27.34**	**76.44**	

PATCHING SCHEDULE LOCATION #3

STATION	SIZE	TYPE II SQ. YD.	LANE
254+73	4 x 12	5.33	E.B. DRIVE LANE
254+73	4 x 12	5.33	E.B. PASS LANE
259+68	4 x 12	5.33	E.B. DRIVE LANE
259+68	4 x 12	5.33	E.B. PASS LANE
259+68	4 x 12	5.33	W.B. DRIVE LANE
259+68	4 x 12	5.33	W.B. PASS LANE
259+68	4 x 20	8.89	W.B. LT. TURN LANE
TOTALS		**40.87**	

PATCHING SCHEDULE TOTALS

LOCATIONS	TYPE I SQ. YD.	TYPE II SQ. YD.	TYPE III SQ. YD.
LOCATION #1	9.78	5.78	
LOCATION #2		27.34	76.44
LOCATION #3		40.87	
TOTALS	**9.78**	**73.99**	**76.44**

LOCATION #1 RESURFACING SCHEDULE

STATION	HOT MIX ASPHALT SURF. N90 TONS	LEVELING BINDER N90 TONS	BIT. MATL. PRIME COAT TONS	AGGREGATE PRIME COAT TONS	HOT-MIX ASPHALT REMOVAL SQ. YDS.	AGGREGATE SHOULDER TYPE B TONS	HOT-MIX ASPHALT SHOULDER TONS	INCIDENTAL HOT MIX ASPHALT TONS
0+00 TO 9+37	390	195	1.8	9	5643	85	26	29
LOCATION #1 TOTALS	390	195	1.8	9	5643	85	26	29

LOCATION #2 RESURFACING SCHEDULE

STATION	HOT MIX ASPHALT SURF. N90 TONS	LEVELING BINDER N90 TONS	BIT. MATL. PRIME COAT TONS	AGGREGATE PRIME COAT TONS	HOT-MIX ASPHALT REMOVAL SQ. YDS.	HOT-MIX ASPHALT SHOULDER TONS
104+10 TO 129+13	1271	636	6.3	30	20269	646
BRIDGE OMMISSION	-	-	-	-	-	-
133+87 TO 136+38	298	149	1.2	6	3545	-
LOCATION #2 TOTALS	1569	785	7.5	36	23814	646

LOCATION #3 RESURFACING SCHEDULE

STATION	HOT MIX ASPHALT SURF. N90 TONS	LEVELING BINDER N90 TONS	BIT. MATL. PRIME COAT TONS	AGGREGATE PRIME COAT TONS	HOT-MIX ASPHALT REMOVAL SQ. YDS.	HOT-MIX ASPHALT SHOULDER TONS
253+00 TO 264+18	587	294	2.8	14	8831	230
LOCATION #3 TOTALS	587	294	2.8	14	8831	230

ILLINOIS DEPARTMENT OF TRANSPORTATION

PATCHING AND RESURFACING SCHEDULES

F.A.P. 789 (IL RTE. 3 & 111)
SECTION IRS-1
MADISON COUNTY

PLOT DATE: 4/5/2007

PLAN
NOTE BOOK
NO. _____
CORRECT
PLOTTED
ALIGNMENT CHECKED
PLANS APPROVED
CADD FILE NAME
BY
DATE

#DATE#
4/5/2007
C:\Projects\Active\80071\Patch\80071patch.dgn
*REF_
*REF_