

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
778	4BR-1	HARDIN	69	40
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT		

PAVEMENT MARKING SCHEDULE				
LOCATION	DESCRIPTION	SHORT-TERM PAVEMENT MARKING	PAINT PAVEMENT MARKING - LINE	TEMP PAVEMENT MARKING - LINE
			4"	4"
		FOOT	FOOT	FOOT
STA. 1018+84 TO STA. 1020+61, CENTERLINE	SKIP DASH YELLOW CENTERLINE	18		
STA. 1021+59.33 TO STA. 1022+00.67, CENTERLINE	SKIP DASH YELLOW CENTERLINE	4		
STA. 1022+99 TO STA. 1024+82, CENTERLINE	SKIP DASH YELLOW CENTERLINE	18		
STA. 1018+84 TO STA. 1020+61, CENTERLINE	SKIP DASH AND SOLID YELLOW CENTERLINE		221	221
STA. 1021+59.33 TO STA. 1022+00.67, CENTERLINE	SKIP DASH AND SOLID YELLOW CENTERLINE		52	52
STA. 1022+99 TO STA. 1024+82, CENTERLINE	SKIP DASH AND SOLID YELLOW CENTERLINE		229	229
STA. 1020+60 TO STA. 1023+00, RT	SOLID WHITE EDGE LINE		240	240
STA. 1020+56.25 TO STA. 1023+03.75, LT	SOLID WHITE EDGE LINE		248	248
TOTALS		40	990	990

GUARDRAIL REMOVAL SCHEDULE	
LOCATION	FOOT
STRUCTURE NO. 035-0008 - NE	45*
STRUCTURE NO. 035-0008 - NW	45*
STRUCTURE NO. 035-0008 - SE	45*
STRUCTURE NO. 035-0008 - SW	45*
TOTALS	180.0

* QUANTITY MAY VARY DEPENDING ON LAYOUT PROPOSED BY THE CONTRACTOR. SEE SHEET NO. 45 FOR DETAILS.

BASE COURSE SCHEDULE	
LOCATION	BASE COURSE WIDENING, 10"
SQ YD	
NE QUADRANT	41
NW QUADRANT	41
SE QUADRANT	41
SW QUADRANT	41
TOTALS	164

PAVEMENT MARKERS AND REMOVAL SCHEDULE	
LOCATION	RRPM (BRIDGE)
EACH	
STA. 1021+80	1
TOTAL	1

WORK ZONE AND PAVEMENT MARKING REMOVAL SCHEDULE			
LOCATION	PAVEMENT MARKING DESCRIPTION	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL
		SQ. FT	SQ. FT
CENTERLINE	SHORT-TERM	14	150
EDGELINES	TEMPORARY	477	
STA. 1020+60 TO STA. 1023+00, RT	EDGELINES		80
STA. 1020+56.25 TO STA. 1021+59.33, LT	EDGELINES		35
STA. 1022+00.67 TO STA. 1023+03.75, LT	EDGELINES		35
TOTALS		491	300

EROSION CONTROL SCHEDULE		
LOCATION	PERIMETER EROSION BARRIER	TEMPORARY EROSION CONTROL SEEDING (2 APPLICATIONS)
	FOOT	POUND
NE QUADRANT	140	5
NW QUADRANT	140	5
SE QUADRANT	140	5
SW QUADRANT	140	5
TOTAL	560	20

GUARDRAIL SCHEDULE				
LOCATION	TRAFFIC BARRIER TERMINAL TYPE 6A	GUARDRAIL MARKERS TYPE A	BARRIER WALL MARKERS, TYPE B	STEEL RAILING, TYPE SM
	EACH		EACH	FOOT
STRUCTURE NO. 035-0008 - NE	1	1		
STRUCTURE NO. 035-0008 - NW	1	1		
STRUCTURE NO. 035-0008 - SE	1	1		
STRUCTURE NO. 035-0008 - SW	1	1		
STRUCTURE NO. 035-0008 - BRIDGE			2	75
TOTALS	4	4	2	75

SEEDING SCHEDULE							
LOCATION	SEEDING, CLASS 2A	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2
	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE
NE QUADRANT	0.025	0.025	2.25	2.25	2.25	0.05	0.05
NW QUADRANT	0.025	0.025	2.25	2.25	2.25	0.05	0.05
SE QUADRANT	0.025	0.025	2.25	2.25	2.25	0.05	0.05
SW QUADRANT	0.025	0.025	2.25	2.25	2.25	0.05	0.05
TOTALS	0.10	0.10	9.0	9.0	9.0	0.20	0.20

HMA SURF REMOVAL SCHEDULE	
LOCATION	5"
SQ. YD	
NORTH ABUTMENT	6
SOUTH ABUTMENT	6
TOTALS	12

NOTE: HMA SURFACE REMOVAL IS INCLUDED IN THE COST OF REMOVAL OF EXISTING SUPERSTRUCTURE.

SCHEDULE OF QUANTITIES
F.A.P. ROUTE 778 (IL ROUTE 34)
SECTION 4BR-1
HARDIN COUNTY