CONTRACT NO. 83905

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1362	06-00047-00-LS	COOK	59	7
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PIPE SCHEDULE

PIPE NO.	FROM STRUCTURE	TO STRUCTURE	MATERIAL	TYPE	LENGTH (FT)	DIA. (IN)	UPPER INVERT	LOWER INVERT	SLOPE	TBF
P-101	S-103	S-101	SS WM REQ	1	57	12	645.00	644.43	1.00	56.10
P-102	S-107	S-102	RCP	1	39	12	645.11	644.72	1.00	34.00
P-103	S-105	S-103	RCP	1	21	12	645.20	645.00	0.95	19.10
P-105	S-106	S-105	RCP	1	11	12	645.27	645.20	0.64	1.20
P-107	S-110	S-109	RCP	1	10	12	647.00	646.90	1.00	3.70
P-108	S-111	S-112	RCP	1	85	12	649.67	649.57	0.12	11.20
P-109	S-112	S-115	RCP	1	20	12	649.57	649.49	0.40	2.60
P-110	S-114	S-113	RCP	1	14	12	647.00	646.94	0.43	5.30
P-111	S-116	S-117	RCP	1	26	12	648.79	648.69	0.38	25.20
									TOTAL=	158.40

PIPE NO.	FROM STRUCTURE	TO STRUCTURE	MATERIAL	TYPE	LENGTH (FT)	DIA. (IN)	UPPER INVERT	LOWER INVERT	SLOPE	TBF
P-201	S-201	S-202	SS WM REQ	1	47	12	646.32	645.85	1.00	43.29
P-202	S-203	S-222	RCP	1	7	36	646.51	646.47	0.57	12.84
P-203	S-206	S-203	RCP	1	167	36	647.42	646.51	0.54	144.62
P-204	S-207	S-206	RCP	1	30	36	647.57	647.42	0.50	25.98
P-205	S-208	S-209	RCP	1	17	24	648.77	648.47	1.76	12.29
P-206	S-209	S-210	RCP	1	40	18	649.32	648.97	0.88	27.36
P-207	S-601	S-210	RCP	1	50	12	649.52	649.32	0.40	25.38
P-208	S-210	S-211	RCP	1	13	18	649.45	649.32	1.00	8.41
P-209	S-211	S-213	RCP	1	13	18	649.57	649.45	0.92	5.30
P-210	S-215	S-214	SS WM REQ	1	65	12	650.20	649.80	0.62	22.17
P-211	S-214	S-213	RCP	1	15	15	649.76	649.57	1.27	5.43
P-212	S-216	S-301	RCP	1	80	12	650.12	649.80	0.40	29.00
P-213	S-217	S-215	RCP	1	48	12	650.35	650.20	0.31	15.36
P-214	S-204	S-206	SS WM REQ	1	67	12	649.25	648.58	1.00	24.25
P-215	S-220	S-219	RCP	1	58	24	648.45	648.25	0.34	46.69
P-216	S-208	S-220	RCP	1	4	24	648.47	648.45	0.50	3.06
P-217	S-219	S-207	RCP	1	12	24	648.25	648.17	0.67	9.17
P-218	S-221	S-204	RCP	1	10	12	649.35	649.25	1.00	3.41
P-219	S-222	S-201	RCP	1	7	12	646.47	646.32	2.14	5.99
									TOTAL=	470.00

PIPE NO.	FROM STRUCTURE	TO STRUCTURE	MATERIAL	TYPE	LENGTH (FT)	DIA. (IN)	UPPER INVERT	LOWER INVERT	SLOPE	TBF
P-301	S-301	S-322	RCP	1	6	12	649.80	649.78	0.33	2.40
P-302	S-303	S-302	RCP	1	5	12	646.15	646.09	1.20	4.93
P-303	S-304	CB 1248	RCP	1	68	12	650.09	650.09	0.00	13.10
P-304	S-307	S-305	RCP	1	43	12	647.00	646.57	1.00	28.60
P-305	S-309	S-310	RCP	1	38	12	648.02	647.87	0.39	12.00
P-306	S-701	S-310	RCP	1	22	12	647.96	647.87	0.41	3.00
P-307	S-310	S-311	RCP	1	10	12	647.87	647.77	1.00	3.40
P-308	S-315	S-314	RCP	1	5	12	646.05	646.00	1.00	3.70
P-309	S-316	S-317	RCP	1	15	12	646.15	646.00	1.00	10.40
P-310	S-318	CB 921	RCP	1	9	12	645.87	645.78	1.00	6.30
P-311	S-319	S-320	RCP	1	13	12	649.00	648.87	1.00	14.60
P-312	S-321	EXISTING	RCP	1	16	12	649.82	649.76	0.38	3.80
P-313	S-322	EXISTING	RCP	1	4	12	649.78	649.76	0.50	1.60
									TOTAL=	107.83

PIPE NO.	FROM STRUCTURE	TO STRUCTURE	MATERIAL	TYPE	LENGTH (FT)	DIA. (IN)	UPPER INVERT	LOWER INVERT	SLOPE	TBF
P-401	S-402	S-401	RCP	1	15	12	646.15	646.00	1.00	10.40
P-402	S-405	S-406	RCP	1	15	12	646.15	646.00	1.00	10.40
P-403	S-403	S-404	RCP	1	15	12	647.92	647.86	0.40	3.90
P-404	S-404	STM 750	RCP	1	48	12	647.86	647.67	0.40	13.30
									TOTAL=	38.00

PIPE NO.	FROM STRUCTURE	TO STRUCTURE	MATERIAL	TYPE	LENGTH (FT)	DIA. (IN)	UPPER INVERT	LOWER INVERT	SLOPE	TBF
P-501	S-501	S-502	RCP	1	85	12	646.50	646.16	0.40	21.80
P-502	S-502	S-503	RCP	1	63	12	646.16	645.91	0.40	16.20
P-503	S-504	S-505	RCP	1	10	12	646.83	646.75	0.80	2.20
									TOTAL=	40.20

PIPE NO.	FROM STRUCTURE	TO STRUCTURE	MATERIAL	TYPE	LENGTH (FT)	DIA. (IN)	UPPER INVERT	LOWER INVERT	SLOPE	TBF
P-701	S-702	S-701	RCP	1	22	12	648.05	647.96	0.41	4.27
P-702	S-703	S-702	RCP	1	28	12	648.16	648.05	0.39	5.43
									TOTAL=	9.70

PLOT DATE = 10/29/2007
FILE NAME = N:\HANKOD\HEIGHTS\06279\Civil\06279ts-2.sch
PLOT SCALE = 50'
USER NAME = PMAGNELLI

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PIPE SCHEDULE

SCALE: VERT.
HORIZ. 50'
DATE 10/29/2007

DRAWN BY PL
CHECKED BY LMF