

SUMMARY OF QUANTITIES				
CODE	PAY ITEM	UNIT	TOTAL	Y003
			QUANTITY	80% Federal 20% Local
20100110	TREE REMOVAL (6 TO 15 INCH DIAMETER)	UNIT	30	30
20200100	EARTH EXCAVATION	CUYD	275	275
20800150	TRENCH BACKFILL	CUYD	40	40
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQYD	1,000	1,000
* 25000400	NITROGEN FERTILIZER NUTRIENT	LBS	15	15
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	LBS	15	15
* 25000600	POTASSIUM FERTILIZER NUTRIENT	LBS	15	15
* 25200100	SODDING	SQYD	1,000	1,000
* 25200200	SUPPLEMENTAL WATERING	UNIT	10	10
* 25300500	TOPSOIL FOR PLANTING	CUYD	45	45
28000510	INLET FILTERS	EACH	25	25
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQYD	1,950	1,950
35300200	PORTLAND CEMENT CONCRETE BASE COURSE, 7"	SQYD	1,350	1,350
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	75	75
40600300	AGGREGATE (PRIME COAT)	TON	20	20
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	26	26
42000300	PORTLAND CEMENT CONCRETE PAVEMENT, 8"	SQYD	100	100
42101300	PROTECTIVE COAT	SQYD	4,475	4,475
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT,	SQYD	410	410
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	SQFT	27,600	27,600
42400800	DETECTABLE WARNINGS	SQFT	1,350	1,350
44000100	PAVEMENT REMOVAL	SQYD	100	100
44000154	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/4"	SQYD	585	585
44000200	DRIVEWAY PAVEMENT REMOVAL	SQYD	650	650
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,570	3,570
44000600	SIDEWALK REMOVAL	SQFT	46,000	46,000
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	45	45
60206905	CATCH BASIN, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	1	1
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	3	3
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	6	6
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1
60266600	VALVE BOXES TO BE ADJUSTED	EACH	5	5
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	30	30
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	4	4

\* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES				
CODE	PAY ITEM	UNIT	TOTAL	Y003
			QUANTITY	80% FEDERAL 20% LOCAL
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	3	3
60601005	CONCRETE CURB, TYPE B (SPECIAL)	FOOT	550	550
60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MOD.)	FOOT	3,570	3,570
67100100	MOBILIZATION	LSUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	LSUM	1	1
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	2	2
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	1,045	1,045
* 81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	125	125
81400115	HANDHOLE TO BE ADJUSTED	EACH	21	21
* 81603080	UNIT DUCT, 600V, 3-1C NO. 4, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1 1/4" DIA., POLYETHYLENE	FOOT	8,025	8,025
* 81702400	ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 3-1/C NO. 2	FOOT	300	300
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	6,475	6,475
* 82500505	LIGHTING CONTROLLER, SPECIAL	EACH	2	2
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	341	341
* A2000724	TREE, ACER PLATANOIDES COLUMNARE (COLUMNAR NORWAY MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	2	2
* A2004724	TREE, GLEDITSIA TRIACANTHOS INTERMIS SHADEMASTER (SHADEMASTER THORNLESS COMMON HONEY LOCUST) 3" CALIPER, BALLED AND BURLAPPED	EACH	6	6
* A2008124	TREE, TILIA CORDATE GREENSPIRE (GREENSPIRE LITTLE LEAF LINDEN), 3" CALIPER, BALLED AND BURLAPPED	EACH	7	7
* B2005616	TREE, PYRUS CALLERYANA BRADFORD (BRADFORD GALLERY PEAR) 2" CALIPER, TREE FORM BALLED AND BURLAPPED	EACH	2	2
XX001186	PLANTER REMOVAL	EACH	21	21
XX001672	STORM SEWERS, PVC, SDR 26, 12"	FOOT	80	80
XX003059	DECORATIVE BRICK SIDEWALK	SQFT	27,000	27,000
X0322256	TEMPORARY INFORMATION SIGNING	SQFT	103	103
XX003424	CONNECTION TO EXISTING STRUCTURE	EACH	2	2

\* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES				
CODE	PAY ITEM	UNIT	TOTAL	Y003
			QUANTITY	80% FEDERAL 20% LOCAL
X0323426	SEDIMENT CONTROL DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	25	25
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL M	6	6
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
△ Z0076600	TRAINEES	HOUR	500	500
* XX007151	PLANTER RAILING	FOOT	550	550
* XX007152	DECORATIVE LIGHT POLE, ALUMINUM, 12' MOUNTING HEIGHT	EACH	56	56
* XX007153	DECORATIVE ACORN STYLE LUMINAIRE, SODIUM VAPOR, TENON MOUNT, 70 WATT	EACH	56	56
XX007000	PORTLAND CEMENT CONCRETE BASE COURSE, 3"	SQFT	8,075	8,075
* XX006937	GROUND ROD, 5/8" X 10 FT	EACH	56	56

\* DENOTES SPECIALTY ITEM

△ Y080

revised 12/21/07  
pay item x0323857 has been eliminated

Drawing File: W:\Projects\76006033 - Grand Ave Streetscape\SUMMO1.dwg Dec 18, 2007 - 2:18pm

	◆ Civil Engineers	9933 Roosevelt Road
	◆ Municipal Consultants	Westchester, Illinois 60154-2780
	◆ Established 1911	Phone: 708/865-8300
		Fax: 708/865-1212

**GRAND AVENUE STREETScape PROJECT  
VILLAGE OF RIVER GROVE, ILLINOIS**

**SUMMARY OF QUANTITIES**

SCALE:	NONE	SHEET	4
DRAWN BY:	LEV/ECW/MK	OF	35
BOOK NO.:	1441,1443,1516		
DATE:	10/15/07		
REVISION:	Addendum #1 - 12/14/07	E.H.E. NO.:	760-06-03320