



**BEGIN IMPROVEMENT
STATION 11+85**

TREE REPLACEMENT				
CODE	COMMON NAME	SCIENTIFIC NAME	SIZE	QUANTITY
A	BRADFORD PEAR	PYRUS CALLERYANA BRADFORD	2" CALIPER	1
B	COLUMNAR NORWAY MAPLE	ACER PLANTANOIDES COLUMNARE	3" CALIPER	1
C	GREENSPIRE LINDEN	TILIA CORDATA GREEN	3" CALIPER	4
D	SHADEMASTER HONEY LOCUST	GLEDTISIA TRIACANTHOS INTERMIS SHADEMASTER	3" CALIPER	4

NOTE: ALL TREES BALLED AND BURLAPPED

LANDSCAPING NOTES

SODDING:
ALL DISTURBED AREAS INDICATED ON CROSS SECTION OR LANDSCAPING PLANS TO BE SODDED, INCLUDING FERTILIZER NUTRIENTS*, AND SUPPLEMENTAL WATERING WHICH IS TO BE USED AFTER THE INITIAL WATERING (AS SPECIFIED AND AS DIRECTED BY THE ENGINEER) AT THE RATE OF 10 GALLONS PER SQUARE YARD SODDING. SODDED SLOPES WHICH ARE 2:1 OR STEEPER SHALL BE STAKED. (PROVIDE A 3" STRIP AROUND CATCH BASINS IN SEEDING AREAS).

FERTILIZER NUTRIENTS* FOR SODDING:
USE A FERTILIZER WITH A 1:1:1 RATIO PER ACRE:
60 LBS. NITROGEN FERTILIZER NUTRIENT
60 LBS. PHOSPHORUS FERTILIZER NUTRIENT
60 LBS. POTASSIUM FERTILIZER NUTRIENT
TOTAL: 180 LBS. PER ACRE

TREE REPLACEMENT:
TREE TYPE & LOCATION TO BE DETERMINED IN THE FIELD BY THE VILLAGE LICENSED FORESTER

4" TOP SOIL LAYER:
SOIL SHALL BE SPREAD AS INDICATED ON THE TYPICAL CROSS SECTIONS.

LEGEND OF SYMBOLS

SYMBOL	DESCRIPTION
	PROPOSED CONCRETE AREA
	PROPOSED DECORATIVE BRICK SIDEWALK AREA
	PROPOSED CONCRETE DRIVEWAY AREA
	PROPOSED SODDED PARKWAY
	PROPOSED TREE WITH PLANTER

Drawing file: W:\Projects\76006033 - Grand Ave Streetscape\Landscaping_Grand.dwg Oct 16, 2007 - 2:24pm

HANCOCK ENGINEERING
 Civil Engineers
 Municipal Consultants
 Established 1911
 9933 Roosevelt Road
 Westchester, Illinois 60154-2780
 Phone: 708/865-0300
 Fax: 708/865-1212

**GRAND AVENUE STREETScape PROJECT
VILLAGE OF RIVER GROVE, ILLINOIS**

**LANDSCAPING PLAN
GRAND AVENUE**

SCALE:	1"=30'	SHEET	27
DRAWN BY:	LEV/ECW/MK	OF	35
BOOK NO.:	1441,1443,1516		
DATE:	10-15-07		
REVISION:	E.H.E. NO.: 760-06-03320		