

# SUMMARY OF QUANTITIES

| CODE NUMBER  | PAY ITEM   | TOTAL BID QNTY | UNIT  | CONSTRUCTION TYPE CODE |         |         |
|--------------|--|----------------|-------|------------------------|---------|---------|
|              |  |                |       | 1000-2A                | Y030-1E | Y031-1F |
| * 83006200   | LIGHT POLE, ALUMINUM, 30FT MH, 6 FT MAST ARM   | 28             | EACH  |                        | 28      |         |
| * 83600200   | LIGHT POLE FOUNDATION, 24" DIAMETER  | 400            | FOOT  |                        | 400     |         |
| * 83800505   | BREAKAWAY DEVICE, COUPLING, WITH ALUMINUM SKIRT  | 112            | EACH  |                        | 112     |         |
| * 85700200   | FULL ACTUATED CONTROLLER AND TYPE IV CABINET   | 1              | EACH  |                        |         | 1       |
| * 87100160   | FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 24F  | 1600           | FOOT  |                        |         | 1600    |
| * 87301215   | ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C   | 2834           | FOOT  |                        |         | 2834    |
| * 87301225   | ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C   | 1392           | FOOT  |                        |         | 1392    |
| * 87301245   | ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C   | 1392           | FOOT  |                        |         | 1392    |
| * 87301255   | ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C   | 1392           | FOOT  |                        |         | 1392    |
| * 87502500   | TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT.  | 4              | EACH  |                        |         | 4       |
| * 87600200   | PEDESTRIAN PUSH BUTTON, TYPE II  | 8              | EACH  |                        |         | 8       |
| * 87702860   | STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 26 FT.   | 2              | EACH  |                        |         | 2       |
| * 87702890   | STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 32 FT.   | 2              | EACH  |                        |         | 2       |
| * 87800100   | CONCRETE FOUNDATION, TYPE A  | 16             | FOOT  |                        |         | 16      |
| * 87800200   | CONCRETE FOUNDATION, TYPE D  | 4              | FOOT  |                        |         | 4       |
| * 87800415   | CONCRETE FOUNDATION, TYPE E, 36 INCH DIAMETER  | 60             | FOOT  |                        |         | 60      |
| * 88030020   | SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED  | 4              | EACH  |                        |         | 4       |
| * 88030050   | SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED   | 4              | EACH  |                        |         | 4       |
| * 88030100   | SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED   | 4              | EACH  |                        |         | 4       |
| * 88030110   | SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED  | 4              | EACH  |                        |         | 4       |
| * 88102740   | PEDESTRIAN SIGNAL HEAD, LED, 2-FACE BRACKET MOUNTED  | 8              | EACH  |                        |         | 8       |
| * 88200100   | TRAFFIC SIGNAL BACKPLATE   | 8              | EACH  |                        |         | 8       |
| * 88700200   | LIGHT DETECTOR   | 2              | EACH  |                        |         | 2       |
| * 88700300   | LIGHT DETECTOR AMPLIFIER   | 2              | EACH  |                        |         | 2       |
| * 89000100   | TEMPORARY TRAFFIC SIGNAL INSTALLATION  | 1              | EACH  |                        |         | 1       |
| * 89100300   | ILLUMINATED SIGN   | 4              | EACH  |                        |         | 4       |
| * ^ 89502375 | REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT   | 1              | EACH  |                        |         | 1       |
| * ^ 89502380 | REMOVE EXISTING HANDHOLE   | 5              | EACH  |                        |         | 5       |
| * ^ 89502385 | REMOVE EXISTING CONCRETE FOUNDATION  | 17             | EACH  |                        | 2       | 15      |
| * ^ X0323481 | VIDEO VEHICLE DETECTION, 4 CAMERAS   | 1              | EACH  |                        |         | 1       |
| * ^ X0322925 | ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1/C  | 1600           | FOOT  |                        |         | 1600    |
| * ^ X8730027 | ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C   | 1392           | FOOT  |                        |         | 1392    |
| * ^ X8730250 | ELECTRIC CABLE IN CONDUIT, NO. 20 3C, TWISTED, SHIELED   | 540            | FOOT  |                        |         | 540     |
| * ^ X8160112 | UNIT DUCT, WITH 2-1/C NO. 6 AND 1-1/C NO. 8 GROUND, 600 V(EPR-TYPE RHW) 1 1/4" DIA. POLYETHYLENE | 5521           | FOOT  |                        | 5521    |         |
| ^ XX003435   | PORTLAND CONCRETE CEMENT DRIVEWAY REMOVAL AND REPLACEMENT  | 17             | SQ YD | 17                     |         |         |
| * ^ XX003954 | REMOVE EXISTING LIGHT POLE AND FOUNDATION  | 9              | EACH  |                        | 9       |         |
| * ^ XX003552 | <i>Video Detection System</i>  | 1              | EACH  |                        |         | 1       |
| Δ Z0076600   | TRAINEES   | 500            | HOUR  | 500                    |         |         |
| * ^ XX007160 | ELECTRIC CABLE IN CONDUIT, NO. 20 6C, TWISTED, SHIELED, 3 PAIR                                   | 751            | FOOT  |                        |         | 751     |
| * ^ X0321760 | <i>DOUBLE HANDHOLE REMOVAL</i>   | 1              | EACH  |                        |         | 1       |
| ^ XX006806   | HOT-MIX ASPHALT DRIVEWAY REMOVAL & REPLACEMENT   | 39             | SQ YD | 39                     |         |         |
| ^ XX007161   | MANHOLE TO BE RECONSTRUCTED W/TYPE 1 FRAME AND LID   | 8              | EACH  | 8                      |         |         |
| ^ XX007162   | AGGREGATE SUB-BASE, 4"   | 818            | SQ YD | 818                    |         |         |
| * ^ XX006937 | GROUND ROD, 5/8" DIA. X 10 FT.   | 29             | EACH  |                        | 29      |         |

\* DENOTES SPECIALTY ITEM  
^ DENOTES SPECIAL PROVISION  
Δ Y080

VILLAGE OF DOWNERS GROVE  
PUBLIC WORKS ENGINEERING DIVISION  
5101 WALNUT AVENUE 60515 (630)434-5460

| REVISIONS |      | WOODWARD AVENUE IMPROVEMENTS SUMMARY OF QUANTITIES |                    |
|-----------|------|--|--------------------|
| NAME      | DATE | DATE: 2/02/07                                      | CHECKED BY: S.A.V. |
|           |      | SCALE: N.T.S.                                      | DRAWN BY: R.W.B.   |
|           |      | FILE NAME: C:\CADFILES\WOODWARD\SUMOFQUANT         |                    |