F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3573	07-00058-00-RS	DUPAGE	21	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 83975

SUMMARY OF QUANTITIES

	CODE NO	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY (1000)
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	100	100
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2307	2307
	40600300	AGGREGATE (PRIME COAT)	TON	45	45
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	380	380
	40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	54	54
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2593	2593
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	6344	6344
	42400800	DETECTABLE WARNINGS	SQ FT	262	262
	44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	23070	23070
	44000600	SIDEWALK REMOVAL	SQ FT	7018	7018
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3681	3681
	44002209	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/4"	SQ YD	427	427
	44201701	CLASS D PATCHES, TYPE I, 5 INCH	SQ YD	200	200
	44201705	CLASS D PATCHES, TYPE II, 5 INCH	SQ YD	200	200
	44201709	CLASS D PATCHES, TYPE III, 5 INCH	SQ YD	200	200
	44201711	CLASS D PATCHES, TYPE IV, 5 INCH	SQ YD	200	200
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1
	60300310	FRAMES AND LIDS TO BE ADJUSTED, SPECIAL	EACH	11	11
	67100100	MOBILIZATION	L SUM	1	1
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1188	1188
*	70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	97	97
*	70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	2729	2729
*	70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	2569	2569
*	70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	293	293
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	594	594
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	97	97
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	956	956
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1773	1773
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2685	2685
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	293	293
*	88600100	DETECTOR LOOP, TYPE I	FOOT	54	54

SUMMARY OF QUANTITIES

X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	35	35
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	969	969
XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	15	15
XX004238	BITUMINOUS DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	247	247
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	10	10
Z0017700	DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED	EACH	10	10
				0
				0
				0
				0

* INDICATES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

WOODRIDGE DRIVE

SUMMARY OF QUANTITIES

DRAWN BY: LLM

DATE: OCTOBER 12, 2007 CHECKED BY: JRP