

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1338	05-00083-00-FF	COOK	167	4

SUMMARY OF QUANTITIES				
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT M-8003(512)		

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A 07C (1) 07C (2)			Y030-1E L23 07C		Y031-1F L23	Y003 07C
				WISE RD / PLUM GROVE (PARTICIPATING)	WISE ROAD (NON-PARTICIPATING)	CUL-DE-SACS (NON-PARTICIPATING)	LIGHTING		TRAFFIC SIGNALS	LANDSCAPING
				70% FEDERAL 30% LOCAL	100% LOCAL	100% LOCAL	70% FEDERAL 30% LOCAL	100% LOCAL	70% FEDERAL 30% LOCAL	100% LOCAL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	136	136						
X 20101000	TEMPORARY FENCE	FOOT	6960	5240		1720				
* 20101100	TREE TRUNK PROTECTION	EACH	173	130		43				
* 20101200	TREE ROOT PRUNING	EACH	173	130		43				
* 20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	86	86						
* 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	44	44						
X 20200100	EARTH EXCAVATION	CU YD	11580	11580						
	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	5373	5373						
X 20400800	FURNISHED EXCAVATION	CU YD	1227	1227						
X 20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	5373	5373						
	TRENCH BACKFILL	CU YD	1560	1560						
	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	16120	16120						
X • 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	20675	18494		2181				
X • 21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	1305						1305	
X 21300010	EXPLORATION TRENCH, SPECIAL	FOOT	725	600		125				
• 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	244	217		27				
• 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	244	217		27				
• 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	244	217		27				
	MOWING	ACRE	4	4						
X • 25200110	SODDING, SALT TOLERANT	SQ YD	19613	17432		2181				
X * 25200200	SUPPLEMENTAL WATERING	UNIT	299	265		34				
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	383	383						
X 28000500	INLET AND PIPE PROTECTION	EACH	29	29						
	INLET FILTERS	EACH	154	146		8				
	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	4714	3977		737				
	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	24853	24428		425				
	AGGREGATE (PRIME COAT)	TON	72	68		4				
	LEVELING BINDER (MACHINE METHOD), N50	TON	476			476				
	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	195	123		72				
	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1011	655		356				
	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	583	583						
	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SQ YD	31374	31374						
	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	591	591						

* INDICATES SPECIALTY ITEMS
X INDICATES SPECIAL PROVISION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE 9/28/07
DRAWN BY DJK
CHECKED BY JRJ