

F.A.J.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1338	05-00083-00-FP	COOK	167	8
SUMMARY OF QUANTITIES				
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT	M-8003(512)	

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A			Y030-1E		Y031-1F	Y003
				WISE RD / PLUM GROVE (PARTICIPATING)	WISE ROAD (NON-PARTICIPATING)	CUL-DE-SACS (NON-PARTICIPATING)	LIGHTING		TRAFFIC SIGNALS	LANDSCAPING
				70% FEDERAL 30% LOCAL	100% LOCAL	100% LOCAL	70% FEDERAL 30% LOCAL	100% LOCAL	70% FEDERAL 30% LOCAL	100% LOCAL
	60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	6816	6816						
X	60605400 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)	FOOT	3725	3725						
	60605900 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	45	45						
	60608300 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	392	392						
X	60618400 CONCRETE MEDIAN, TYPE C-4	SQ FT	4201	4201						
	60622800 CONCRETE MEDIAN, TYPE SM-6.12	SQ FT	592	592						
	60624600 CORRUGATED MEDIAN	SQ FT	2672	2672						
	63200310 GUARDRAIL REMOVAL	FOOT	578	578						
	67000400 ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9						
	67100100 MOBILIZATION	L. SUM	1	1						
X	70101700 TRAFFIC CONTROL AND PROTECTION	L. SUM	1	1						
X	70101900 TRAFFIC CONTROL AND PROTECTION (DETOUR 1)	L. SUM	1	1						
X	70102000 TRAFFIC CONTROL AND PROTECTION (DETOUR 2)	L. SUM	1	1						
	70106800 CHANGEABLE MESSAGE SIGN	CAL MO	6	6						
	70300100 SHORT-TERM PAVEMENT MARKING	FOOT	411	411						
	70300510 PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	73	73						
	70300520 PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1038	1038						
	70300610 TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	582	582						
	70300625 TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	29709	29709						
	70300635 TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	2848	2848						
	70300645 TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	687	687						
	70300660 TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	781	781						
	70301000 WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	830	830						
*	78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	364	364						
*	78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17490	17490						
*	78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2285	2285						
*	78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	559	559						
*	78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	355	355						
*	78001100 PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	153	153						
*	78001110 PAINT PAVEMENT MARKING - LINE 4"	FOOT	1983	1983						
*	78001130 PAINT PAVEMENT MARKING - LINE 6"	FOOT	930	930						
*	78001150 PAINT PAVEMENT MARKING - LINE 12"	FOOT	395	395						
*	78001180 PAINT PAVEMENT MARKING - LINE 24"	FOOT	107	107						

* INDICATES SPECIALTY ITEMS
X INDICATES SPECIAL PROVISION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE 9/28/07
DRAWN BY DJK
CHECKED BY JRV