

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1338	05-00083-00-FP	COOK	167	10

SUMMARY OF QUANTITIES
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT M-8003(512)

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A			Y030-1E		Y031-1F	Y003
				WISE RD / PLUM GROVE (PARTICIPATING)	WISE ROAD (NON-PARTICIPATING)	CUL-DE-SACS (NON-PARTICIPATING)	LIGHTING		TRAFFIC SIGNALS	LANDSCAPING
							70% FEDERAL 30% LOCAL	100% LOCAL		
X • 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1						1	
X • 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	759						759	
X • 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1139						1139	
X • 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1184						1184	
X • 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2337						2337	
X • 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3427						3427	
X • 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	59						59	
X • 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4						4	
X • 87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1						1	
X • 87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	3						3	
X • 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16						16	
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4						4	
X • 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	60						60	
• 87900200	DRILL EXISTING HANDHOLE	EACH	1						1	
X • 88030020	SIGNAL HEAD, L.E.D., 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	3						3	
X • 88030110	SIGNAL HEAD, L.E.D., 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	5						5	
X * 88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1						1	
X • 88030240	SIGNAL HEAD, L.E.D., 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	3						3	
X • 88102710	PEDESTRIAN SIGNAL HEAD, L.E.D., 1-FACE, BRACKET MOUNTED	EACH	4						4	
• 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	8						8	
• 88500100	INDUCTIVE LOOP DETECTOR	EACH	10						10	
X • 88600100	DETECTOR LOOP, TYPE 1	FOOT	1038						1038	
X • 88700200	LIGHT DETECTOR	EACH	2						2	
X • 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1						1	
X • 88800100	PEDESTRIAN PUSH-BUTTON	EACH	4						4	
X • 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1						1	
• 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	21586				21586			
X • 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1						1	
X • 89502380	REMOVE EXISTING HANDHOLE	EACH	10						10	
X • 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9						9	
X	Z0001050 AGGREGATE SUBGRADE 12"	SQ YD	1204	1204						
	Z0013798 CONSTRUCTION LAYOUT	L SUM	1	1						
X	Z0015200 CURB STOPS 1 1/2"	EACH	11							11
X	Z0022800 FENCE REMOVAL	FOOT	116	116						

* INDICATES SPECIALTY ITEMS
X INDICATES SPECIAL PROVISION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE 9/28/07
DRAWN BY DJK
CHECKED BY JRV