

| | | | | |
|-----------------------|----------------|------------------|--------------|-----------|
| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 1338 | 05-00083-00-FP | COOK | 167 | 11 |
| SUMMARY OF QUANTITIES | | | | |
| FED. ROAD DIST. NO. 7 | ILLINOIS | FED. AID PROJECT | M-8003(512) | |

| CODED PAY ITEM NO. | ITEM DESCRIPTION | UNIT | TOTAL QUANTITY | 1000-2A | | | Y030-1E | | Y031-1F | Y003 |
|--------------------|---|-------|----------------|--------------------------------------|-------------------------------|---------------------------------|--------------------------|------------|--------------------------|-------------|
| | | | | WISE RD / PLUM GROVE (PARTICIPATING) | WISE ROAD (NON-PARTICIPATING) | CUL-DE-SACS (NON-PARTICIPATING) | LIGHTING | | TRAFFIC SIGNALS | LANDSCAPING |
| | | | | 70% FEDERAL 30% LOCAL | 100% LOCAL | 100% LOCAL | 70% FEDERAL 30% LOCAL | 100% LOCAL | 70% FEDERAL 30% LOCAL | 100% LOCAL |
| X * | Z0056900 SANITARY SEWER 8" | FOOT | 18 | | 18 | | | | | |
| X * | Z0057000 SANITARY SEWER 10" | FOOT | 50 | | 50 | | | | | |
| X Δ | Z0076600 TRAINEES | HOURS | 2000 | 2000 | | | | | | |
| X * | A2002924 TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 3" CALIPER, BALLED AND BURLAPPED | EACH | 4 | | | | | | 4 | |
| X * | A2004820 TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 2-1/2" CALIPER, BALLED AND BURLAPPED | EACH | 4 | | | | | | 4 | |
| X * | C2007224 SHRUB, ROSA KNOCKOUT (KNOCKOUT ROSE), 24" HEIGHT, CONTAINER | EACH | 67 | | | | | | 67 | |
| X * | C2007924 SHRUB, ROSA MEIPITAC (CAREFREE WONDER ROSE), 24" HEIGHT, CONTAINER | EACH | 69 | | | | | | 69 | |
| X * | C2011936 SHRUB, VIBURNUM DENTATUM RALPH SENIOR (AUTUMN JAZZ ARROWWOOD VIBURNUM), 3' HEIGHT, BALLED AND BURLAPPED | EACH | 4 | | | | | | 4 | |
| X * | D2000624 EVERGREEN, JUNIPERUS CHINENSIS SEA GREEN (SEA GREEN JUNIPER), 2' WIDTH, CONTAINER | EACH | 12 | | | | | | 12 | |
| X * | E2015065 VINE-HYDRANGEA ANOMALA SUBSP. PETIOLARIS (CLIMBING HYDRANGEA), 5-GALLON POT | EACH | 18 | | | | | | 18 | |
| X * | K1005481 SHREDDED BARK MULCH 3" | SQ YD | 1305 | | | | | | 1305 | |
| X | XX000613 MODULAR BLOCK RETAINING WALL | SQ FT | 540 | | | | | | 540 | |
| X * | XX000810 CONCRETE PAVERS | SQ FT | 9683 | | | | | | 9683 | |
| X | XX000882 WOOD FENCE | FOOT | 106 | 106 | | | | | | |
| X * | XX000959 TRASH RECEPTACLES | EACH | 8 | | | | | | 8 | |
| X * | XX001249 ORNAMENTAL FENCE | FOOT | 109 | | | | | | 109 | |
| X | XX002029 SANITARY SEWER REMOVAL, 8" | FOOT | 18 | | 18 | | | | | |
| X * | XX002136 PRESSURE CONNECTION | EACH | 19 | | 19 | | | | | |
| X * | XX003848 GYPSUM PLACEMENT | POUND | 3524 | | | | | | 3524 | |
| X | XX004801 BITUMINOUS BIKE PATH REMOVAL | SQ YD | 44 | 44 | | | | | | |
| X * | XX007217 PAVER BLOCKS, SPECIAL | SQ FT | 90 | | | | | | 90 | |
| X * | XX004911 SIGN PANEL - TYPE AZ REFLECTORIZED SHEETING | SQ FT | 30 | | | | | 30 | | |
| X * | XX005166 SHRUB, HYDRANGEA ARBORESCENS ANNABELLE (ANNABELLE SMOOTH HYDRANGEA), 2' HEIGHT CONTAINER | EACH | 1 | | | | | | 1 | |
| X * | XX005167 SHRUB, RIBES ALPINUM GREEN MOUND (GREEN MOUND ALPINE CURRANT), 24" WIDTH, CONTAINER | EACH | 88 | | | | | | 88 | |
| X * | XX005283 BRICK PAVER CROSSWALK | SQ FT | 1255 | | | | | | 1255 | |
| X | XX005656 INLET FILTER CLEANING | EACH | 308 | 292 | | 16 | | | | |
| X * | XX005962 BENCH | EACH | 4 | | | | | | 4 | |
| X * | XX005995 SHRUB, CLETHRA ALNIFOLIA (SUMMER SWEET), 5 GALLON | EACH | 12 | | | | | | 12 | |
| X * | XX006159 MEDIAN SOIL FURNISH AND PLACE | CU YD | 598 | 598 | | | | | | |
| X | XX006642 STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 2, 15" | FOOT | 20 | 20 | | | | | | |
| X * | XX011700 WATER MAIN FITTINGS | POUND | 2000 | | 2000 | | | | | |
| X * | X0301407 PERENNIAL PLANTS, GALLON POT | UNIT | 2540 | | | | | | 2540 | |
| X | X0301766 DRILL AND GROUT #6 TIE BARS | EACH | 825 | 825 | | | | | | |

* INDICATES SPECIALTY ITEMS
 X INDICATES SPECIAL PROVISION
 Δ Y080

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 DRAWN BY DJK
 CHECKED BY JRV
 DATE 9/28/07