

SUMMARY OF QUANTITIES				
CODE	PAY ITEM	UNIT	TOTAL QUANTITY	1000-2A 80% FEDERAL 20% LOCAL
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CUYD	100	100
20800150	TRENCH BACKFILL	CUYD	825	825
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQYD	700	700
21101610	TOPSOIL FURNISH AND PLACE, 3"	SQYD	5,850	5,850
25200100	SODDING	SQYD	5,850	5,850
25200200	SUPPLEMENTAL WATERING	UNIT	45	45
28000510	INLET FILTERS	EACH	60	60
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQYD	700	700
35300300	PORTLAND CEMENT CONCRETE BASE COURSE, 8"	SQYD	1,230	1,230
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	2,200	2,200
40600300	AGGREGATE (PRIME COAT)	TON	45	45
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1,350	1,350
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	175	175
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2,025	2,025
42101300	PROTECTIVE COAT	SQYD	7,175	7,175
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQYD	2,700	2,700
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQFT	12,750	12,750
42400800	DETECTABLE WARNINGS	SQFT	1,100	1,100
44000100	PAVEMENT REMOVAL	SQYD	1,400	1,400
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQYD	14,250	14,250
44000200	DRIVEWAY PAVEMENT REMOVAL	SQYD	2,700	2,700
44000600	SIDEWALK REMOVAL	SQFT	12,750	12,750
44001900	COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)	FOOT	13,775	13,775
60213800	RESTRICTED DEPTH CATCH BASINS, 4' DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	39	39
60224600	RESTRICTED DEPTH MANHOLES, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	13	13
60250200	CATCH BASINS TO BE ADJUSTED	EACH	9	9
60255500	MANHOLES TO BE ADJUSTED	EACH	13	13
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	24	24
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	3	3
60406500	FRAMES AND LIDS, SPECIAL	EACH	30	30
60500050	REMOVING CATCH BASINS	EACH	6	6
67100100	MOBILIZATION	LUSM	1	1

* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES				
CODE	PAY ITEM	UNIT	TOTAL QUANTITY	1000-2A 80% FEDERAL 20% LOCAL
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,842	2,842
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	375	375
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	60	60
X0325207	TELEVISION INSPECTION OF SEWER	FOOT	2,900	2,900
X4420132	CLASS D PATCHES (SPECIAL)	SQYD	5,820	5,820
XX001286	SPECIAL EXCAVATION	CUYD	300	300
XX003036	STORM SEWERS, PVC, SDR 26, 10 INCH	FOOT	1,255	1,255
XX004208	SEWER SERVICE LATERAL REPAIR, 6" POLYVINYL CHLORIDE	FOOT	200	200
XX005565	REMOVE AND RESET BRICK PAVERS	SQFT	150	150
XX005634	12" X 6" PVC SEWER SERVICE CONNECTIONS	EACH	20	20
XX005770	STRUCTURE TO BE ABANDONED	EACH	12	12
XX006452	15" X 6" PVC SEWER SERVICE CONNECTIONS	EACH	10	10
XX006464	DOMESTIC WATER SERVICE BOX TO BE ADJUSTED (SPECIAL)	EACH	10	10
Z0018900	DRILL AND GROUT DOWEL BARS	EACH	685	685
Δ Z0076600	TRAINEES	HOUR	500	500
XX005689	STORM SEWERS, DIP CLASS 52, 10"	FOOT	50	50
XX007154	18" X 6" SEWER SERVICE CONNECTIONS	EACH	3	3
XX007155	27" X 6" SEWER SERVICE CONENCTIONS	EACH	13	13
XX007156	12" DIAMETER, PVC STORM SEWER PIPE REPLACEMENT (POINT REPAIR)	FOOT	375	375
XX007157	15" DIAMETER, PVC STORM SEWER PIPE REPLACEMENT (POINT REPAIR)	FOOT	60	60
XX007158	18" DIAMETER, PVC STORM SEWER PIPE REPLACEMENT (POINT REPAIR)	FOOT	70	70
XX007159	27" DIA. RCP, C-76 W/C-443 JOINTS, CLASS III, STORM SEWER (POINT REPAIR)	FOOT	300	300
XX000671	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-4.12	FOOT	13,775	13,775

* DENOTES SPECIALTY ITEM

Δ Y080

Drawing file: W:\Projects\03206305 - High Priority Project Bristol & Dover\Summary of quantities.dwg Oct. 03, 2007 - 11:13am

	◆ Civil Engineers	9933 Roosevelt Road
	◆ Municipal Consultants	Westchester, Illinois 60154-2780
	◆ Established 1911	Phone: 708/865-0300
		Fax: 708/865-1212

HIGH PRIORITY PROJECT HPP-2902 (002)
BRISTOL AVENUE & DOVER STREET
VILLAGE OF WESTCHESTER, ILLINOIS

SUMMARY OF QUANTITIES

SCALE:	NONE	SHEET 4 OF 22
DRAWN BY:	ECW/LEV	
BOOK NO.:	1541	
DATE:	10-2-07	
REVISION:	E.H.E. NO.: 838-06-38501	