CONTRACT NO. 83985

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1512	05-00093-00-WR	DUPAGE	72	5
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS FED. AID PROJECT			

PROJECT NO.: M-8003 (699)

SUMMARY OF QUANTITIES

SP	CODED PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	TOTAL QUANTITY	ROADWAY IQQQ-2A PARTICIPATING	HIGHWAY LIGHTING YQ30-1E NON-PARTICIPATING
	60500060	REMOVING INLETS	EACH	2	2	-
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2,373	2,373	-
	63200310	GUARDRAIL REMOVAL	FOOT	14	14	-
	67100100	MOBILIZATION	L SUM	1	1	-
△	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1	-
△	70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1	-
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1,000	1,000	-
	72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	42	42	-
	72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	12	12	-
	72900100	METAL POST - TYPE A	FOOT	22	22	-
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	37	37	-
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,392	2,392	-
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	423	423	-
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	23	23	-
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	388	388	-
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	-	1
* △	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	-	1
*	81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	904	-	904
*	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	60	-	60
*	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	210	-	210
*	81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	1204	-	1,204
*	81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	60	-	60
*	81702410	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 4	FOOT	1204	-	1,204
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	874	-	874
*	82102150	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 150 WATT	EACH	14	-	14
*	83007300	LIGHT POLE, ALUMINUM, 35 FT. M.H., 8 FT. MAST ARM	EACH	11	-	11
*	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	149	-	149
* △	84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	6	-	6
*	88600100	DETECTOR LOOP, TYPE I	FOOT	156	156	-
*	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	195	-	195
*	B2001124	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 3" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	6	6	-
*	B2004120	TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	6	6	-
*	B2006220	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5	5	-
*	B2010016	TREE, AMELANCHIER CANADENSIS (SHADBLOW SERVICEBERRY), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5	5	-
* △	X0321478	MAINTENANCE OF EXISTING LIGHTING SYSTEM COMPLETE	L SUM	1	-	1
* △	X0323682	BARE COPPER WIRE, NO. 2/0	FOOT	45	-	45
* △	X0324637	BASE COVER, LIGHT POLE	EACH	11	-	11
* △	X8250400	LIGHTING CONTROLLER PEDESTAL MOUNT	EACH	1	-	1
* △	X8380090	BREAKAWAY DEVICE, COUPLING	EACH	44	-	44
* △	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	60	-	60
△	XX000610	RELOCATE EXISTING MAILBOX	EACH	12	12	-
△	XX000882	WOOD FENCE	FOOT	49	49	-
△	XX004904	BITUMINOUS DRIVEWAY PAVEMENT, 10"	SQ YD	742	742	-
△	Z0001050	AGGREGATE SUBGRADE, 12"	SQ YD	4,583	4,583	-
* △	X0329863	INTERCEPT EXISTING CONDUIT	EACH	6	-	6
* △	XX007163	INTERCEPT EXISTING CONDUIT FOR LIGHTING CONTROLLER	EACH	1	-	1
* △	XX000986	REMOVAL OF EXISTING LUMINAIRE, SALVAGE	EACH	3	-	3

* INDICATES SPECIALTY ITEM
△ INDICATES SPECIAL PROVISION

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

VILLAGE OF WESTMONT
59TH STREET RECONSTRUCTION

SUMMARY OF QUANTITIES
SHEET 2 OF 2

SCALE: N.T.S. DRAWN BY: JMT
DATE: 09/21/07 CHECKED BY: AJB

PLAN: SURVEYED / PLOTTED / ALIGNMENT CHECKED / TIES OF R/W CHECKED / ROD FILE NAME / NOTE BOOK NO. / BY / DATE

PROFILE: SURVEYED / PLOTTED / GRADES CHECKED / B.M. NOTED / STRUCTURE NOTATIONS CHKD / NOTE BOOK NO. / BY / DATE

PLOT DATE = $DATE$
FILE NAME = $FILL$
PLOT SCALE = $SCALE$
PLOT SPACE = $SPACE$
USER NAME = $USER$