CONTRACT NO. 83985

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1512	05-00093-00-WR	DUPAGE	72	35
STA.		TO STA.		
FED. ROAD DIST. NO. 1 ILLINOIS		FED. AID PROJECT		

PROJECT NO.: M-8003 (699)

DRAINAGE STRUCTURE TABLE

STR NO.	STA	O/S	MH	CB	INL	DIA (FEET)	FRAME	TOP OF GRATE	N. Inv.	E. Inv.	S. Inv.	W. Inv.	Other Inv.	SHEET NO.
1	109+84.45	-21.61	A	--	--	6	1	736.43	729.2	--	--	729.26	--	3
2	109+22.00	-21.58	A	--	--	5	1	736.31	--	729.87	730.4	729.87	--	2
3	107+56.00	-21.58	A	--	--	5	1	738.25	--	732.12	732.5	732.4	--	2
4	106+21.00	-21.58	A	--	--	5	1	740.3	--	733.75	733.9	733.9	--	2
5	103+95.00	-21.58	A	--	--	4	1	742.69	--	736.13	736.3	736.3	--	1
6	101+38.50	-21.58	A *	--	--	4	1	742.54	--	738.05	738.2	--	--	1
7	101+37.00	-17.00	--	A *	--	4	3	742.22	738.25	--	738.4	--	--	1
8	101+37.00	17.00	--	A *	--	4	3	742.22	738.74	--	--	--	--	1
9	103+95.00	-17.00	--	A	--	4	3	742.4	736.33	--	736.5	--	--	1
10	103+95.00	17.00	--	A *	--	4	3	742.4	736.84	--	738.02	--	--	1
11	106+21.00	-17.00	--	A	--	4	3	740.04	733.95	--	734.3	--	--	2
12	106+21.00	17.00	--	A	--	4	3	740.04	--	--	734.81	--	--	2
13	107+56.00	-17.00	--	A	--	4	3	738.05	732.53	--	732.6	--	--	2
14	107+56.00	17.00	--	A	--	4	3	738.05	732.77	--	--	--	--	2
15	109+22.00	-17.00	--	A	--	4	3	736.10	730.43	--	730.6	--	--	2
16	109+22.00	17.00	A	--	--	6	two 3, special	736.10	--	--	730.94	--	--	2

STORM SEWER TABLE

NO.	U/S STA.	CLASS AND TYPE	D/S STA.	DIA (Inches)	LENGTH (feet)	SHEET NO.	UPSTREAM ELEV	DOWNSTREAM ELEV	SLOPE (FT/FT)	TRENCH BACKFILL (CY)
1	109+22.00	C III, T-2	109+84.45	27	63	3	729.87	729.26	0.01	76.49
2	107+56.00	C III, T-2	109+22.00	27	166	2	732.12	729.87	0.014	201.54
3	106+21.00	C IV, T-1	107+56.00	24	135	2	733.75	732.4	0.01	159.30
4	103+95.00	C IV, T-1	106+21.00	18	226	2	736.13	733.9	0.01	248.93
5	101+38.50	C IV, T-1	103+95.00	12	256.5	1	738.05	736.3	0.0068	201.94
6	101+37.00	C IV, T-1	101+38.50	12	4.8	1	738.25	738.05	0.0069	3.06
7	101+37.00	C IV, T-1	101+37.00	12	34	1	738.74	738.4	0.01	19.16
8	103+95.00	C IV, T-1	103+95.00	12	4.6	1	736.33	736.3	0.0065	4.30
9	103+95.00	C IV, T-1	103+95.00	12	34	1	736.84	736.5	0.01	29.23
10	106+21.00	C IV, T-1	106+21.00	12	4.6	2	733.95	733.9	0.01	4.30
11	106+21.00	C IV, T-1	106+21.00	12	34	2	734.81	734.5	0.009	26.72
12	107+56.00	C IV, T-1	107+56.00	24	4.6	2	732.53	732.5	0.0065	4.48
13	107+56.00	C IV, T-1	107+56.00	18	34	2	732.77	732.6	0.005	28.95
14	109+22.00	C IV, T-1	109+22.00	18	4.6	2	730.43	730.4	0.0065	4.30
15	109+22.00	C IV, T-1	109+22.00	18	34	2	730.94	730.6	0.01	28.95
16	103+95.00	C IV, T-1	103+95.00	12	10	1	738.12	738.02	0.01	7.86

PLAN
NOTE BOOK NO. ____
SURVEYED ____
PLOTTED ____
ALIGNMENT CHECKED ____
RT OF WAY STAKED ____
CADD FILE NAME ____
BY
DATE

PROFILE
NOTE BOOK NO. ____
SURVEYED ____
PLOTTED ____
GRADES CHECKED ____
STRUCTURE NOTATIONS CHKD ____
BY
DATE

PLOT DATE = $DATE$
FILE NAME = $FILE$
PLOT SCALE = $SCALE$
PLOT UNITS = $UNITS$
USER NAME = $USER$

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

VILLAGE OF WESTMONT
59TH STREET RECONSTRUCTION

DRAINAGE SCHEDULES
SHEET 1 OF 1

SCALE: N.T.S. DRAWN BY: DEB
DATE: 09/21/07 CHECKED BY: AJB