CONTRACT NO. 83986

F.A.U RTE.	SECTION	COUNTY	TOTAL	SHEET NO.
2993	05-00094-00-WR	DUPAGE	67	7
STA.	-	TO STA.		
FED. RO	DAD DIST. NO. 1 ILLIN	OIS FED. AID	PROJECT	

TREE REMOVAL SCHEDULE 6 TO 15 UNITS DIAMETER

TREE	<u>RE</u>	<u>MOVAL</u>	SCHEDUL	E
OVER	15	UNITS	DIAMETE	F

	2333 03-00034-00-MK	DUFAGE 01 1
	STA. TO	STA.
	FED. ROAD DIST, NO. 1 ILLINOIS	FED. AID PROJECT
:	PROJECT NO.: M-8003 (70	271

STATION	OFFSET	UNITS
109+92.69	37.33′ LT	12
110+32.37	38.83′ LT	10
110+61.69	35.70′ LT	6
111+39.66	35.39′ LT	6
111+72.58	38.08' LT	10
112+18.01	38.10′ LT	12
113+69.54	38.78′ LT	12
105+50.14	33.76′ RT	6
106+48.44	32.90′ RT	6
107+79.18	23.45′ RT	9
117+77.60	31.90' RT	10
117+90.24	31.87′ RT	10
118+42.99	34.83' RT	12

STATION | OFFSET | UNITS 118+60.60 35.80' RT 18

STATION	OFFSET	SPECIES*
109+23.10	31.19' LT	Α
109+95.30	31.19' LT	В
110+45.30	31.19′ LT	С
110+95.30	31.19' LT	D
111+45.30	31.19' LT	Α
111+95.30	31.19' LT	В
105+87.14	30.78′ RT	С
106+37,14	30.78′ RT	D
106+87.14	30.78′ RT	Α
107+37.14	30,78' RT	В
107+87.14	30.78' RT	С
108+37.14	30.78' RT	D
108+87.14	30.78' RT	A
109+87.14	30.78' RT	В
110+37.14	30.78' RT	С
110+87,14	30.78' RT	D
111+37.14	30.78' RT	Α
111+87.14	30.78' RT	В

PROPOSED TREE SCHEDULE

*THE FOLLOWING TREE SPECIES SHALL BE USED:

A: TREE, CERCIS CANADENSIS (EASTERN REDBUD), 3" CALIPER, TREE FORM, BALLED AND BURLAPPED

B: TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED

C: TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED

D: TREE, AMELANCHIER CANADENSIS (SHADBLOW SERVICEBERRY), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED

ILLINOIS DEPARTMENT OF TRANSPORTATION VILLAGE OF WESTMONT WILLIAMS STREET RECONSTRUCTION TREE SCHEDULE SCALE: N.T.S. DRAWN BY: JAL CHECKED BY: AJB

BY						
					CH/KD	
			CKED	1	NOTATINS	
	SURVEYED	PLOTTED	GRADES CH	B.M. NOTED	STRUCTURE	
	OF LE		TE BOOK			_
1	Ţ		2	2	ġ	